APR 3 1982

TD 230:82/005

Report No. FHWA/RD-82/005

OPTIMIZED SECTIONS FOR MAJOR PRESTRESSED CONCRETE BRIDGE GIRDERS

COMPLETED
195

February 1982
Final Report



Prepared for

U.S. Department of Transportation
Federal Highway Administration

Offices of Research & Development
Structures and Applied Mechanics Division
Washington, D.C. 20590

Document is available to the U.S. public through the National Technical Information Service Springfield, Virginia 22161

I

FOREWORD

This report presents the results of an analytical investigation of standard prestressed concrete bridge girder designs and makes recommendations regarding new national standards. The report will be of interest to engineers involved in the design, analysis and construction of highway bridges.

The research documented in this report was done as part of the Federal Highway Administration FCP Program. Results are being integrated into FCP Project 5K entitled "New Bridge Design Concepts." Mr. Craig A. Ballinger is the project manager and Mr. Thomas Krylowski is the task manager.

Sufficient copies of the report are being distributed to provide a minimum of one copy to each regional office, one copy to each division office, and two copies to each State highway department. Direct distribution is being made to the division offices.

Charles F. Scheffey
Director, Office of Research
Federal Highway Administration

NOTICE

This document is disseminated under the sponsorship of the Department of Transportation in the interest of information exchange. The United States Government assumes no liability for its contents or use thereof. The contents of this report reflect the views of the contractor, who is responsible for the accuracy of the data presented herein. The contents do not necessarily reflect the official policy of the Department of Transportation. This report does not constitute a standard, specification, or regulation.

The United States Government does not endorse products or manufacturers. Trade or manufacturers' names appear herein only because they are considered essential to the object of this document.

Technical Report Documentation Page

1. Report No.	2. Government Accession No.	3. Recipient's Catalog No.
FHWA/RD-82/005		

4. Title and Subtitle	5. Report Date
Optimized Sections for Major Prestressed Concrete Bridge Girders	February 1982
	6. Performing Organization Code CR4475/4321
7. Author(s) B. G. Rabbat, T. Takayanagi, and H. G. Russell	8. Performing Organization Report No.
9. Performing Organization Name and Address Construction Technology Laboratories A Division of the Portland Cement Association 5420 Old Orchard Road Skokie, Illinois 60077	10. Work Unit No. (TRAIS) FCP 35K2-012
	11. Contract or Grant No. DOT FH-11-9598
12. Sponsoring Agency Name and Address Office of Research Federal Highway Administration Washington, D. C. 20590	13. Type of Report and Period Covered Final Report June 1979 - July 1981
	14. Sponsoring Agency Code

15. Supplementary Notes

FHWA Contract Manager, Mr. Thomas Krylowski (HRS-11)

16. Abstract

The objectives of this investigation were to evaluate the latest prestressed concrete bridge girder designs being used in the United States and to determine which represent optimum designs that could be promoted as national or regional standards. Bridges built with pretensioned I- and T-sections for spans in excess of 80 ft (24.4 m) and concrete compressive strengths up to 7000 psi (48.3 MPa) were considered.

Information on current designs was collected from selected highway agencies and producers throughout the United States. In all states surveyed except California, the most economical bridges for spans of 70 to 130 ft (21.3 to 39.6 m) were constructed with pretensioned bridge girders. Precast prestressed bridge girder sections inventoried were analyzed on three efficiency scales. Bulb-T's, Colorado, and Washington girders were more structurally efficient than AASHTO-PCI girders.

A computer program called "BRIDGE" was developed to perform cost analyses. Parameters included girder span, girder spacing, deck thickness and concrete compressive strength. Based on relative unit costs for in-place materials and labor, cost charts were prepared for existing Bulb-T's, Colorado, Washington and AASHTO girders, and for their modified counterparts with 6-in. (152 mm) thick webs. All girders were compared using optimum cost curves. Bulb-T's were found most cost-effective with estimated cost savings of 17% on the in-place cost of girders and deck compared to the AASHTO girders. Next most cost-effective sections were the Washington Series girders.

Modified Bulb-T's are recommended for use as national standards.

17. Key Words	18. Distribution Statement
Beams (supports), Bridges(Structures), Costs, Girders, Long span, Precast concrete, Prestressed concrete, Sturctural analysis, Structural design.	No restrictions. This document is available through the National Technical Information Service, Springfield, Virginia 22161

19. Security Classif. (of this report)	20. Security Classif. (of this page)	21. No. of Pages	22. Price
Unclassified	Unclassified	178	

Form DOT F 1700.7 (8-72) Reproduction of completed page authorized

TABLE OF CONTENTS

	Page No.
INTRODUCTION	1
Background	1
Objectives	3
Scope	3
Findings	3
RESEARCH APPROACH	4
Phase I - Evaluation of Current Designs	4
Phase II - Structural Efficiency and Cost Effectiveness	5
PHASE I - SURVEY RESULTS	5
Design, Fabrication, and Construction Details	6
Transportation Requirements and Restrictions	20
Availability and Costs	21
Structural Durability	22
Aesthetics and Safety	22
Opinions and Policies	23
Special Concepts	24
PHASE II - STRUCTURAL EFFICIENCY	26
PHASE II - COST EFFECTIVENESS	32
Cross Sections Analyzed	33
Structural Parameters	43
Development of Computer Program	43
Optimum Cost Index Charts	46
Cost Effectiveness Comparisons	52
SI CONVERSION	76
CONCLUSIONS	76
RECOMMENDATIONS	78
IMPLEMENTATION	79
REFERENCES	81
APPENDIX A - SURVEY PARTICIPANTS	84
APPENDIX B - SURVEY OUTLINE	85
APPENDIX C - GIRDER PROPERTIES	90
APPENDIX D - COST DATA	105

	Page No.
APPENDIX E - COMPUTER PROGRAM "BRIDGE"	109
Program Documentation	109
Source Listing	128
Sample Problems	141
APPENDIX F - COST INDEX CHARTS	149

LIST OF FIGURES

Figure		Page No.
1.	Girder Cross Sections	7
2.	Stirrup Schemes	18
3.	Relationship Between Modulus of Section for Bottom Fibers and Cross-Sectional Area	27
4.	Variation of Efficiency Factor with Depth of Section	29
5.	Variation of Efficiency Ratio with Depth of Section	30
6.	Existing Girders Analyzed	35
7.	Modified Girders Analyzed	37
8.	Relationship Between Modulus of Section for Bottom Fibers and Cross-Sectional Area for Washington Series and Bulb-T's	40
9.	Variation of Efficiency Factor with Depth of Section for Washington Series and Bulb-T's	41
10.	Variation of Efficiency Ratio with Depth of Section for Washington Series and Bulb-T's	42
11.	Required Number of Strands in AASHTO Type VI Girder	47
12.	Required Number of Strands in Washington Series 14 Girder	48
13.	Variation of Maximum Span with Girder Spacing	49
14.	Cost Chart for AASHTO Type VI Girder	50
15.	Optimum Cost Curves for AASHTO Girders	53
16.	Optimum Cost Curves for Modified AASHTO Girders	54
17.	Optimum Cost Curves for Colorado Girders and Modified G68/6 Girder	55
18.	Optimum Cost Curves for Washington Series	57
19.	Comparison of Optimum Cost Curves for Washington and Modified Washington Series	58
20.	Optimum Cost Curves for Anderson's Bulb-T's	60
21.	Comparison of Optimum Cost Curves for Bulb-T's and Modified Bulb-T's	61

Figure		Page No.
22.	Comparison of Optimum Cost Curves for AASHTO Type VI, Colorado G68, Washington Series 14, and Bulb-T BT72 Girders	63
23.	Comparison of Optimum Cost Curves for AASHTO Type VI and Modified G68/6, Series 14/6, and BT72/6 Girders	64
24.	Comparison of Optimum Cost Curves for Modified Bulb-T's and Modified Washington Series	66
25.	Comparison of Optimum Cost Curves for Modified Bulb-T's and AASHTO Girders	68
26.	Variation of Optimum Cost Curves with Concrete Compressive Strength for AASHTO Type IV Girder	69
27.	Variation of Optimum Cost Curves with Concrete Compressive Strength for AASHTO Type VI Girder	70
28.	Effect of Strands Bundling on Optimum Cost Curves for Colorado G54 Girders	72
29.	Effect of Strands Bundling on Optimum Cost Curves for AASHTO Type VI Girder	73
30.	Nomenclature for Cross-Sectional Dimensions Shown in Tables 3 and 4	91
31.	Dimensions Defining Girder Cross-Section for Computer Input	112
32.	Assumed Stress-Strain Characteristics of Strands	115
33.	Effective Slab Span	117
34.	Strands Locations	121
35.	Cost Chart for AASHTO Type IV Girder	150
36.	Cost Chart for AASHTO Type V Girder	151
37.	Cost Chart for AASHTO Type VI Girder	152
38.	Cost Chart for Modified Type IV Girder	153
39.	Cost Chart for Modified Type V Girder	154
40.	Cost Chart for Modified Type VI Girder	155
41.	Cost Chart for Colorado G54 Girder	156
42.	Cost Chart for Colorado G68 Girder	157
43.	Cost Chart for Modified G68/6 Girder	158
44.	Cost Chart for Washington Series 80	159

Figure		Page No.
45.	Cost Chart for Washington Series 100	160
46.	Cost Chart for Washington Series 120	161
47.	Cost Chart for Washington Series 14	162
48.	Cost Chart for Modified Series 80/6	163
49.	Cost Chart for Modified Series 100/6	164
50.	Cost Chart for Modified Series 120/6	165
51.	Cost Chart for Modified Series 14/6	166
52.	Cost Chart for BT48	167
53.	Cost Chart for BT60	168
54.	Cost Chart for BT72	169
55.	Cost Chart for Modified BT48/6	170
56.	Cost Chart for Modified BT60/6	171
57.	Cost Chart for Modified BT72/6	172

OPTIMIZED SECTIONS FOR MAJOR PRESTRESSED CONCRETE BRIDGE GIRDERS

INTRODUCTION

Background

The concept of prestressed concrete can be traced back to early 19th Century.[1]* Modern development of prestressed concrete is credited to E. Freyssinet of France, who, in 1928, started using high strength steel wires for prestressing. Early application in the United States tended to be concentrated in the area of circular prestressed structures, especially as applied to storage tanks.

Linear prestressing did not start in the United States until 1949 when the famous Walnut Lane Bridge was constructed in Philadelphia. Following this initial effort, application of prestressing in the transportation industry grew rapidly. Annual reports of Bureau of Public Roads for each of fiscal years 1954 through 1957 reported that "Use of prestressed concrete in bridge construction continued to grow in favor because in many situations it permits large savings in materials and cost."[2]

In early applications of prestressed concrete to bridges, designers developed their own ideas of the "best" girder sections. The result was that each contractor used a slightly different girder shape. Consequently, it was not possible to re-use girder forms on subsequent contracts. It soon became apparent that producers could not afford to have a variety of expensive steel forms. Moreover, it was too expensive to design "custom" girders for each bridge.

---

* Numbers in parenthesis denote references listed at the end of the report.

As a result, representatives of the Bureau of Public Roads, the American Association of State Highway Officials (AASHO)*, and the Prestressed Concrete Institute (PCI) began working on what has since become a series of standard AASHO (now AASHTO) sections for bridge girders. Standard girders Types I through IV were developed in the late 1950's, while Types V and VI were developed in the early 1960's.

Adoption of the AASHO-PCI standard bridge girders simplified design practice and led to wider utilization of prestressed concrete for bridges. A Bureau of Public Roads survey showed that for the years 1957-1960, 2,052 prestressed concrete bridges were authorized for construction with an aggregate cost of $290 million.[1]

There is no doubt that standardization of girders has led to considerable savings in the construction of bridges.[3-5] While standardization may be good, it should also be recognized that it has some drawbacks. Standardization may not only retard further development but also may result in a decrease in economy as the basis for the original selection becomes obsolete.

Since adoption of the standard AASHO girder shapes, there have been significant advancements in the technology of prestressed concrete design and construction. Numerous research studies have provided increased knowledge of structural behavior of prestressed concrete members. This, in turn, has led to refinements in criteria for designing such members. Also, safety standards for interstate and other high speed highways require stricter clearance requirements. These have necessitated longer span bridges.

In recent years, there have been several indications of a need to update design of the standard AASHTO-PCI girders or possibly develop entirely new designs for major prestressed

* The American Association of State Highway and Transportation Officials (AASHTO) was formerly called American Association of State Highway Officials (AASHO).

concrete girders. For example, some state highway departments have developed "improved" girder shapes and others have begun using other girder types or have ceased using prestressed concrete girders. Therefore, the question is, "How efficient are Standard AASHTO-PCI girder sections, especially for spans in excess of 80 ft?"

Objectives

The objectives of this investigation are:

"To evaluate the latest prestressed concrete bridge girder designs being used in this country and to determine which represent optimum designs that could be promoted as national or regional standards."

This investigation was limited to bridges built with pretensioned I- and T-sections, for spans in excess of 80 ft (24.4 m), and with concrete compressive strengths up to 7000 psi (48.3 MPa).

Scope

The above objectives were accomplished within the following scope:

1. Current prestressed concrete girder designs being employed in the United States were summarized.
2. Creative, new concepts becoming available through research were reviewed.
3. Girders representing optimum designs and exhibiting strong potential for standardization were determined.
4. Recommendations for standardization of most practical and cost-effective designs were made.

Findings

The cost-effectiveness of existing "improved" girders was compared with that of the AASHTO girders. Existing improved girders included Colorado and Washington state girders, and Bulb-T's. Most cost-effective girders were the Bulb-T's. Next

most cost-effective girders were the Washington Series followed by the Colorado girders.

Except for one section, the above improved girder shapes have 5-in (127 mm) thick webs. As a result, to satisfy the minimum clear concrete cover requirements, the strands are bundled in the center portion of the girder. Moreover, these improved girders have end blocks.

To avoid bundling of strands, and for ease of consolidating the concrete in the girders during manufacture, cost-effective sections with 5-in (127 mm) thick webs were analyzed with modifications. The web thickness was increased to 6 in (152 mm). Cost-effectiveness of the modified sections was also compared with that of the AASHTO girders. Among the modified sections, Bulb-T's were found to be the most cost-effective.

Based on survey results and cost analyses made in this report, Modified Bulb-T's are recommended for use as national standards. These girders lead to savings up to 17% on the in-place cost of deck and girder compared to the AASHTO girders.

RESEARCH APPROACH

The project was divided into two phases.

Phase I - Evaluation of Current Designs

The project was limited to "Solid-Form" prestressed concrete girders for spans in excess of 80 ft (24.4 m). Information was collected from selected users and suppliers throughout the United States. Selected highway agencies and producers were surveyed either through telephone conversations or through site visits. The purpose of collecting the information was to permit effective evaluation of girder design concepts used in different states.

Advantages and disadvantages of concepts inventoried were assessed. Design, fabrication, transportation, erection, and performance of the different sections were evaluated.

Information inventoried and assessed during Phase I was summarized in an Interim Report.[6] This summary is repeated in this report. The Interim Report also contained a work plan for Phase II of the project.

Phase II - Structural Efficiency and Cost Effectiveness

In Phase II, structural efficiency and cost effectiveness of the "best" existing designs, as well as some modified ones, were evaluated relative to the efficiency of AASHTO sections. This included evaluation of structural parameters such as girder spacing, span length, concrete strength, and deck thickness.

A computer program was developed for use in the parametric studies. A relative unit cost index was assigned to girder and deck slab concretes, prestressing strands, and reinforcing steel. These units reflected in-place relative costs for finished girder and deck. Costs of materials and labor were included. Parameters considered in the cost-effectiveness analysis pertained to the superstructure only. Data generated by the computer program was used to determine the most cost-effective girders.

PHASE I - SURVEY RESULTS

During Task A of Phase I, information was collected on "solid-form" prestressed concrete bridge girders with spans in excess of 80 ft (24.4 m) and concrete compressive strengths up to 7000 psi (48.3 MPa). This information was collected from selected highway agencies and producers located in different regions of the United States.

Highway agencies and other organizations were selected to reflect practices of different regions of the United States. Some States adopted the AASHTO-PCI standard bridge girders. However, a broad range of States used modified and improved girders as discussed later. States with known innovative concepts were surveyed.

Agencies and producers participating in the survey are listed in Appendix A. The survey started with telephone conversations with each participant. It was then followed by site visits to some of the agencies and producers. An outline of items discussed during site visits is listed in Appendix B.

Following the site surveys, collected information was compiled. Findings are summarized in the following sections.

Design, Fabrication and Construction Details

Girder Sections

Girder sections used by each of the surveyed highway agencies are listed in Appendix C. Included are sectional dimensions and properties of the AASHTO-PCI standard bridge girders and other girders used by the survey participants. Approximate span ranges of each section, are also given. Sections used for spans longer than 80 ft (24.4 m) are shown in Figures 1.a through 1.e. Main details differentiating sections are web thickness, size of flanges, and slope of haunch between web and flanges.

It is important to keep evolution of the different sections in perspective. Within the highway agencies surveyed, Pennsylvania's sections were the first to be developed. They were developed in the early 1950's. The AASHTO-PCI standard bridge girders Types I through IV were developed around 1957. They were adopted by several states. Around the same time, several states such as California, Illinois, Texas, and Washington started to produce their own sections.

Recognizing the need for long span girders, AASHTO-PCI standard bridge girders Types V and VI were developed around 1963. By 1971, the State of Colorado stopped using the AASHTO girders and adopted their present sections. At the same time the State of Wisconsin adopted the 70-in (1,778 mm) section.

In the Fall of 1979, none of the agencies and producers surveyed were spending any effort to modify or improve sections for long span girders. Virginia's Department of Highways and Transportation, in cooperation with the local producers was working on developing a single and a double-T girder for short span bridges.

More recently, it was learned that the State of Washington revised their Series 120 prestressed girder. The new section, labeled Series 14 prestressed girder, has a modified top flange that provides additional lateral stiffness. The dimensions of the new section are shown in Figure 1.e. The Series 14 girder will eventually replace the present Series 120 girder.[7]

All Dimensions in Inches
1in = 25.4 mm



Type IV Type V Type VI

AASHTO – PCI



5'- 0" 5'- 6" Type D

California Iowa

Figure 1.a Girder Cross Sections

BEST DOCUMENT AVAILABLE

All Dimensions in Inches
1 in = 25.4 mm



Colorado



Illinois

Figure 1.b Girder Cross Sections

BEST DOCUMENT AVAILABLE

All Dimensions in Inches
1 in = 25.4 mm



Figure 1.c Girder Cross Sections

BEST DOCUMENT AVAILABLE

All Dimensions in Inches
1 in = 25.4 mm



Pennsylvania

Figure 1.d Girder Cross Sections

BEST DOCUMENT AVAILABLE

All Dimensions in Inches
1 in = 25.4 mm



Figure 1.e Girder Cross Sections

BEST DOCUMENT AVAILABLE

Participants were asked if they would consider improved sections if developed. Several agencies are satisfied with their present sections. However, they said that they would consider new sections if these resulted in significant advantages and were cost effective. Some agencies are reluctant to change the AASHTO sections they use. The basic reason is that their producers are successful in producing these sections. Moreover, the forms represent a large investment. New forms would increase the unit cost of girders.

Longest spans built from standard, single unit girders are as follows: 105 ft (32 m) in Illinois, 112 ft (34.1 m) in Louisiana, 118 ft (36 m) in Pennsylvania, 120 ft (36.6 m) in Virginia and California, 125 ft (38.1 m) in Tennessee, 130 ft (39.6 m) in Colorado and Wisconsin, 140 ft (42.7 m) in Oregon, 145 ft (44.2 m) in Washington, and 150 ft (45.7 m) in Texas. Spans longer than 150 ft (45.7 m) have been produced by increasing the depth of the top flange or through splicing of long precast segments. Splicing of I-girders is discussed separately under the heading "Special Concepts".

End Blocks

End blocks serve two functions. First they provide a larger anchorage zone at the ends of the girder. Large bursting stresses occur in these areas due to stress transfer from the pretensioned strands to the surrounding concrete. Vertical stirrups are required to resist the bursting stresses and thereby prevent splitting (horizontal) cracks at the ends of the girder.

The second function of end blocks is that they provide greater web thickness at the ends of girders where shear forces are highest. Where adjacent spans are made continuous for live load, higher shear forces occur near the supports.

The most recent edition of "AASHTO Standard Specifications for Highway Bridges"[8] does not require use of end blocks in pretensioned beams. End blocks are utilized in very few states. Shear design dictates the need for end blocks in sections with thin webs and long spans. Included in this category are the

Washington and Colorado State standard sections as well as the Wisconsin 70-in (1,778 mm) girder. These girders have webs 5- or 6-in (127 or 152 mm) thick.

In Oregon, all bridge girders have end blocks. Girder sections include AASHTO standard girders Types II, III, and IV, Oregon Type V, bulb-T's and a 7-ft (2.13 m) deep I-Girder. Oregon sections having 7.5- and 8-in (190 and 203 mm) thick webs have three side-by-side strands deflected from each row. The end blocks are utilized to prevent cracking and spalling in end regions.

In Pennsylvania, some sections have webs up to 14 in (356 mm) thick. In these sections, five side-by-side strands are deflected from each row of strands. The State of Texas has one producer equipped to deflect three side-by-side strands.

Continuity for Live Load

Most survey participants design adjacent spans to be continuous for live load. Some started this practice recently and consider it occasionally for long spans. It has been estimated that continuity will provide about 10% more span capability than if the beams are simply supported. The AASHTO Specifications provide guidelines for design of "Bridges Composed of Simple-Span Precast Prestressed Girders Made Continuous".[8]

Diaphragms

In all states surveyed, diaphragms are used at span ends as recommended by the AASHTO Specifications.[8] It was reported that end diaphragms ensure distribution of reactions at span ends and provide smoother riding as vehicles cross over supports.

Intermediate diaphragms are not used in the States of Illinois and Tennessee. In all other states, intermediate diaphragms are used for spans in excess of 40 ft (12.2 m) as recommended by the AASHTO Specifications.[8] For spans from 40 to 80 ft (12.2 to 24.4 m), one diaphragm is recommended at mid-span. For spans in excess of 80 ft (24.4 m), diaphragms are recommended at third points of the span.

In several states, the feeling was that intermediate diaphragms were useful in cases of collisions by overheight vehicles. Research has indicated that the structural usefulness of diaphragms is minimal, and they are harmful in most cases.[9-10]

Level of Tension in Concrete

Most states surveyed design for 6 $\sqrt{f'_c}$ psi (0.5 $\sqrt{f'_c}$ MPa) tensile stress in the concrete under service conditions. This is the upper level currently permitted by the AASHTO Specifications.[8] In one state, allowable concrete tension under service condition is limited to 3 $\sqrt{f'_c}$ psi (0.25 $\sqrt{f'_c}$ MPa). Several states do not allow tension in the concrete after all losses have occurred. In one case, factored dead and live loads correspond to cracking moment.

Concrete Properties

In most states, pretensioned bridge girders are manufactured from normal weight concrete (150 lb/cu ft, 2,403 kg/m^3). In the Pacific Northwest Region, concrete density is 155 lb/cu ft (2,483 kg/m^3).

Generally, girders are designed for concrete compressive strength, f'_c, of 5000 to 6000 psi (34.5 to 41.4 MPa) at 28 days. However, concrete design strength is as low as 4000 psi (27.6 MPa) in the Pacific Southwest Region and as high as 7000 psi (48.3 MPa) in the Pacific Northwest Region. Compressive strength of concrete at time of initial prestress, f'_{ci}, ranges from 4000 to 6000 psi (27.6 to 41.4 MPa).

Among survey participants, girders of only one bridge in Washington were built from lightweight concrete. Decks made of lightweight concrete have been used only on a few bridges having steel girders. Survey participants believe that the behavior of structural lightweight concrete is not adequately understood, and creep characteristics are not sufficiently documented. Consequently, lightweight concrete is not considered for pretensioned bridge girders.

Strand Properties

The most common size strand for pretensioned girders is 1/2-in (12.7 mm) diameter. It is the only size used in several states. A few states also design with 7/16-in (11.1 mm) diameter strands. To allow for competitive bids, alternate designs with both sizes of strands are prepared. In all cases, Grade 270 (1,860 MPa) strands are used.

Requirements for surface condition of strands vary with states. The State of Washington specifies bright strands. In California, shiny strands are required for post-tensioned girders. "Rust free" steel is specified for use in pretensioned girders. Most states permit a light coating of surface rust. In no case is loose rust or pitting allowed.

All states specify stress-relieved strands, while some also allow low-relaxation strands.

Girder Spacing

Spacing used for pretensioned girders varies between 4.5 and 10 ft (1.37 and 305 m) in most states. In exceptional cases, the spacing is larger. Maximum spacing reported is 12 ft (3.66 m). To reduce the cost of prestressed concrete bridges, Scott[11] has suggested using as few girders as possible in each span.

Decks

Three types of decks are used in conjunction with pretensioned bridge girders. Most decks are cast-in-place and supported on temporary wood forms. In Pennsylvania and Texas, some decks are cast on permanent steel forms.

A technique gaining popularity in several states is the use of precast prestressed concrete deck panels. These panels act as permanent forms for the cast-in-place concrete deck. They become an integral part of the finished deck. Recent AASHTO Specifications provide guidance for design of the precast deck panels.[12]

Design Loads

All survey participants design their highway bridges to carry the HS 20-44 loading. It is recognized that overloads occur frequently. In the State of Oregon, bridges subjected to heavy traffic are designed for HS-25 loading.

All Interstate highway bridges are also checked for military loading. This loading governs the design of spans less than approximately 37 ft (11.3 m) when simply supported.

Design Aids

Preliminary designs are based on experience and/or design charts or tables. In the majority of agencies, final design calculations are performed by electronic computers. In one state, the only design aids used are detailed design charts. This elaborate set of charts was developed at an appreciable initial cost.

Influence of Producers and Contractors on Type of Bridge

During the survey, questions were asked regarding adequacy of girder producers and construction contractors and whether they influenced the engineer's decision regarding type of bridge. Generally, highway agencies are satisfied with performance of both manufacturers and contractors. Occasionally, problems are encountered in some states. Usually, decisions regarding type of bridge rest on least initial cost and contractor's experience.

Alternate Designs

In many states, alternate designs are provided to stimulate competition and obtain least cost bridges. In some agencies, options are prepared for straight or draped strands and different compressive strength of concrete at initial prestress. Alternate designs and options are prepared by the highway agencies. Preliminary designs undergo value engineering, i.e., overall improvement in the cost of bridges is realized by carefully investigating availability of materials, construction methods, shipping costs, and similar cost influencing items.

Fabrication Details

Procedures for pretensioning strands, and deflecting draped strands vary with manufacturers. Some highway agencies require bundling of strands at hold down points. Usually strands are deflected at two locations, each at about 0.4 point of span. In long span girders, a larger number of strands are draped. In such cases, some plants choose to deflect the strands at four hold down points in each girder. Acceptable surface condition of strands was described earlier under "Strand Properties".

The AASHTO Specifications[8] contain requirements for minimum concrete cover for reinforcement and minimum spacing between strands. The minimum concrete cover is 1-1/2 in (38.1 mm) for prestressing steel and 1 in (25.4 mm) for web reinforcement. For pretensioning steel, minimum clear spacing of strands at the ends of beams is three times the diameter of the steel or 1-1/3 times the maximum size of the concrete aggregate, whichever is greater. For 1/2-in (12.7 mm) diameter strands, the minimum distance between center of strands is 2 in (50.8 mm) provided maximum aggregate size does not exceed 1-1/8 in (28.6 mm).

Almost all survey participants follow the above requirements. There are two exceptions. In Washington, minimum vertical and horizontal spacing between center of strands is 1-3/4 in (44.5 mm). However, maximum aggregate size is 1/2 in (12.7 mm) and the concrete is denser than in other states. In Colorado, horizontal spacing between center of strands is 1-3/4 in (44.5 mm) while vertical spacing is 2 in (50.8 mm). In Pennsylvania, Virginia, and Wisconsin, minimum clear concrete cover for the web reinforcement is increased to 1-1/2 in (38.1 mm).

Detailing of web reinforcement greatly affects fabrication costs of pretensioned girders. Figures 2.a and 2.b show the types of web reinforcing schemes used in different states. It can be seen that there are as many schemes as survey participants. Scott[11] has suggested stirrups should be detailed such that reinforcement cages can be prefabricated. Alternatively,



California

Colorado



Illinois



Iowa

Louisiana



Oregon

Figure 2.a Stirrup Schemes

BEST DOCUMENT AVAILABLE



Pennsylvania

Tennessee



Texas



Virginia

Washington



Wisconsin

Figure 2.b Stirrup Schemes

BEST DOCUMENT AVAILABLE

stirrups should be easy to tie into place after the strands are tensioned. Moreover, it is not necessary to have the stirrups surrounding the strands.

Construction Details

Lateral stability of long span slender sections, during hauling and erection, presents problems in several states. External lateral stiffening devices made up of preassembled steel space trusses or external adjustable devices (hog rods) are provided. These devices are attached to the girder in the plant. They are only removed after setting and bracing the girders in their final position. The problem of lateral stability is discussed later under the heading "STRUCTURAL EFFICIENCY".

Minimum erection and bracing requirements are provided on some state drawings. Girders set on neoprene pads are found to be wobbly. Additional diagonal bracing is required. Guidelines for construction procedures are available in AASHTO Specifications[8] and state construction specification manuals.

Construction manuals provide a set of fabrication and construction tolerances. Camber differential of girders is of particular interest. In Pennsylvania and Washington, allowable camber differential between adjacent beams is 1/8 in per 10 ft (3.2 mm per 3.05 m) of span, up to a specified maximum. Maximum camber differential is 1-1/4 in (31.8 mm) in Pennsylvania, and 1 in (25.4 mm) in Washington.

Transportation Requirements and Restrictions

Regulations for hauling girders on highways and roads vary from state to state. Maximum overall length hauled without permit varies between 55 and 80 ft (16.8 and 24.4 m) for states surveyed. Lengths beyond these limits require special permit. Maximum permitted length depends on the route traveled. In some states, there is no limit to overlength, while others have an upper limit. In Pennsylvania, a length in excess of 160 ft (48.8 m) is not normally permitted. For spans discussed in this report, special overlength permits would be needed.

Maximum legal gross weight hauled without permit varies between 72 and 96 kips (320 and 427 kN), depending on the state. Beyond this limit, a special permit is required. Maximum legal overloads depend on the number of axles and distance between consecutive axles. Using appropriate number of axles, maximum girder weights discussed in this report may be hauled with special permits.

Overwidth and overheight regulations do not present limitations for the type of girders considered in this report.

Availability and Costs

Cost data obtained during the survey are summarized in Appendix D. Costs of material and labor vary from region to region within the United States. They also vary between states of a region, between districts of a state, and within a district according to bridge location.

Main factors affecting materials costs within a state are accessibility of the construction site, distance between girder producers and site, and distance between ready mix plants and site. Size of a bridge, and consequently number of girders ordered for a project, affect the unit cost of girders. This cost is higher for smaller quantities.

In remote areas, availability of labor experienced with bridge construction is often limited. This necessitates relocating skilled labor. As a result, contract cost increases.

Combining all the above factors presents difficulties in assessing cost factors in the different regions of the United States. The effect of these factors is reflected in the discrepancies in unit costs within a given state as shown in Appendix D. In addition, each highway agency uses a different approach to itemize unit costs. Costs for new construction, rehabilitation, and bridge widening are all averaged in several states.

Suggestions for Bridge Cost Reduction

During the survey, the question was asked about what could be done to reduce the cost of bridge construction. Suggestions

to reduce the cost of pretensioned concrete bridge girder construction included:

1. Eliminate intermediate diaphragms
2. Use superplasticizers
3. Reduce web thickness of AASHTO standard bridge girders
4. Use a more efficient section to replace AASHTO Type IV girder
5. Use higher concrete compressive strength
6. Use maximum girder spacing

Structural Durability

Prestressed concrete bridge construction started in the United States 30 years ago. In recent years, the first post-tensioned bridge, the Walnut Lane Bridge, has shown signs of distress.[13] Generally, prestressed concrete bridges have displayed excellent performance. In all states surveyed, durability and performance of pretensioned bridge girders were reported to be very good.

Problems with pretensioned girders occur due to collisions by overheight vehicles. Where de-icing salts are used, deterioration of concrete decks presents problems. However, pretensioned concrete girders require virtually no maintenance.

Expected life span of pretensioned bridges varies between 40 and 100 years. Inspection frequency varies with age and condition of bridges. In several states, inspection is performed on a yearly basis. In some states, a routine inspection is made every six months, and an in-depth inspection is made every two years.

In-service pretensioned girders are reported to be free of cracks. The only cracks reported have occurred in the plant at release of prestress.

Aesthetics and Safety

No strict aesthetic requirements are specified by any of the states surveyed. However, they all plan and build their bridges to be aesthetically pleasing. It has been suggested

that the most structurally efficient bridge would be the most aesthetically pleasing.[14]

In California, box girder bridges are found to be more appealing and economical. In all other states, pretensioned bridge girders are found more economical for spans of 70 to 130 ft (21.3 to 39.6 m).

In Oregon and Virginia, exposed girders and supports are painted to improve their appearance. In Washington, architects are consulted in the preliminary design stages. In the City of Philadelphia, an art commission approves every bridge.

Girders having end blocks were discussed earlier. For aesthetic reasons, all end blocks are gradually tapered over several feet.

Safety requirements specified by the Federal Highway Administration are incorporated in the section on General Features of Design in the AASHTO Specifications for Highway Bridges.[8]

Opinions and Policies

In all states surveyed, opinions and policies regarding type of bridge have a common ground. The type of bridge selected is based on economy. For short spans up to 30 ft (9.1 m), cast-in-place reinforced concrete slabs are the most economical. For spans from 30 to 75 ft (9.1 to 22.9 m), precast spread boxes or double-T's are considered. For longer spans between 70 and 150 ft (21.3 and 45.7 m), depending on the state, pretensioned I and T girders are selected. Beyond this range, steel bridges are considered.

In recent years, post-tensioned segmental construction has gained acceptance. This has proven to be the most economical for spans from roughly one hundred to several hundred feet long.

In California, 85% of the bridges are cast-in-place post-tensioned box girders. This type of bridge is found to be more attractive and economical than pretensioned I-girder construction.

Special Concepts

The following special concepts used by some states deserve mention:

Splicing of Girders

Transportation of girders for spans in excess of about 120 ft (36.6 m) presents overlength and overload problems in some areas. To achieve longer spans, splicing of precast segments has been used successfully in several states and in Ontario, Canada. Several splicing techniques are available. Guidelines to design the splice have been published.[15-16]

Among participants, four states have built bridges from long precast segments. Three other states have considered the technique. In California, spans of 139 ft (42.4 m) have been achieved. In Illinois, two bridges, each having two 125 ft (38.1 m) spans, have been built by splicing three girders segments.[17] In Oregon, 190 ft (57.9 m) spans have been achieved by splicing 7-ft (2.1 m) deep I-Sections or bulb-T sections. In 1975, Pennsylvania built a 140 ft (42.7 m) span from spliced girders.

Drop-In Spans

Another method to achieve long spans uses dapped girders dropped onto cast-in-place members cantilevering from the piers. This technique has been used in Oregon, Virginia, and Washington.

Precasting Deck Panels

For multiple span bridges built with precast I-girders, it is often cost effective to use precast prestressed deck panels. These pretensioned deck panels serve as permanent forms to place the cast-in-place concrete deck. They become an integral part of the finished deck. Recent AASHTO Specifications provide guidance for design of the precast deck panels.[12]

Precast deck panels have been successfully used in Illinois, Louisiana, Texas, and Virginia. This technique has also been used experimentally in Pennsylvania. California, Oregon, and

Washington are considering precast deck panels as alternate designs.

Bridge deck construction is accelerated where precast deck panels are used. This technique has been found economical on multiple span bridges. The large volume of required panels justifies the initial investment for set-up of a precasting bed.

Blanketing Strands

Blanketing is a means of eliminating the need for draped strands.[18] With this method, all strands are kept straight. Some are debonded at the ends of the girders to control the concrete stresses. Advantages of this technique are that stressing is done in one operation. There is better control over the level of prestress along the length of the girder. No hold-up or hold-down devices are needed.

Blanketing has been used for several years in Tennessee for the manufacture of pretensioned box girders. Several plants blanket some strands at the end of the member to avoid sudden transfer of prestress from all strands at the same region. Bursting stresses are spread over a longer portion of the member. Recently, the State of Louisiana has utilized this concept on some bridges. The PCI Committee on Bridges is preparing a report on "Use of Debonded Strands in Pretensioned Bridge Members".[19]

Pre Post-Tensioning

In pre post-tensioning, girders are pretensioned in the plant to a level that permits handling. They are then post-tensioned either in the plant at a later date or on site. Advantages of this procedure[20] are early stress transfer and control of deflection. Higher prestress eccentricities are achieved.

Pre post-tensioning has been used in the past in Washington. It has also been experimented with in Pennsylvania. It has been considered as an alternate design by other states.

PHASE II - STRUCTURAL EFFICIENCY

Currently, there is no well established procedure to measure the efficiency of a structural section. In a pretensioned bridge member, predominant stresses are flexural. Therefore, the designer's goal should be to use a section that has the highest section modulus with least area. Conversely, for a given sectional area, the highest section modulus is desirable. The final decision is based on economy. Usually, efficiency and economy go hand-in-hand.

One way of measuring the relative performance of bridge girder sections has been suggested by Anderson.[20] He suggests that the relationship between cross sectional area and section modulus for the bottom fibers be compared. Such a relationship is shown in Figure 3 for standard state sections of survey participants. Although the AASHTO-PCI Type VI section has the highest modulus, it also has the biggest area, i.e., it is the heaviest. It is interesting to note that Colorado's G68 section, the Washington Series 120 and 14, and AASHTO Type VI have about the same span capabilities. This is shown in Appendix C. However, G68 and Series 120 and 14 are about 40 percent lighter than Type VI.

An efficiency factor for prestressed sections has been derived by Guyon.[21] It is based on minimizing the area of the section for a given section modulus. This efficiency factor, ρ, is defined as:

$$\rho = \frac{r^2}{y_t y_b}$$

where r = radius of gyration of section $= \sqrt{I/A}$

y_t, y_b = distance from center of gravity to top and bottom fibers, respectively

I = moment of inertia

A = cross sectional area

The efficiency factor for various sections is listed in Tables 5 and 6 of Appendix C. Variation of the efficiency

BEST DOCUMENT AVAILABLE



Figure 3 Relationship Between Modulus of Section for Bottom Fibers and Cross-Sectional Area

BEST DOCUMENT AVAILABLE

factor, ρ, with respect to depth of section is plotted in Figure 4. This figure indicates that the Colorado sections are comparable in efficiency to the Washington sections. Both are superior to the AASHTO Sections.

More recently, Aswad[22] has suggested another way of judging efficiency of I-Sections used in bridge superstructures. He proposed an efficiency ratio, α, defined as

$$\alpha = \frac{3.46\ S_b}{A\ h}$$

where S_b = section modulus for bottom fibers
A = cross sectional area
h = depth of section

Through analysis based on Colorado regional costs, Aswad found that the girders with the highest efficiency factor had the lowest cost per square foot of superstructure.[22]

Efficiency ratios of various sections are listed in Tables 5 and 6 of Appendix C. Figure 5 shows variation of efficiency ratio for different section depths. Data plotted are for all standard sections inventoried. According to Figures 3 to 5, Washington Series and Colorado girders are the most structurally efficient sections.

The three approaches described above confirm that the designer's goal should be to use sections that have the highest modulus with the least area within practical limitations. To achieve these goals in I-Sections, as much of the area as possible should be concentrated in the flanges. Therefore, the web should be as thin as practicable. Moreover, the haunch between web and flanges should be as flat as possible but still permit placing the concrete and stripping the forms.

Minimum web thickness is controlled by the present AASHTO Specifications.[8] For two 1/2-in (12.7 mm) diameter strands deflected side-by-side and No. 4 web reinforcement, the minimum web thickness is 5-1/2 in (140 mm). If the strands are bundled, minimum web thickness is 5 in (127 mm). All Washington



Figure 4 Variation of Efficiency Factor with Depth of Section

BEST DOCUMENT AVAILABLE



Figure 5 Variation of Efficiency Ratio with Depth of Section

BEST DOCUMENT AVAILABLE

State I-Sections and Colorado's G68 have 5-in (127 mm) thick webs.

It should be recognized that I-Sections with very thin webs are slender sections. As a result, stability during handling becomes a problem. Girders having 5-in (127 mm) thick webs and spans in excess of about 100 ft (30.5 m) require special attention during handling. On the other hand, I-Section girders having 7-in (178 mm) thick webs and narrow flanges also present stability problems during handling. Therefore, the overall lateral stiffness should be considered.[23-24]

Concern about the lateral stiffness of long spans prompted the State of Washington to develop Series 14 prestressed girder. This new section will eventually replace Series 120 girder. Lateral stiffness of Series 14 is about 1.9 times that of Series 120.

Bulb-T's and decked Bulb-T's are utilized in the Pacific Northwest. They provide better lateral stiffness compared to I-Sections. A Bulb-T is an I-Section with a wide (4 to 6 ft, 1.2 to 1.8 m) and thin top flange. A concrete deck is cast-in-place on top of the Bulb-T. As the top flange of Bulb-T's is wider than that of I-girders, less formwork is needed to support the deck concrete.

A decked Bulb-T has a full depth (5 to 6 in, 127 to 152 mm) and full width (4 to 10 ft, 1.22 to 3.05 m) top flange. The top flanges constitute the bridge deck. Adjacent units are joined through lateral post-tensioning or welded flange connectors where potential problems are currently being studied. The shear keys are grouted. Anderson has suggested use of decked Bulb-T's for simple spans up to 190 ft[20] (57.9 m). Because of their weight and length, such girders usually can be transported only on barges.

Bulb-T sections have been utilized in the State of Oregon for construction of bridges on the primary highway system during the last 15 years. Spans of 190 ft (57.9 m) have been achieved by splicing segments. At splice locations, the segments are supported on temporary supports. After casting the concrete deck, the bridge is post-tensioned. Continuity at

permanent supports is obtained. Temporary supports are then removed. Over half a dozen bridges have been built using this technique.

Some 15 bridges have also been built in the State of Oregon from single unit Bulb-T's. Maximum spans obtained are 140 ft (42.7 m). Longer spans have been achieved through drop-in methods. Cast-in-place concrete members cantilever from the supports. Dapped end Bulb-T's are then dropped-in.

Decked Bulb-T's are also called integral deck Bulb-T's. They have been used for bridge construction only on secondary routes in the State of Oregon. First applications started three years ago. A dozen bridges, with spans up to 130 ft (39.6 m) have been built.

At the time of the survey, the State of Washington Department of Transportation had not built any bridges with decked Bulb-T's. However, they had been considered as alternative designs. Bulb-T's have been utilized during the last three years on about a dozen bridges in Washington. These sections have 5-in (127 mm) thick webs.

With the need for energy efficiency, the designer's goal should be to use the lightest section. This is accomplished by using the least amount of material possible. The section is lighter to transport, lighter to erect, and requires fewer prestressing strands.

In the previous section, different girder sections were compared with the AASHTO sections on three structural efficiency scales. In the next section cost effectiveness comparisons will be made for selected girder sections. Additional observations will be reported on the structural efficiency of selected girders.

PHASE II - COST EFFECTIVENESS

In this section, girder cross sections are selected for cost-effectiveness analysis. Assumptions made for the cost-effectiveness analysis are stated. The number of parameters involved in the analysis necessitated development of a computer program. This program is briefly described. Cost-effectiveness

comparisons are made to reflect the effect of the parameters considered.

Cross Sections Analyzed

Earlier discussions under the heading "STRUCTURAL EFFICIENCY" indicated that the most efficient sections were the Washington state series and Colorado's G54 and G68 sections. It was also indicated that Bulb-T's had been used successfully in the Pacific Northwest. A set of Bulb-T sections was developed in 1959 by Anderson.[20] These sections, as well as the Washington series and Colorado's G68 have 5-in (127 mm) thick webs. To satisfy the AASHTO specifications,[8,12] web width should be not less than 5-1/2 in (140 mm) if strands are not bundled at mid-span. If strands are bundled, web width of 5 in (127 mm) would satisfy requirements for concrete cover and clear spacing between strands.

Several survey participants expressed concern about possible difficulties in manufacturing and transporting girders having 5-in (127 mm) thick webs. Main concerns were consolidation of the concrete in thin and deep members, and stability of such slender members during transportation. On the other hand some survey participants felt that present AASHTO girders can be improved by reducing their web thickness.

At a meeting[25] held in April 1980, members of the PCI Bridge Committee were asked about minimum practical web width to place and consolidate the concrete in precast prestressed I-sections. All committee members were in favor of a minimum web width of 6 in (152 mm).

AASHTO Standard Bridge Girders Types I and II have 6-in (152 mm) thick webs. In all regions of the United States, concrete has been placed and consolidated in these sections without difficulty. Therefore, in Phase II, existing sections having 5-in (127 mm) thick webs were evaluated and compared with similar sections having 6-in (152 mm) thick webs. Sections with 6-in (152 mm) thick webs should be easier to manufacture and transport than sections with 5-in (127 mm) thick webs.

Based on the above discussion, the following sections were evaluated in Phase II of the project:

1. Colorado's G54 and G68 girders. Girder G68 has a 5-in (127 mm) thick web.
2. Washington Series 80, 100, 120, and 14 girders. These girders have 5-in (127 mm) thick webs.
3. Anderson's Bulb-T's[20] BT48, BT60, and BT72. These girders have 5-in (127 mm) thick webs. The tips of the top flanges are 1 in (25.4 mm) thick.
4. Girder similar to Colorado's G68 but with 6-in (152 mm) thick web. This girder is designated Modified Colorado G68/6 in this report.
5. Girders similar to Washington series but with 6-in (152 mm) thick webs. These sections are designated Modified Washington Series 80/6, 100/6, 120/6, and 14/6.
6. Girders similar to Anderson's Bulb-T's, but with 6-in (152 mm) thick webs and 2-in (50.8 mm) thick top flange tips. These sections are designated Modified Bulb-T's BT48/6, BT60/6 and BT72/6.
7. AASHTO standard bridge girders Types IV, V, and VI.
8. Modified AASHTO girders where web thickness, and top and bottom flange widths are reduced by 2 in (50.8 mm). These were considered with the idea that existing forms could be used with reduced space between them. These sections are designated Modified Types IV, V, and VI.

Dimensions of existing and modified sections considered are shown in Figures 6 and 7, respectively. Both the Washington series and Anderson's bulb-T's with 5-in (127 mm) thick webs and the modified sections with 6-in (152 mm) thick webs are compared on the three efficiency scales in Figures 8 to 10. Sections with 6 in (152 mm) webs are slightly less efficient than similar sections with 5 in (127 mm) webs. However, according to Figures 9 and 10, Bulb-T's are more efficient than Washington Series. Further comparisons between sections are made below based on cost-effectiveness charts.

All Dimensions in Inches
1in = 25.4 mm



Type IV Type V Type VI

AASHTO – PCI



G 54 G 68

Colorado

Figure 6.a Existing Girders Analyzed

BEST DOCUMENT AVAILABLE

All Dimensions in Inches
1 in = 25.4 mm



BT	48	60	72
d	48	60	72
e	33	45	57

Bulb-T



Series 80 Series 100 Series 120 Series 14

Washington

Figure 6.b Existing Girders Analyzed

BEST DOCUMENT AVAILABLE

All Dimensions in Inches
1 in = 25.4 mm



Mod. Type IV Mod. Type V Mod. Type VI

Modified AASHTO

Figure 7.a Modified Girders Analyzed

BEST DOCUMENT AVAILABLE

All Dimensions in Inches
1 in = 25.4 mm



BT	48/6	60/6	72/6
d	48	60	72
e	33	45	57

Modified Bulb - T



Modified Colorado G 68/6

Figure 7.b Modified Girders Analyzed

BEST DOCUMENT AVAILABLE

All Dimensions in Inches
1in =25.4 mm



Mod. Series 80/6



Mod. Series 100/6



Mod. Series 120/6



Mod. Series 14/6

Modified Washington Series

Figure 7.c Modified Girders Analyzed

BEST DOCUMENT AVAILABLE



Figure 8 Relationship Between Modulus of Section for Bottom Fibers and Cross-Sectional Area for Washington Series and Bulb-T's

BEST DOCUMENT AVAILABLE



Figure 9 Variation of Efficiency Factor with Depth of Section for Washington Series and Bulb T's

BEST DOCUMENT AVAILABLE



Figure 10 Variation of Efficiency Ratio with Depth of Section for Washington Series and Bulb-T's

BEST DOCUMENT AVAILABLE

Structural Parameters

The sections were evaluated through a detailed structural analysis. The following parameters were considered:

1. Girder spacing
2. Span length
3. Deck thickness
4. Concrete strength

Girder spacing was varied between 4.5 and 10 ft (1.37 and 3.05 m). Spans in excess of 80 ft (24.4 m) were considered. Deck thickness varied with girder spacing. Concrete strength for girders was varied between 5,000 and 7,000 psi (34.5 and 48.3 MPa).

Development of Computer Program

To evaluate the effect of each variable, a parametric study was carried out. The number of variables necessitated preparing a computer program to analyze each case and generate cost data.

The computer program, called BRIDGE, is described in detail in Appendix E. Program documentation, user's instructions, source listing and sample problems are all included in the Appendix. The following are highlights of the program.

Program BRIDGE requires input of the following data:

1. Geometric properties: Included are girder span, spacing, and cross section.
2. Materials properties: Included are concrete and strand characteristics.
3. Relative costs of materials: Materials considered are deck and girder concrete, deck transverse flexural reinforcement, and girder strands. Deck temperature reinforcement and girder web reinforcement are not considered in the cost analysis.

Data input is further simplified by making some of the above data optional. Where material properties and relative costs are not input in the program, default options are assigned internally by the program. These default options are summarized in the "User's Input Instructions" in Appendix E.

In addition to listing data input or information internally assigned, the computer program outputs the following information:

1. Allowable concrete stresses and strand stresses, both at prestress transfer and service load conditions
2. Deck thickness and reinforcement
3. Sectional properties for the girder (non-composite) section, and the composite (girder-deck) section
4. Dead and live load moments and impact factor
5. Required number of strands and corresponding midspan concrete and strand stresses, both at prestress transfer and service load conditions
6. Midspan camber or deflection
7. Weight of materials and cost index per unit surface area of bridge deck

The following assumptions were made in Program BRIDGE:

1. Design conforms to AASHTO Specifications.[8,12]
2. Live load consists of HS 20-44 loading.
3. Girders are simply supported.
4. A typical interior girder is considered.
5. Concrete deck is cast-in-place and acts compositely with the girder. Deck formwork is supported on the girder. In calculations of the composite section properties, the transformed area of strands is neglected.
6. Concrete compressive strength of the deck is constant and equal to 4000 psi (27.6 MPa) at 28 days.
7. Strands are Grade 270 (1,862 MPa) stress relieved with 1/2-in (12.7 mm) diameter and have an idealized trilinear stress-strain curve.
8. Total prestress losses are constant and equal 45,000 psi (310 MPa).
9. Cost of materials, labor, transportation, and erection of girders having concrete compressive strength between 5000 and 7000 psi (34.5 and 48.3 MPa) is assumed constant. The effect of increasing the girder concrete strength from 5000 to 7000 psi (34.5 to 48.3 MPa) on the in-place cost of the girder is negligible.

10. Relative unit costs of materials and labor are constant for the cost analysis.
11. Cost analysis comparisons are for the precast girder and a cast-in-place deck. Cost of substructure and approach fills are not considered.

Relative Unit Cost Indexes

Several factors affect the cost of the superstructure. They have been discussed under the heading "Availability and Cost". An assessment of local and regional factors was not possible within the scope of this project. However, a cost analysis was possible by comparing the cost of the recommended sections based on a common ground.

From survey data, an average cost for girder concrete, deck concrete, reinforcing steel, and prestressing strands was determined. Average costs included cost of materials and labor. For girder concrete, the cost also included transportation and erection. These average costs were then reduced to relative costs per pound of in-place material. The following relative unit costs for in-place materials (including labor) were used for the cost analysis.

Concrete (girders and deck)	1 unit/lb
Strands	8 units/lb
Reinforcing steel	9 units/lb
Epoxy coated reinforcing steel	12 units/lb

Girders were compared based on the same unit costs. In the cost analysis, top deck reinforcement was assumed to consist of epoxy coated bars. However, this is optional in Program BRIDGE. Top deck reinforcement can be specified as regular deformed bars.

The relative costs of materials were taken as the product of material weight and relative unit costs. The summation of relative costs of materials was then divided by deck area to give cost index per square foot.

Design Charts

Data generated by Program BRIDGE can be used to prepare different types of design aids. For preliminary designs, the relation between girder span, girder spacing, and required number of strands can be very useful.

Figure 11 shows the required number of strands versus span length for selected girder spacings of AASHTO Type VI section. A similar plot is shown in Figure 12 for Washington Series 14 girder. For comparable spans, the number of strands required in the Washington Series 14 section is considerably less than that required in the AASHTO Type VI.

Another type of design aid is shown in Figure 13. It depicts maximum spans that can be achieved at different girder spacing for four girder cross-sections. This figure indicates that for a given girder spacing, the longest spans are achieved using AASHTO Type VI girder. Design aids in the form of charts as shown in Figures 11 to 13 do not reflect the cost-effectiveness of the sections. The main purpose of Program BRIDGE is to generate cost analysis data for comparisons.

Optimum Cost Index Charts

Using Program BRIDGE, a cost chart was prepared for each of the sections considered in Phase II of the project. Same relative unit costs for in-place materials (material and labor) as well as material properties were assumed for all girders and decks. For the girders, the concrete compressive strength was assumed to be 4500 psi (31.0 MPa) at transfer (f'_{ci}), and 6000 psi (41.4 MPa) at 28 days (f'_c). For the deck, the concrete compressive strength at 28 days, f'_c, was assumed to be 4000 psi (27.6 MPa).

All cost charts were drawn to the same scale for comparison purposes. These charts are presented in Appendix F. A representative chart is given in Figure 14. It depicts cost index per square foot of deck versus span length for AASHTO Type VI girder. The solid lines are for selected girder spacing.

Cost curves can be drawn for different girder spacings varying between 4.5 and 10 ft (1.37 and 3.05 m). If for each span



Figure 11 Required Number of Strands in AASHTO Type VI Girder

BEST DOCUMENT AVAILABLE



Figure 12 Required Number of Strands in Washington Series 14 Girder

BEST DOCUMENT AVAILABLE



Figure 13 Variation of Maximum Span with Girder Spacing

BEST DOCUMENT AVAILABLE



Figure 14 Cost Chart for AASHTO Type VI Girder

BEST DOCUMENT AVAILABLE

the least cost index points are joined, an "optimum cost curve" is obtained. These points will correspond to different girder spacings, except where the maximum girder spacing of 10 ft (3.05 m) controls.

In Figure 14, the dotted curve is an actual optimum cost curve. It was obtained through a detailed analysis. Discontinuities of this curve are due to several factors affecting the cost index. The main factor is the deck thickness.

As girder spacing increases, deck thickness increases in 1/2-in (12.7 mm) increments. The result is a sudden change in weight of deck and composite sectional properties. In turn, section properties affect member design and cost of materials. In addition required number of strands is computed to the whole nearest number. Although the cost of one strand is negligible compared to the overall cost, each strand has an important effect on the concrete stress level.

In this report, discontinuities in the optimum cost curves are ignored and an idealized curve is plotted for all cost charts. In Figure 14, this idealized curve is shown as a dashed line.

Figure 14 illustrates the effect of girder spacing on cost. For a given span, as girder spacing increases, unit cost per square foot of bridge deck decreases. For an AASHTO Type VI section, if girders are spaced 10 ft (3.05 m) apart, the cost per unit area of bridge deck is 30% less than if girders are spaced 4.5 ft (1.37 m) apart. Therefore it would be most economical to place girders at the largest practical girder spacing.

For sections analyzed in this report, the cost of girders represents a significant portion of the cost of the bridge superstructure. For example, if AASHTO Type VI girders are placed at a spacing of 10 ft (3.05 m), the in-place cost of the girders is about 40% of the overall in-place cost of girders and deck. However, if AASHTO Type VI girder spacing is reduced to 4.5 ft (1.37 m), then the cost of the girders is about 65% of the in-place cost of girders and deck. The overall in-place cost with a girder spacing of 4.5 ft (1.37 m) is 45% higher than with a girder spacing of 10 ft (3.05 m).

Cost Effectiveness Comparisons

Optimum cost curves were used to compare the cost effectiveness of selected girders. Spans in excess of 80 ft (24.4 m) were investigated. Girder spacing considered ranged between 4.5 and 10 ft (1.37 and 3.05 m).

Comparisons of Girder Cross Sections

AASHTO Girders - Optimum cost curves for AASHTO Types IV, V, and VI girders are shown in Figure 15. For spans from 80 to 100 ft (24.4 to 30.5 m), the cost index per square foot is about the same for the three sections, when used at maximum girder spacing. Detailed analysis reveals that a Type IV girder can be used at a maximum girder spacing of 9.0 ft (2.74 m). Types V and VI girders can be used at the limiting maximum girder spacing of 10 ft (3.05 m).

Figure 15 indicates that for spans larger than 100, 125 and 140 ft (30.5, 38.1, and 42.7 m), the cost index increases rapidly for AASHTO girders Types IV, V, and VI, respectively. Maximum spans that could be achieved at the limiting minimum girder spacing of 4.5 ft (1.37 m) are 119, 144, and 158 ft (36.3, 43.9, and 48.2 m).

Modified AASHTO Girders - Optimum cost curves for Modified AASHTO Types IV, V and VI girders are shown in Figure 16. These girders have a 6-in (152 mm) thick web. Span capabilities of the Modified sections are comparable to those of the corresponding AASHTO girders. However, the modified girders lead to savings of about 6% on the overall cost of the in-place girders and deck.

Colorado Sections - Colorado's G54 and G68 girders are compared in Figure 17. For an 80 ft (24.4 m) span, with maximum girder spacing, the cost index is the same for both girders. Detailed analysis shows that maximum girder spacing is 8.2 and 9.0 ft (2.5 and 2.74 m) for G54 and G68 girders, respectively. At a girder spacing of 4.5 ft (1.37 m), maximum girder spans are 122 and 140 ft (37.2 and 42.7 m) for G54 and G68, respectively.



Figure 15 Optimum Cost Curves for AASHTO Girders

BEST DOCUMENT AVAILABLE



Figure 16 Optimum Cost Curves for Modified AASHTO Girders

BEST DOCUMENT AVAILABLE



Figure 17 Optimum Cost Curves for Colorado Girders and Modified G68/6 Girder

BEST DOCUMENT AVAILABLE

Modified Colorado Section - An optimum cost curve for Modified G68/6 girder is also plotted in Figure 17. This section is similar to G68 but has a 6 in (152 mm) web. Span capabilities are the same for G68 and G68/6. However, for similar spans, Girder G68/6 costs about 3% more than G68.

Washington Series - Cost comparisons of Washington Series girders are made in Figure 18. In the range of 80 to 90 ft (24.4 to 27.4 m), the cost is about the same for Series 80, 100, 120 and 14. Maximum girder spacing is 7.0, 7.5, 8.5, and 9.0 ft (2.13, 2.29, 2.59, and 2.74 m), respectively. At a girder spacing of 4.5 ft (1.37 m), maximum spans are 106, 122, 142, and 150 ft (32.3, 37.2, 43.3, and 45.7 m) for Series 80, 100, 120, and 14, respectively. Figure 18 shows that Series 14 girder is slightly more cost-effective than Series 120 girder. Newly developed Series 14 girder is a replacement for Series 120 girder.

Modified Washington Series - Modified Washington Series 80/6, 100/6, 120/6 and 14/6 girders are compared with Washington Series 80, 100, 120, and 14 in Figures 19a and 19b. The modified sections with 6 in (152 mm) web cost 3 to 5% more than similar sections having 5 in (127 mm) web. The higher costs correspond to the heavier sections. Apart from this cost difference, Washington Series girders and their modified counterparts have about same maximum span and maximum girder spacing capabilities.

Bulb-T's - Optimum cost curves for Anderson's Bulb-T's are plotted in Figure 20. For spans of 80 to 85 ft (24.4 to 25.9 m), the cost is about the same for BT48, BT60, and BT72. Maximum girder spacing for 80 ft (24.4 m) spans is 7.0, 8.0, and 8.8 ft (2.13, 2.44, and 2.68 m). At a girder spacing of 4.5 ft (1.37 m), maximum achievable spans are 100, 127, and 142 ft (30.5, 38.7, and 43.3 m).

Modified Bulb-T's - Modified Bulb-T's BT60/6 and BT72/6 girders are compared with BT60 and BT72 girders in the cost chart of Figure 21. Bulb-T's with 6-in (152 mm) thick webs cost about 4% more than Bulb-T's with 5-in (127 mm) thick webs.



Figure 18 Optimum Cost Curves for Washington Series

BEST DOCUMENT AVAILABLE



Figure 19.a Comparison of Optimum Cost Curves for Washington and Modified Washington Series

BEST DOCUMENT AVAILABLE



Figure 19.b Comparison of Optimum Cost Curves for Washington and Modified Washington Series

BEST DOCUMENT AVAILABLE



Figure 20 Optimum Cost Curves for Anderson's Bulb-T's

BEST DOCUMENT AVAILABLE



Figure 21 Comparison of Optimum Cost Curves for Bulb-T's and Modified Bulb-T's

BEST DOCUMENT AVAILABLE

Overall Comparisons - Optimum cost curves for AASHTO Type VI, Colorado's G68, Washington Series 14, and Bulb-T BT72 girders are compared in Figure 22. These girders are intended for use for spans in excess of 100 ft (30.5 m). Figure 22 indicates that Bulb-T BT72 is the most economical for spans up to 135 ft (41.2 m), and the AASHTO Type VI girder is the most expensive.

Modified Girders G68/6, Series 14/6, and BT72/6 are compared with AASHTO Type VI girder in Figure 23. For spans up to 140 ft (42.7 m), Modified Bulb-T BT72/6 is the most economic and is on the average about 3% cheaper than a Modified Series 14/6 girder.

Comparisons of cost index for sections plotted in Figures 22 and 23 relative to cost index of AASHTO Type VI girder are given in Table 1. These comparisons are made for different girder spans. Cost ratios for spans of 80 and 90 ft (24.4 and 27.4 m) are not shown because these heavy girders are not used for these spans. The cost ratios tabulated indicate that savings up to 20% can be achieved on the in-place total cost of girder and deck by using Bulb-T girders instead of the AASHTO Type VI girder. For spans in excess of 100 ft (30.5 m), Bulb-T 72, Washington Series 14, and Modified BT72/6 and Series 14/6 yield the least cost, the first being the most economical.

Web Thickness - The above comparisons between Bulb-T's, Washington Series, and Colorado G68 girders with 5-in (127 mm) thick webs and similar sections with 6-in (152 mm) thick webs indicate that girders with 6-in (152 mm) thick webs cost 3 to 5% more than similar girders having 5 in (127 mm) webs. However, sections with 6 in (152 mm) web would be easier to manufacture in all regions of the United States according to the survey results of Phase I. Their lateral stiffness is also improved. Therefore, they would be more stable during transportation.

Modified Bulb-T's and Modified Washington Series - Optimum cost curves for Modified Bulb-T's and Modified Washington Series girders are plotted in Figure 24. Up to spans of 140 ft (42.7 m), Modified Bulb-T's are most economical. For spans



Figure 22 Comparison of Optimum Cost Curves for AASHTO Type VI, Colorado G68, Washington Series 14 and Bulb-T BT72

BEST DOCUMENT AVAILABLE



Figure 23 Comparison of Optimum Cost Curves for AASHTO Type VI and Modified G68/6, Series 14/6 and BT 72/6 Girders

BEST DOCUMENT AVAILABLE

TABLE 1 - COST RELATIVE TO TYPE VI GIRDER

Cross Section	Span, ft				
	100	110	120	130	140
AASHTO Type VI	1.00	1.00	1.00	1.00	1.00
Colorado G68	0.86	0.87	0.90	0.96	1.01
Wash. Series 14	0.83	0.83	0.86	0.90	0.92
Bulb-T BT72	0.79	0.80	0.83	0.89	0.95
Mod. G68/6	0.88	0.89	0.93	0.98	1.06
Mod. Ser. 14/6	0.86	0.86	0.90	0.94	0.98
Mod. BT72/6	0.83	0.83	0.87	0.92	0.98

1 ft = 0.305 m

BEST DOCUMENT AVAILABLE



Figure 24 Comparison of Optimum Cost Curves for Modified Bulb-T's and Modified Washington Series

BEST DOCUMENT AVAILABLE

from 140 to about 150 ft (42.7 to 45.7 m), Modified Series 14/6 is slightly cheaper than Modified BT72/6.

Modified Bulb-T's and AASHTO Girders - Modified Bulb-T's are compared to the AASHTO Sections in Figure 25. For spans from 80 to 120 ft (24.4 to 36.6 m), Modified Bulb-T's yield savings of about 17% over the AASHTO girders. For spans of 120 to 140 ft (36.6 to 42.7 m), cost savings vary from 17 to 2%. These comparisons indicate that considerable savings can be achieved by using Modified Bulb-T's rather than AASHTO girders for spans up to 140 ft (42.7 m).

Effect of Concrete Strength

In all the above comparisons, the girder's concrete compressive strength was assumed to be 6000 psi (41.4 MPa). Some girders were analyzed assuming 5000 and 7000 psi (34.5 and 48.3 MPa) concrete. The effect of concrete compressive strength on optimum cost curves is illustrated in Figures 26 and 27. These figures indicate that by increasing the girder's concrete compressive strength, maximum span capability of a section is increased.

By increasing the concrete compressive strength from 5000 to 7000 psi (34.5 to 48.3 MPa), the maximum span of AASHTO Type IV girder is increased by about 15 ft (4.6 m). For AASHTO Type VI girder, maximum span range is increased by about 22 ft (6.7 m). This is equivalent to increasing the span capability by about 7% for each 1000 psi (6.9 MPa). However, this increase in span capability is associated with an increase in cost per unit area of bridge deck.

Effect of Bundling Strands

In all the above comparisons, strands were assumed spaced 2 in (50.8 mm) on center at midspan. Strands were positioned as low as possible in the section to obtain maximum eccentricity of prestressing force. Colorado G54 and AASHTO Type VI girders were also analyzed assuming that strands were bundled. They were positioned 1/2 in (127 mm) on center to produce maximum eccentricity of prestress. Minimum clear concrete cover for



Figure 25 Comparison of Optimum Cost Curves for Modified Bulb-T's and AASHTO Girders

BEST DOCUMENT AVAILABLE



Figure 26 Variation of Optimum Cost Curves with Concrete Compressive Strength for AASHTO Type IV Girder

BEST DOCUMENT AVAILABLE



Figure 27 Variation of Optimum Cost Curves with Concrete Compressive Strength for AASHTO Type VI Girder

BEST DOCUMENT AVAILABLE

strands was assumed to be 1-3/4 in (44.5 mm). For analysis of bundled strands, strands were assumed placed next to each other in rows. The first row was assumed positioned 2 in (50.8 mm) from the bottom of the girder, and subsequent rows 1/2 in (12.7 mm) on center.

The effect of bundling strands on cost index is illustrated in Figures 28 and 29. Optimum cost curves for Colorado G54 girder with strands spaced 2 in (50.8 mm) on center, and with bundled strands are shown in Figure 28. Similar curves for AASHTO Type VI girder are shown in Figure 29.

Analysis of Colorado's G54 section assuming a girder spacing of 4.5 ft (1.37 m) and strands spaced 2 in (50.8 mm) on center indicates that maximum span is 122 ft (37.2 m) and corresponding number of strands is 37. When strands are bundled, maximum span is 125 ft (38.1 m) and corresponding number of strands is 35. Therefore, the effect of strand bundling is negligible.

Of all sections analyzed, AASHTO Type VI girder required the largest number of strands. When strands are spaced 2 in (50.8 mm) on center, maximum span is 158 ft (48.2 m). Corresponding number of strands is 67. When strands are bundled, maximum span is 160 ft (48.8 m) and number of strands is 55. The overall cost savings resulting from reduction in number of strands are negligible. Increase in span capability due to bundling of strands is also negligible.

Governing Design Criteria

Output from Program BRIDGE included concrete stress in top and bottom fibers at midspan at transfer and service load and flexural strength of member. A study of these concrete stresses and required flexural strength revealed that in all cases considered, design was governed by bottom concrete stress at midspan under service load. In Program BRIDGE, this concrete stress was limited to a tension of $6\sqrt{f'_c}$ psi ($0.5\sqrt{f'_c}$ MPa).

The above observation was also made by Aswad.[22] He found that for spans up to about 72 ft (22 m), strength design governs. For spans in excess of 72 ft (22 m), bottom concrete



Figure 28 Effect of Strands Bundling on Optimum Cost Curves for Colorado G54 Girders

BEST DOCUMENT AVAILABLE



Figure 29 Effect of Strands Bundling on Optimum Cost Curves for AASHTO Type VI Girder

BEST DOCUMENT AVAILABLE

stress at service load governs. Based on the above observation, preliminary design of bridges can be accelerated by satisfying midspan bottom concrete stresses under service loads. Other stress and strength requirements can then be checked. Bottom concrete stress at midspan will also control when no tensile concrete stress is allowed under service load.

As the bottom concrete stress at midspan due to service load controls the design of spans in excess of 80 ft (24.4 m), the aim of any optimization should be to maximize the composite modulus of section for bottom fibers. Efficiency factor or efficiency ratio as discussed under "STRUCTURAL EFFICIENCY" should be a function of the composite modulus of section for bottom fibers. Therefore, girder spacing should be considered when determining efficiency of a girder cross-section.

Shear Design Considerations

Program BRIDGE determines the number of strands that satisfy flexural service load stresses and strength requirements. No attempt was made to incorporate shear design in the program because this was outside the scope of this project. Shear design is a tedious task for the prestressed concrete bridge designer. The problem is further complicated when adjacent spans built with precast prestressed members are made continuous for live load only.

Simplified calculations were made to check whether end blocks might be required for the sections recommended in this report. Nine selected cases judged to produce the highest nominal shear stress were analyzed. Girders were assumed simply supported. End shear was assumed equal to values of end reactions given in Appendix A of the AASHTO Specifications.[8]

Table 2 summarizes the nominal shear stress calculated for the nine cases analyzed. The level of nominal shear stress is well within the minimum allowable value of $9.7\sqrt{f'_c}$ psi ($0.81\sqrt{f'_c}$ MPa) given in the Interim 1980 AASHTO Specifications.[12] Based on shear design considerations, end blocks are not needed in any of these sections, including the Washington Series 14 and Bulb BT72 with 5 in (127 mm) webs. However, detailed shear design

TABLE 2 - NOMINAL SHEAR STRESS

Case No.	Girder	Span (ft)	Girder Spacing (ft)	Nominal Shear v_u, psi	$v_u/\sqrt{f'_c}$*
1	AASHTO Type IV	100	8.0	520	6.7
2	AASHTO Type VI	110	8.0	447	5.8
3	AASHTO Type VI	120	10.0	561	7.2
4	AASHTO Type VI	140	8.0	533	6.9
5	Bulb-T BT72	110	8.0	625	8.0
6	Mod BT72/6	110	8.0	533	6.9
7	Wash. Ser. 14	110	8.0	622	8.0
8	Wash. Ser. 14	140	4.5	475	6.1
9	Mod. Ser. 14/6	110	8.0	531	6.9

*Value of concrete compressive strength, f'_c, assumed 6000 psi.

1 ft = 0.305 m; 1 psi = 6.895 kPa

BEST DOCUMENT AVAILABLE

is necessary, for each bridge, and particularly when adjacent spans are made continuous for live load.

SI CONVERSION

Recently, new SI (metric) sections were adopted in Canada under an arrangement agreed to by the prestressed concrete producers. For an unspecified period of time, bridges in Canada will be designed using the new sections, but alternate designs will be provided based on existing non-metric sections. Since the new sections are more efficient than the existing ones, it was felt that the changeover would be accelerated by the competitive need to use the new sections. Dimensions and sectional properties of the old and new Canadian sections are given in Appendix C.

CONCLUSIONS

Based on the survey of Phase I and cost-analyses of Phase II, the following conclusions are made.

1. In all states surveyed except California, the most economical bridges for spans of approximately 70 to 130 ft (21.3 to 39.6 m) are constructed with pretensioned bridge girders. In California, cast-in-place post-tensioned box girder bridges are most economical.
2. When compared with other sections, AASHTO standard bridge girders are not the most structurally efficient or cost-effective for spans of 80 to 140 ft (24.4 to 42.7 m).
3. Because of transportation restrictions, maximum spans made of single units are limited to about 140 ft (42.7 m). Longer spans are possible by splicing girders.
4. Intermediate diaphragms are not needed. End diaphragms are sufficient.
5. For girders with 5-in (127 mm) thick webs, the most cost-effective sections are Bulb-T's. For spans from 80 to 120 ft (24.4 to 36.6 m), Bulb-T's have 20% less in-place cost of girder and deck compared to AASHTO

girders. For spans of 120 to 135 ft (36.6 to 41.2 m), the cost reduction for Bulb-T's varies from 20 to 5%. Next most cost-effective sections with 5-in (127 mm) thick webs are the Washington series.

6. In most regions of the United States, it may not be easy to consolidate the concrete in girders with 5-in (127 mm) thick webs. Moreover, in these girders, strands must be bundled at midspan and end blocks are needed to conform with minimum concrete cover requirements.
7. By using girders with 6-in (152 mm) thick webs, it will be possible to consolidate the concrete in these girders in all regions of the United States.
8. Use of 6-in (152 mm) thick webs instead of 5 in (127 mm) in Bulb-T's, Washington series, and Colorado G68 girders increases overall in-place cost of girder and deck by 3 to 5%.
9. For girders with 6-in (152 mm) thick webs, most cost-effective sections are Modified Bulb-T's. For spans of 80 to 120 ft (24.4 to 36.6 m), Modified Bulb-T's have 17% less in-place cost of girder and deck compared to AASHTO girders. For spans of 120 to 140 ft (36.6 to 42.7 m), the cost reduction varies from 17 to 2%.
10. Next to Modified Bulb-T's, modified Washington Series girders with 6-in (152 mm) thick webs are the most cost-effective sections. For spans from 80 to 120 ft (24.4 to 36.6 m), overall reduction of the in-place cost of girder and deck is 14%. For spans of 120 to 140 ft (36.6 to 42.7 m), cost reduction ranges from 14 to 2%, compared to the AASHTO girders.
11. Reduction of top and bottom flange widths and web thicknesses of AASHTO Types IV, V and VI girders by 2 in (50.8 mm) reduces overall in-place cost of girders and deck by about 6%. Span capability of the

modified sections is not affected by this change in width.

12. The overall in-place cost of girders and deck is decreased substantially by placing girders at the largest practical girder spacing.
13. Increase of girder's concrete compressive strength from 5000 to 7000 psi (34.5 to 48.3 MPa) increases the span capability of AASHTO girders by about 15%.
14. Bundling of strands at midspan in order to increase eccentricity of prestress does not lead to any significant overall cost reduction for girders considered.

RECOMMENDATIONS

Based on the cost-analysis results discussed in the report and the above conclusions, the following are recommended:

1. Modified Bulb-T girders with 6-in (152 mm) thick webs are recommended for use as national standard precast prestressed concrete bridge girders in the United States for spans from 80 to 140 ft (24.4 to 42.7 m).
2. If metrication is adopted, modification of the above sections to SI (metric) units should be considered as part of any standardization.
3. Girder spacing should be as large as possible.
4. A synthesis report is needed on techniques available for splicing girders for spans in excess of 135 ft (41.2 m).
5. Although lightweight concrete was not considered in this investigation, it should be given more consideration for bridges built with precast prestressed concrete girders and cast-in-place concrete deck. Lightweight concrete has a cost premium above that of normal weight concrete. However, overall weight reduction can lead to cost savings.
6. Lateral stability of long span girders should be investigated to determine critical lengths beyond which girders should be braced laterally during transportation and erection.

IMPLEMENTATION

Construction of the Interstate highway system has been completed in a few states. In most states, it is close to completion. Therefore, the rate of bridge construction on the interstate highway is much slower than in the period between late 1950's and early 1970's. However, according to statistics prepared by the Bridge Division, Federal Highway Administration, U.S. Department of Transportation, considerable new bridge construction and major reconstruction is ongoing.

The cost of new prestressed concrete bridge construction and major reconstruction with participation of federal funds authorized during calendar year 1980 totaled $695 million. Based on bridge inventory and inspection records, it is anticipated that "in the next 20 to 30 years, we will have over $30 billion worth of bridge construction based on the value of the dollar today."[26]

As mentioned earlier, selection of bridge type is based on economy. Safety standards for interstate and other high speed highways require greater clearances. Therefore, there is need for construction of bridges with spans of 110 to 130 ft (33.5 to 39.6 m). In all states surveyed except California, most economical bridges for spans of approximately 70 to 130 ft (21.3 to 39.6 m) were constructed with pretensioned bridge girders.

Cost analyses discussed earlier indicate that modified Bulb-T's can yield savings of 17% on the overall cost of girder and deck compared to AASHTO girders. This is in addition to the fact that the Modified Bulb-T's are about 35% lighter than AASHTO girders for comparable spans. A 140 ft (42.7 m) AASHTO Type VI girder is extremely heavy and therefore very difficult to transport on highways. Lighter sections with 140 ft (42.7 m) have been transported on highways.

Steel forms constitute a capital investment. However, their life span is limited to about 10 years. Cost savings resulting from use of optimized girders should be adequate to cover the cost of new forms over a period of a few years in areas where AASHTO girders are used. Where new forms are needed, new plants

built, or improved sections sought, optimized sections should be considered.

Implementation of new sections should be gradual over a period of time. It will require effort on the part of both Departments of Transportation and producers. Preparation of design aids for the new sections will encourage and facilitate implementation of the new sections.

Highway agencies should be informed of economic benefits that can be achieved with optimized sections. Departments of Transportation will have to design with old and new sections over a transition period. The Canadian experience in switching to new metric sections sets an example of implementation of new sections under an arrangement agreeable to producers and highway agencies.

REFERENCES

1. Lin, T.Y., "Design of Prestressed Concrete Structures", John Wiley and Sons, Inc., New York, N.Y., Second Edition, 1963, 614 pp.

2. U. S. Department of Commerce, Bureau of Public Roads, Annual Reports for Fiscal Years 1954 through 1957.

3. "Precast Concrete Elements for Transportation Facilities", National Cooperative Highway Research Program, Synthesis of Highway Practice No. 53, 1978, 48 pp.

4. Somerville, G. and Tiller, R.M., "Standard Bridge Beams for Spans from 7m to 36m", Cement and Concrete Association, Publication No. 32.005, 1971, 32 pp.

5. Lie, Erik, "Prefabrikerte broer standardisering og nytenkning" (Prefabricated Bridges--Standardization and New Ideas), Nordisk Betong, Vol. 24, No. 3, 1980, pp. 81-84.

6. Rabbat, B.G., Saatcioglu, M., and Russell, H.G., "Optimized Sections for Major Prestressed Concrete Bridge Girders - Phase I", Interim Report prepared by Construction Technology Laboratories for U.S. Department of Transportation, Federal Highway Administration, April 1981, 80 pp.

7. Private Correspondence with Messrs. C. S. Gloyd and G. Markich, State of Washington, Department of Transportation, February 1981.

8. "Standard Specifications for Highway Bridges", American Association of State Highway and Transportation Officials, Twelfth Edition, Washington, D.C., 1977.

9. Sithichaikasem, S. and Gamble, W.L., "Effects of Diaphragms in Bridges with Prestressed Concrete I-Section Girders", University of Illinois, Civil Engineering Studies, Structural Research Series No. 383, February 1972, 287 pp.

10. Wong, A.Y.C. and Gamble, W.L., "Effects of Diaphragms in Continuous Slab and Girder Highway Bridges", Civil Engineering Studies, Structural Research Series 391, University of Illinois at Urbana-Champaign, May 1973, 123 pp.

11. Scott, N.L., "Suggestions for Reducing Costs in Prestressed Concrete Bridges", Highway Research Record No. 34, 1963, p. 117-129.

12. "Interim Specifications for Highway Bridges", American Association of State Highway and Transportation Officials, 1979.

13. Koretzky, H.P., "What Has Been Learned from the First Prestressed Concrete Bridges - Repair of Such Bridges", Transporttion Research Record No. 664, 1978, p. 37-46.

14. Pierce, L.F., "Esthetics and Standardization in Bridges", Paper presented at ASCE Convention, Atlanta, Georgia, October 23-25, 1979, Preprint No. 3788, 22 pp.

15. Anderson, A.R., "Stretched-Out, AASHO-PCI Beams Types III and IV for Longer Span Highway Bridge", Journal of the Prestressed Concrete Institute, September 1973, p. 32-49.

16. Gamble, W.L., "Design Guide for Prestressed Concrete Long-Segment Bridge Girders", Civil Engineering Studies, Structural Research Series No. 464, University of Illinois at Urbana-Champaign, June 1979, 83 pp.

17. Fadl, A.I., Gamble, W.L., and Mohraz, B., "Tests of a Precast Post-Tensioned Bridge Girder Having Two Spans of 124 Feet", Civil Engineering Studies, Structural Research Series No. 459, University of Illinois at Urbana-Champaign, February 1979, 246 pp.

18. Rabbat, B.G., Kaar, P.H., Russell, H.G., and Bruce, R.N., Jr., "Fatigue Tests of Pretensioned Girders with Blanketed and Draped Strands", Journal of the Prestressed Concrete Institute, July 1979, p. 88-114.

19. "Use of Debonded Strands in Pretensioned Bridge Members", Report prepared by D.G. Horn for PCI Committee on Bridges, to be published.

20. Anderson, A.R., "Systems Concepts for Precast and Prestressed Concrete Bridge Construction", Highway Research Board, Special Report 132, 1972, pp. 9-21.

21. Guyon, Y., "Prestressed Concrete", John Wiley and Sons, Inc., New York, 1953, 543 pp.

22. Aswad, A., "An Efficiency Criterion for Pretensioned I-Girders", to be published.

23. Muller, J., "Lateral Stability of Precast Members During Handling and Placing", Journal of the Prestressed Concrete Institute, February 1962, p. 20-31.

24. Swann, R.A. and Godden, W.G., "The Lateral Buckling of Concrete Beams Lifted by Cables", The Structural Engineer, London, Vol. 44, No. 1, January 1966.

25. Barker J., Chairman, Minutes of PCI Bridge Committee Meeting held on April 15, 1980, at the Ramada O'Hare Inn, Des Plaines, Illinois.

26. Herr, L.A. and Sears, F.D., "Bidding and Contract Arrangement in Bridge Construction", Journal of the Prestressed Concrete Institute, July-August 1980, pp. 38-40.

27. "Prestressed Concrete Design Manual", Bureau of Design, Division of Highways, State of Illinois, 1979.

28. "Bridge Design Manual, Reinforced Concrete Superstructure", Vol. 2 Design Aids, State of Washington, Department of Transportation, p. 5-305, September 1975.

29. "Notes on ACI 318-77 Building Code Requirements", Portland Cement Association, 716 pp., 1980.

30. Furr, H.L., Sinno, R., and Ingram, L.L., "Prestress Loss and Creep Camber in a Highway Bridge with Reinforced Concrete Slabs on Pretensioned Prestressed Concrete Beams", Research Report No. 69-3, Texas A & M University, 144 pp., October 1968.

APPENDIX A - SURVEY PARTICIPANTS

Highway agencies and producers selected for the survey are listed below. In all cases, the survey was initiated through telephone conversations. In addition, site surveys were made where indicated by "(S)".

Highway Agencies

1. State of California, Department of Transportation. (S)
2. State of Colorado, State Department of Highways.
3. State of Illinois, Department of Transportation. (S)
4. State of Louisiana, Department of Transportation and Development.
5. Oregon State Highway Division. (S)
6. Commonwealth of Pennsylvania, Department of Transportation. (S)
7. State of Tennessee, Department of Transportation.
8. State of Texas, State Department of Highways and Public Transportation. (S)
9. Commonwealth of Virginia, Department of Highways and Transportation. (S)
10. Washington State, Department of Transportation. (S)
11. State of Wisconsin, Department of Transportation. (S)

Producers

12. Concrete Technology Associates, Tacoma, Washington. (S)
13. Prestressed Concrete Operations, St. Regis Paper Company, Iowa Falls, Iowa.
14. Stanley Structures, Denver, Colorado. (S)

APPENDIX B - SURVEY OUTLINE

In order to conduct efficient and systematic site surveys, an outline of required information was prepared. It covers all items discussed under Phase I of the Research Approach. Survey outline is reproduced below. Results of the survey are presented in the body of the report.

Design and Construction Details

1. Solid-form sections used in the State
   - Which AASHTO-PCI sections
   - Other sections and corresponding span range
   - When developed
   - When first pretensioned bridge built
   - When first post-tensioned bridge built
   - Any effort presently to modify/improve sections
   - Would State consider improved sections, if developed
   - Obtain drawings of sections
2. Longest spans built using single pretensioned girders
3. End blocks required
   - When used
4. How bursting (end splitting) reinforcement designed
5. End diaphragms used
   - Policy for intermediate diaphragms
6. Is tension in concrete under service load permitted
   - How much
   - When adopted
7. Concrete Properties
   - Strength at release f'_{ci}
   - 28 day strength f'_c
   - Density of normal weight concrete
   - Lightweight concrete for bridge girders
   - Lightweight concrete for decks
   - f'_c lightweight
   - Density of lightweight concrete

8. Strand Properties
   - Size
   - Grade
   - Surface condition
   - Stress-relieved, low-relaxation
   - Where strands manufactured
9. Maximum girder spacing
10. Maximum allowable camber and differential camber
11. Types of decks
   - Cast-in-place
   - Precast deck panels
   - Permanent forms, steel or concrete
   - Maximum deck thickness
   - Bent-up bars in deck
12. Design Loads
   - HS20-44
   - Other loads
13. Design aids for bridge designers
   - Tables or charts
14. Does adequacy of manufacturers, erectors, contractors influence decision regarding type of bridge.
15. Does State permit (or encourage) contractor/supplier alternate designs to reduce overall cost? (emphasis on fabrication details and erection procedure)

Fabrication Details

1. Minimum spacing between strands (center to center)
2. Minimum concrete cover
3. Limitation on web thickness
4. Stability during handling
5. Restrictions on draping locations
6. Precasting plants
   - How many within State
   - Use of out of state
   - Licensed by State

7. Turn-around time for prestressing beds
8. Crane capacity in plant
9. Any new developments in prestressing hardware systems

Transportation Requirements and Restrictions

1. Maximum girder length without permit
   - Maximum transported
2. Maximum girder weight without permit
   - Maximum weight of girders transported
3. Availability of moving equipment
4. Instability during transportation

Availability and Costs

1. Cost in-place per lineal foot of girder (each section)
2. Cost in place per square foot of deck
3. Cost per square foot of superstructure
4. Cost variation due to concrete strength f'_c
5. Prestressing beds, steel forms
   - Initial cost
   - Life span
   - End blocks - how incorporated
   - effect on cost
6. Labor (plant, site)
   - Availability, skilled
   - Wages
7. What could be done to cut down on cost
8. How manufacturers estimate cost
9. Haul costs $/kip/mile - Freight tariff steps
10. State unit prices for cost estimate
11. Cranes at construction site
    - Availability
    - Capacity
    - Costs

Structural Durability

1. Design life span
2. Frequency of inspection
3. Problems encountered (and frequency)
4. Cracks in prestressed concrete girders

Aesthetics and Safety

1. Aesthetics requirements
2. Safety requirements

Opinions and Policies

1. Opinions and policies of local authorities, including industry regarding selection and use of major prestressed concrete girders

New Concepts

1. New concepts related to design, manufacture, erection or construction of pretensioned bridge girders
2. Blanketing or debonding of strands
   - Used
   - Why not
   - Draping satisfactory
3. Has splicing of pretensioned I, or T-segments been used
   - If yes, longest spans achieved
   - If not, has it been considered
4. Combination pretensioning and post-tensioning of single (non-spliced) units
5. Precast prestressed deck panels as permanent forms
6. Possible use of lightweight concrete

Other

1. Trade-offs between I, box and steel sections
2. Projections on future bridge construction (pretensioned girders)
   - Spans
   - Volume
3. Criteria for optimization
4. What can be done to make pretensioned bridge construction more attractive and more economical

APPENDIX C - GIRDER PROPERTIES

Dimensions and properties of standard bridge girder sections used by the survey participants are presented in this Appendix. Table 3 lists the sectional dimensions. Notations appearing in this table are identified in the sketches of Figure 30. Dimensions of the new Canadian standard metric prestressed I-Girders are listed in Table 4. These sections were approved by the Canadian Prestressed Concrete Institute in October 1979.

Properties of sections appearing in Tables 3 and 4 are listed in Tables 5 and 6, respectively. Standard sectional property notations have been used. They are defined as follows:

y_t = Distance from centroid of girder to top concrete fiber

y_b = Distance from centroid of girder to bottom concrete fiber

S_t = Modulus of section for top concrete fiber

S_t = Modulus of section for bottom concrete fiber

Efficiency factors α and ρ have been suggested by Aswad[22] and Guyon[21], respectively. They are defined as follows:

$$\alpha = \frac{3.46\, S_b}{A \cdot h}$$

$$\rho = \frac{r^2}{y_t \cdot y_b} = \frac{S_b}{A \cdot y_t}$$

Approximate span range capabilities of each girder section are also shown in Tables 5 and 6. The span range varies with the concrete compressive strength at transfer and at 28 days.



a. I - Section



b. T - Section

Figure 30 Nomenclature for Cross-Sectional Dimensions Shown in Tables 3 and 4

BEST DOCUMENT AVAILABLE

TABLE 3 - CROSS-SECTIONAL DIMENSIONS

Agency	Girder Type	Dimension*, in												
		a	b	c	d	e	f	g	h	j	w	x	y	z
AASHTO-PCI	Type I	12	4	3	-	11	5	5	28	16	6	3	-	5
	Type II	12	6	3	-	15	6	6	36	18	6	3	-	6
	Type III	16	7	4.5	-	19	7.5	7	45	22	7	4.5	-	7.5
	Type IV	20	8	6	-	23	9	8	54	26	8	6	-	9
	Type V	42	5	3	4	33	10	8	63	28	8	4	13	10
	Type VI	42	5	3	4	42	10	8	72	28	8	4	13	10
California	3'-0"	19	3	6	-	15	6	6	36	19	7	6	-	6
	3'-6"	19	3	6	-	21	6	6	42	19	7	6	-	6
	4'-0"	19	3	6	-	27	6	6	48	19	7	6	-	6
	4'-6"	19	3	6	-	33	6	6	54	19	7	6	-	6
	5'-0"	19	3	6	-	39	6	6	60	19	7	6	-	6
	5'-6"	19	3	6	-	45	6	6	66	19	7	6	-	6
Colorado	G54	28	5.5	1.5	2	33.5	5	6.5	54	24	6	2	9	8.5
	G68	28	5.5	1.5	2	49	3.5	6.5	68	24	5	2	9.5	8.5
Illinois	36"	12	4	3	-	17	6	6	36	18	6	3	-	6
	42"	16	4	2.5	-	21.5	8	6	42	22	6	5	-	8
	48"	18	4	2.63	-	27.12	7.25	7	48	22	7.5	5.25	-	7.25
	54"	20	6	3	-	30.75	7.25	7	54	22	6	7	-	8

*Notations are identified in Figure 30

1 in = 25.4 mm

BEST DOCUMENT AVAILABLE

TABLE 3 - CROSS-SECTIONAL DIMENSIONS

(Cont.)

Agency	Girder Type	Dimension*, in												
		a	b	c	d	e	f	g	h	j	w	x	y	z
Iowa	A30-A46	13	4	1	-	16	6	5	32	17	6	3.5	-	5.5
	A50-A55	16	4	1	-	16	6	5	32	20	9	3.5	-	5.5
	B34-B59	13	5	1	-	20	6	7	39	17	6	3.5	-	5.5
	B63-B67	16	5	1	-	20	6	7	39	20	9	3.5	-	5.5
	C30-C67	13	5	1	-	25	6	8	45	17	6	3.5	-	5.5
	C71-C80	16	5	1	-	25	6	8	45	20	9	3.5	-	5.5
	D35-D95	20	6	1	-	31.5	7.5	8	54	22	7	6.5	-	7.5
Louisiana	AASHTO-PCI Types II, III, and IV													
Oregon	AASHTO-PCI Types II, III, and IV													
	Type V	20	8	6	-	32	9	8	63	26	8	6	-	9
	BT 65"	48	2.5	2.5	3	48	4	5	65	24	7.5	3	17.25	8.25
	BT 72"	48	2	3	2	56	3	6	72	26	6	2	19	10
	I 84"	24	6	6	-	60	6	6	84	24	7.5	8.25	-	8.25
Pennsylvania	20/30	14	3	3	-	12	8	4	30	20	8	3	-	6
	20/33	14	4	3	-	12	8	6	33	20	8	3	-	6
	20/36	14	5	3	-	12	8	8	36	20	8	3	-	6
	20/39	14	8	3	-	12	8	8	39	20	8	3	-	6
	24/33	18	4	3	-	12	8	6	33	24	12	3	-	6
	24/36	18	5	3	-	12	8	8	36	24	12	3	-	6

*Notations are identified in Figure 30

1 in = 25.4 mm

BEST DOCUMENT AVAILABLE

TABLE 3 - CROSS-SECTIONAL DIMENSIONS

(Cont.)

Agency	Girder Type	Dimension*, in												
		a	b	c	d	e	f	g	h	j	w	x	y	z
Pennsylvania	24/42	18	4	4	-	17	10	7	42	24	8	5	-	8
	24/45	18	7	4	-	17	10	7	45	24	8	5	-	8
	24/48	18	8	4	-	17	10	9	48	24	8	5	-	8
	24/51	18	11	4	-	17	10	9	51	24	8	5	-	8
	24/54	18	14	4	-	17	10	9	54	24	8	5	-	8
	26/33	20	4	3	-	12	8	6	33	26	14	3	-	6
	26/36	20	5	3	-	12	8	8	36	26	14	3	-	6
	26/60	26	6	6	-	29	10	9	60	26	10	8	-	8
	26/63	26	9	6	-	29	10	9	63	26	10	8	-	8
	28/63	AASHTO-PCI Type V												
Tennessee		AASHTO-PCI Types I, II, III, and IV												
Texas	A	12	4	3	-	11	5	5	28	16	6	3	-	5
	B	12	5.5	2.75	-	14	5.75	6	34	18	6.5	2.75	-	5.75
	C	14	6	3.5	-	16	7.5	7	40	22	7	3.5	-	7.50
	48	14	3.5	4	-	29.5	4	7	48	14	6	4	-	4
	54	16	4	5	-	32	5	8	54	16	6	5	-	5
	60	18	4.5	5.5	-	35.5	5.5	9	60	18	7	5.5	-	5.5
	66	20	5	6.5	-	38	6.5	10	66	20	7	6.5	-	6.5
	72	22	5.5	7.5	-	40.5	7.5	11	72	22	7	7.5	-	7.5
	IV	AASHTO-PCI Type IV												

*Notations are identified in Figure 30

1 in = 25.4 mm

BEST DOCUMENT AVAILABLE

TABLE 3 - CROSS-SECTIONAL DIMENSIONS

(Cont.)

Agency	Girder Type	Dimension*, in												
		a	b	c	d	e	f	g	h	j	w	x	y	z
Virginia	AASHTO-PCI Types III, IV, V, and VI													
	T 34"	Max. 48"	4	3	-	27	-	-	34	12	12	3	15	-
Washington	Series 40	14	3.5	1.5	-	21	2	4	32	16	5	4.5	-	5.5
	Series 60	14	3.5	1.5	-	30	2	5	42	19	5	4.5	-	7
	Series 80	19	5	2	-	34	3	6	50	24	5	7	-	9.5
	Series 100	24	5	2	-	42	3	6	58	24	5	9.5	-	9.5
	Series 120	28	4	1.5	2	57	3	6	73.5	24	5	2	9.5	9.5
	Series 14	42	2.87	2.63	2	57	3	6	73.5	24	5	2	16.5	9.5
Wisconsin	AASHTO-PCI Types II, III, and IV													
	70"	30	6	1.5	2	49.5	3.5	7.5	70	26	6	2	10	10
Ontario (Canada)	AASHTO-PCI Types II, and III													
	CPCI IV	22	6	3	-	31.5	6.5	7	54	26	7	7.5	-	9.5
	CPCI IV+4	22	10	3	-	31.5	6.5	7	58	26	7	7.5		9.5
	ONT 90	36	5	3	3	63	8	8	90	26	8	3	11	9
	MOD. ONT 90	37	5	2	3	69	4	7	90	27	7	3	12	10

*Notations are identified in Figure 30

1 in = 25.4 mm

BEST DOCUMENT AVAILABLE

TABLE 3 - CROSS-SECTIONAL DIMENSIONS

(Cont.)

Cross Section Identification	Dimension*, in												
	a	b	c	d	e	f	g	h	j	w	x	y	z
Anderson BT 48	48	1	3.0	2	33	3	6	48	24	5	2	19.5	9.5
BT 60	48	1	3.0	2	45	3	6	60	24	5	2	19.5	-
BT 72	48	1	3.0	2	57	3	6	72	24	5	2	19.5	9.5
Modified AASHTO													
Type IV	18	8	6	-	23	9	8	54	24	6	6	-	9.0
Type V	40	5	3	4	33	10	8	63	26	6	4	13	10.0
Type VI	40	5	3	4	42	10	8	72	26	6	4	13	10.0
Modified Colorado													
G68/6	28	5.5	1.5	2	49	3.5	6.5	68	24	6	2	9.0	8.0
Modified Washington													
Series 80/6	19	5	2	-	34	3	6	50	24	6	6.5	-	9.0
Series 100/6	24	5	2	-	42	3	6	58	24	6	9.0	-	9.0
Series 120/6	28	4	1.5	2	57	3	6	73.5	24	6	2	9	9.0
Series 14/6	42	2.87	2.63	2	57	3	6	73.5	24	6	2	16.0	9.0
Modified Bulb-T													
BT 48/6	48	2	2	2	33	3	6	48	24	6	2	19.0	9.0
BT 60/6	48	2	2	2	45	3	6	60	24	6	2	19.0	9.0
BT 72/6	48	2	2	2	57	3	6	72	24	6	2	19.0	9.0

*Notations are identified in Figure 30

1 in = 25.4 mm

BEST DOCUMENT AVAILABLE

TABLE 4 - DIMENSIONS OF NEW CPCI METRIC SECTIONS

Agency	Girder Type	Dimension*, mm												
		a	b	c	d	e	f	g	h	j	w	x	y	z
CPCI Canadian Metric Sections	900	300	150	30	-	480	90	150	900	450	150	75	-	150
	1200	400	150	50	-	700	120	180	1200	550	150	125	-	200
	1200	400	150	50	-	700	120	180	1200	550	150	125	-	200
	1400	550	150	80	-	840	150	180	1400	650	150	200	-	250
	1900	900	125	50	75	1300	150	200	1900	650	150	75	300	250
	1900A	930	125	50	75	1300	150	200	1900	680	180	75	300	250
	2300	900	125	50	75	1700	150	200	2300	650	150	75	300	250
	2300A	930	125	50	75	1700	150	200	2300	680	180	75	300	250

*Notations are identified in Figure 30

1 mm = 0.0394 in

BEST DOCUMENT AVAILABLE

TABLE 5 - CROSS-SECTIONAL PROPERTIES

Agency	Girder Type	h (in)	y_t (in)	y_b (in)	Area (in^2)	S_{t_3} (in^3)	S_{b_4} (in^4)	Inertia (in^4)	α	ρ	Span Range* (ft)
AASHTO-PCI	Type I	28	15.41	12.59	276	1,476	1,807	22,750	0.81	0.42	30 - 45
	II	36	20.17	15.83	369	2,528	3,220	50,980	0.84	0.43	40 - 60
	III	45	24.73	20.27	560	5,070	6,186	125,390	0.85	0.45	55 - 80
	IV	54	29.27	24.73	789	8,908	10,543	260,730	0.86	0.46	70 - 120
	V	63	31.04	31.96	1,013	16,791	16,307	521,180	0.88	0.52	90 - 140
	VI	72	35.62	36.38	1,085	20,587	20,157	733,320	0.89	0.52	110 - 150
California	3'-0"	36	18.9	17.1	432	3,350	3,700	63,300	0.82	0.45	50 - 55
	3'-6"	42	22.0	20.0	474	4,320	4,750	95,000	0.83	0.46	55 - 65
	4'-0"	48	25.2	22.8	516	5,450	6,020	137,300	0.84	0.46	65 - 75
	4'-6"	54	28.3	25.7	558	6,640	7,310	187,800	0.84	0.46	75 - 80
	5'-0"	60	31.4	28.6	600	7,920	8,690	248,600	0.84	0.46	80 - 90
	5'-6"	66	34.4	31.6	642	9,240	10,070	318,000	0.82	0.46	90 - 100
Colorado	G54	54	27.33	26.67	631	8,877	9,095	242,585	0.92	0.53	80 - 120
	G68	68	34.09	33.91	648	12,120	12,185	413,184	0.96	0.55	105 - 140
Illinois	36"	36	20.63	15.37	357	2,358	3,165	48,648	0.85	0.43	30 - 70
	42"	42	24.35	17.65	465	3,736	5,153	90,956	0.91	0.46	40 - 85
	48"	48	26.91	21.09	570	5,355	6,834	144,117	0.86	0.45	50 - 95
	54"	54	29.03	24.97	599	7,362	8,559	213,715	0.92	0.49	60 - 110

*Varies with concrete compressive strength at transfer and at 28 days

1 in = 25.4 mm; 1 ft = 0.305 m

BEST DOCUMENT AVAILABLE

TABLE 5 - CROSS-SECTIONAL PROPERTIES

(Cont.)

Agency	Girder Type	h (in)	y_t (in)	y_b (in)	Area (in^2)	S_t (in^3)	S_b (in^3)	Inertia (in^4)	α	ρ	Span Range* (ft)
Iowa	A30-A46	32	17.95	14.05	312	1,899	2,426	34,082	0.84	0.43	30 - 46
	A50-A55	32	17.49	14.51	408	2,433	2,933	42,552	0.78	0.41	50 - 55
	B34-B59	39	21.94	17.06	383	2,826	3,634	62,000	0.84	0.43	34 - 59
	B63-B67	39	21.37	17.63	500	3,620	4,388	77,364	0.78	0.41	63 - 67
	C30-C67	45	25.48	19.52	530	3,637	4,747	92,659	0.85	0.43	30 - 67
	C71-C80	45	24.77	20.23	565	4,697	5,752	116,354	0.78	0.41	71 - 80
	D35-D95	54	29.63	24.37	639	7,255	8,821	214,974	0.88	0.47	35 - 95
Louisiana	AASHTO-PCI Types II, III, and IV										
Oregon	AASHTO-PCI Types II, III, and IV										
	Type V	63	34.06	28.94	861	11,595	13,648	394,941	0.87	0.47	90 - 120
	BT65"	65	30.23	34.77	771	13,864	12,052	419,064	0.83	0.52	100 - 140
	BT72"	72	35.32	36.68	739	14,835	14,285	523,962	0.93	0.55	100 - 145
	I84"	84	42.00	42.00	927	18,734	18,734	786,834	0.83	0.48	Up to 190
Pennsylvania	20/30	30	16.88	13.12	363	1,942	2,499	32,786	0.79	0.41	40 - 55
	20/33	33	18.65	14.35	417	2,400	3,119	44,757	0.78	0.40	44 - 60
	20/36	36	20.38	15.62	471	2,899	3,782	59,077	0.77	0.39	47 - 66
	20/39	39	21.59	17.41	513	3,593	4,456	77,576	0.77	0.40	50 - 70
	24/33	33	18.13	14.87	549	3,155	3,847	57,200	0.73	0.39	46 - 63

*Varies with concrete compressive strength at transfer and at 28 days

1 in = 25.4 mm; 1 ft = 0.305 m

BEST DOCUMENT AVAILABLE

TABLE 5 - CROSS-SECTIONAL PROPERTIES

(Cont.)

Agency	Girder Type	h (in)	y_t (in)	y_b (in)	Area (in^2)	S_t (in^3)	S_b (in^3)	Inertia (in^4)	α	ρ	Span Range* (ft)
Pennsylvania	24/36	36	19.83	16.17	615	3,795	4,654	75,256	0.73	0.38	50 - 68
	24/42	42	23.96	18.04	588	4,506	5,985	107,967	0.84	0.42	57 - 87
	24/45	45	24.82	20.18	642	5,643	6,941	140,065	0.83	0.44	60 - 83
	24/48	48	26.61	21.39	708	6,490	8,074	172,712	0.82	0.43	66 - 88
	24/51	51	27.62	23.38	762	7,690	9,085	212,399	0.81	0.43	69 - 92
	24/54	54	28.69	25.31	816	8,895	10,083	255,194	0.79	0.43	72 - 109
	26/33	33	17.96	15.04	615	3,527	4,212	63,346	0.72	0.38	48 - 64
	26/36	36	19.63	16.37	687	4,241	5,085	83,247	0.71	0.38	52 - 70
	26/60	60	31.48	28.52	968	12,436	13,727	391,487	0.82	0.45	78 - 105
	26/63	63	32.03	30.97	1,046	14,676	15,179	470,081	0.80	0.45	80 - 108
	28/63	AASHTO-PCI Type V									
Tennessee	AASHTO-PCI Types I, II, III, and IV										
Texas	A	28	15.39	12.61	275	1,472	1,797	22,658	0.81	0.42	28 - 45
	B	34	19.07	14.93	360	2,264	2,892	43,177	0.82	0.42	40 - 60
	C	40	22.91	17.09	495	3,606	4,833	82,602	0.84	0.43	50 - 85
	48	48	25.13	22.87	403	4,057	4,458	101,950	0.80	0.44	-
	54	54	28.47	25.53	493	5,761	6,425	164,022	0.84	0.46	60 - 100
	60	60	31.59	28.41	628	8,082	8,987	255,319	0.83	0.45	-

*Varies with concrete compressive strength at transfer and at 28 days

1 in = 25.4 mm; 1 ft = 0.305 m

BEST DOCUMENT AVAILABLE

TABLE 5 - CROSS-SECTIONAL PROPERTIES

(Cont.)

Agency	Girder Type	h (in)	y_t (in)	y_b (in)	Area (in^2)	S_t (in^3)	S_b (in^4)	Inertia (in^4)	α	ρ	Span Range* (ft)
Texas	66	66	34.93	31.07	741	10,727	12,059	374,688	0.85	0.47	-
	72	72	38.27	33.73	863	13,903	15,774	532,060	0.88	0.48	100 - 150
	IV	AASHTO-PCI Type IV									
Virginia	AASHTO-PCI Types III, IV, V, and VI										
	T34"	34	Varies with top flange width								30 - 60
Washington	Series 40	32	16.84	15.16	253	1,841	2,045	31,000	0.87	0.48	40 - 55
	Series 60	42	23.37	18.63	332	3,000	3,763	70,100	0.93	0.48	55 - 80
	Series 80	50	27.47	22.53	476	5,639	6,875	154,900	1.00	0.53	65 - 105
	Series 100	58	30.10	27.90	546	8,272	8,925	249,000	0.98	0.54	65 - 125
	Series 120	73.5	37.90	35.60	626	12,032	12,809	456,000	0.96	0.54	85 - 145
	Series 14	73.5	35.33	38.16	674	14,556	13,476	514,312	0.94	0.57	110 - 150
Wisconsin	AASHTO-PCI Types II, III and IV										
	70"	70	35.38	34.62	774	14,430	14,751	510,613	0.94	0.54	105 - 135

*Varies with concrete compressive strength at transfer and at 28 days

1 in = 25.4 mm; 1 ft = 0.305 m

BEST DOCUMENT AVAILABLE

TABLE 5 - CROSS-SECTIONAL PROPERTIES

(Cont.)

Agency	Girder Type	h (in)	y_t (in)	y_b (in)	Area (in^2)	S_t (in^3)	S_b (in^4)	Inertia (in^4)	α	ρ	Span Range* (ft)
Ontario (Canada)	AASHTO-PCI Types II, and III										
	CPCI IV	54	29.36	24.64	685	8,274	9,859	242,936	0.92	0.49	80 - 120
	CPCI IV+4	58	29.79	28.21	773	10,733	11,334	319,737	0.87	0.49	95 - 125
	ONT 90	90	45.11	44.89	1,136	25,619	25,743	1,155,669	0.87	0.50	up to 145
	MOD. ONT 90	90	44.16	45.84	1,005	23,981	23,103	1,059,014	0.88	0.52	140 - 170

*Varies with concrete compressive strength at transfer and at 28 days

1 in = 25.4 mm; 1 ft = 0.305 m

BEST DOCUMENT AVAILABLE

TABLE 5 - CROSS-SECTIONAL PROPERTIES
(Cont.)

Cross Section Identification	h (in)	y_t (in)	y_b (in)	Area (in^2)	S_t (in^3)	S_b (in^3)	Inertia (in^4)	α	ρ	Span Range* (ft)
Anderson BT 48	48	24.50	23.50	500	6,695	6,975	163,972	1.01	0.57	70 - 100
BT 60	60	30.71	29.29	560	9,224	9,669	283,229	1.00	0.56	80 - 125
BT 72	72	36.88	35.12	620	12,005	12,607	442,764	0.98	0.55	90 - 140
Modified AASHTO										
Type IV	54	29.63	24.37	681	7,894	9,594	233,854	0.90	0.48	70 - 115
Type V	63	30.98	32.02	887	15,477	14,973	479,458	0.93	0.55	90 - 140
Type VI	72	35.56	36.44	941	18,871	18,417	671,088	0.94	0.55	110 - 150
Modified Colorado G68/6	68	33.99	34.01	701	12,548	12,544	426,575	0.91	0.53	105 - 140
Modified Washington										
Series 80/6	50	27.24	22.76	513	5,844	6,994	159,191	0.94	0.50	70 - 105
Series 100/6	58	30.01	27.99	591	8,549	9,166	256,560	0.93	0.52	80 - 125
Series 120/6	73.5	37.68	35.82	688	12,619	13,275	475,502	0.91	0.51	85 - 140
Series 14/6	73.5	35.31	38.19	736	15,122	13,985	534,037	0.89	0.54	105 - 150
Modified Bulb-T										
BT 48/6	48	23.53	24.47	557	7,553	7,264	177,736	0.94	0.55	70 - 105
BT 60/6	60	29.59	30.41	629	10,432	10,154	308,722	0.93	0.54	80 - 130
BT 72/6	72	35.64	36.36	701	13,606	13,340	484,993	0.92	0.53	100 - 144

*Varies with concrete compressive strength at transfer and at 28 days

1 in = 25.4 mm; 1 ft = 0.305 m

BEST DOCUMENT AVAILABLE

TABLE 6 - PROPERTIES OF NEW CPCI METRIC SECTIONS

Agency	Girder Type	h (mm)	y_t (mm)	y_b (mm)	Area (mm^2)	S_t ($mm^3 \times 10^6$)	S_b	Inertia ($mm^4 \times 10^6$)	α	p	Span Range* (ft)
CPCI Canadian Metric Sections	900	900	502	398	218,000	38.5	48.5	19,310	0.86	0.44	40 - 60
	1200	1200	673	527	320,000	80.0	102.2	53,868	0.92	0.47	55 - 80
	1400	1400	765	635	413,000	134.1	161.5	102,580	0.97	0.51	80 - 100
	1900	1900	960	940	544,000	279.6	285.6	268,420	0.96	0.55	100 - 135
	1900A	1900	960	940	601,000	297.5	303.8	285,570	0.92	0.53	100 - 135
	2300	2300	1165	1135	604,000	370.6	380.4	431,790	0.95	0.54	140 - 170
	2300A	2300	1163	1137	673,000	397.4	406.5	462,220	0.91	0.52	140 - 170

*Varies with concrete compressive strength at transfer and at 28 days

1 mm = 0.0394 in; 1 ft = 0.305 m

BEST DOCUMENT AVAILABLE

APPENDIX D - COST DATA

The following unit costs were obtained from seven agencies and one producer.

California

In the State of California, the majority of highway bridges were cast-in-place, post-tensioned concrete box girders. This type of bridge has been successfully built since the early 1950's. Contractors were experienced with this type of construction and the cost was competitive. These bridges were considered aesthetically pleasing and were cheaper to manufacture than precast girders. It was felt that as the cost of lumber increases the cost of cast-in-place boxes would increase and possibly precast bridge girders might become more competitive.

Precast, pretensioned girders were mostly used in coastal areas and where traffic could not be interrupted during construction. Cost data were compiled on a global unit cost basis. For 1978, the cost of precast, prestressed concrete was $714.18 per composite cubic yard. In October, 1979, this cost was estimated at about $800 per composite cubic yard. This included the cost of prestressing steel, reinforcing bars, Class A concrete, and labor.

Illinois

In the State of Illinois, unit costs for in-place girders, reinforcing steel, and concrete for decks were as follows:

Item	Cost	
	December 1978	June 1979
Girder Type 36 in	$46/ft	$67/ft
Girder Type 42 in	55	69
Girder Type 48 in	61	94
Girder Type 54 in	78	74
Reinforcing Bars	43¢/lb	52¢/lb
Epoxy coated (top bars)	67¢/lb	87¢/lb
Class X concrete	$250/cu yd.	$250/cu yd.

1 in = 25.4 mm; 1 ft = 0.305 m; 1 yd = 0.914 m; 1 lb = 4.45 N

BEST DOCUMENT AVAILABLE

Differences in unit costs occurred between December 1978 and June 1979. While the cost of 48 in (1.22 m) girders increased tremendously in 1979, cost of 54 in (1.37 m) girders decreased. These inconsistencies are due to factors discussed in the body of the report under "Availability and Costs."

Oregon

In the State of Oregon, unit costs used to estimate the cost of bridge construction during the fourth quarter of 1979 were as follows:

Girder	Girder Cost $/ft (excluding transportation)	Overall Bridge Cost $/sq ft of Deck Area
Type II	65	41
Type III	75	43
Type IV	95	44
Bulb-T	105	47

1 ft = 0.305 m

Texas

In the State of Texas, unit costs were based on bids received during the period of January to September 1979. These costs were as follows:

Item	Cost
Girder Type A	$59.80/ft
Girder Type B	44.68
Girder Type C	51.40
Girder Type 54	54.80
Girder Type IV	68.68
Cast-In-Place Decks	$7.30/sq ft
In-Place Concrete for Decks	$214/cu yd
In-Place Steel for Decks	41¢/lb
In-Place Strands for Decks	20¢/ft

1 ft = 0.305 m; 1 yd = 0.914 m; 1 lb = 4.45 N

BEST DOCUMENT AVAILABLE

In 1978, 74 state highway bridges were built in the State of Texas at a cost of $16.86/sq ft for the superstructure.

Girder Type A, identical to AASHTO-PCI standard girder Type I was the smallest section. It required the least amount of concrete, strands, and reinforcing steel. However, the unit cost was relatively very high because this girder has been used mainly ror bridge widening.

Virginia

As of June 1979, unit costs in the State of Virginia were as follows:

Item	Cost
AASHTO Type II	$31-47/ft
AASHTO Type III	37-56
AASHTO Type IV	56-76
AASHTO Type V	69-77
AASHTO Type VI	89-92
Class A4 Concrete for Decks	$240/cu yd
Reinforcing Steel	27¢/lb
Epoxy Coated Bars	52¢/lb

1 ft = 0.305 m; 1 yd = 0.914 m; 1 lb = 4.45 N

The wide range of cost for the girders reflected cost variation due to factors discussed in the report.

Washington

As of August 1979, unit costs for comparative cost estimates of alternate designs were as follows:

Item	Cost
Girders 40 Series	$50/ft
Girders 60 Series	51
Girders 80 Series	57
Girders 100 Series	64
Girders 120 Series	70
Concrete Class AX for Decks	$200-250

1 ft = 0.305 m

BEST DOCUMENT AVAILABLE

Wisconsin

As of August 1979, costs in the State of Wisconsin were as follows:

Item	Cost
Girder Type II	$49/ft
Girder Type III	62
Girder Type IV	79
Girder Type 70 inch	84
Finished Superstructure	$11.68-14.04/sq ft

1 ft = 0.305 m

Stanley Structures

In October of 1979, pretensioned girders produced by Stanley Structures, located in Denver, Colorado, were delivered at sites within metropolitan Denver at the following cost:

Girder G54	$65/ft ($213/m)
Girder G68	$70/ft ($230/m)

These costs varied slightly with number of strands in each girder. They did not include cost of bearings or contractors' profit.

BEST DOCUMENT AVAILABLE

APPENDIX E - COMPUTER PROGRAM "BRIDGE"

To perform the parametric studies discussed in this report, a computer program was developed. This appendix contains Program Documentation, Source Listing, and Sample Problems.

Program Documentation

Program Name: BRIDGE

Language: Fortran IV

Purpose and Capabilities

The main purpose of Program BRIDGE is to compute a cost index per unit surface area of simply supported bridges built with precast prestressed I or T-girders and cast-in-place concrete deck. Program BRIDGE generates additional information including:

1. Deck thickness and main deck reinforcement
2. Non-composite and composite sectional properties
3. Dead and live load moments and impact factor
4. Required number of strands
5. Stress levels in concrete and strands at prestress transfer and service load conditions
6. Midspan deflection
7. Total concrete and reinforcement quantities

All computations are made for an interior girder. Design procedures are based on 1977 AASHTO Specifications[8] and 1978 to 1980 Interim Specifications[12], and for HS20 loading. Details of data input and output, design assumptions, capabilities, and limitations of Program BRIDGE are discussed below in the solution steps.

Solution Steps

Program BRIDGE is divided into eight solution steps as follows:

1. Input of geometric and material properties, and relative unit costs of materials.
2. Allowable material properties are computed.
3. Deck thickness and reinforcement are determined.

4. Non-composite and composite sectional properties are calculated.
5. Design loads and moments are computed.
6. Number of strands required to satisfy service and strength conditions are determined.
7. Midspan deflections are computed.
8. Total material quantities and cost index per unit surface area of bridge are calculated.

Data input and values computed within each step are printed with adequate explanation as output. Each step is now described in detail.

Step 1 - Data Input Each case problem requires input of data on a set of 12 punched cards. The last card is a control card to determine whether a new problem follows. Therefore, several problems can be solved consecutively.

For each sample problem, input of some data is optional. Where no information is provided, the program assumes values stored as default options. Minimum information needed is girder dimensions, span length, and girder spacing.

A detailed description of data input and default options is presented in the following paragraphs. After discussing each of the eight solution steps, a summary of data input for each case problem is presented under the heading "User's Input Instructions."

Twelve punched cards contain the data input of each case problem. Each card has 80 columns. Two formats are used.

The A format code is convenient for input of character strings. These may consist of combinations of letters, digits or symbols. The A format is useful for titles identifying case problems.

The F format code is used to input real values. In Program BRIDGE all values or quantities are input using F12.0 format. Therefore, twelve columns are allocated for each value. Each value should have a decimal point and may have up to 11 digits. If no value is punched within the allocated columns, a value of

zero is assumed. As will be seen later, if a variable is given a value of zero, then a default option value is assumed.

Format code for data on each of the 12 cards is summarized in the "User's Input Instructions" section. Data input on each card follows:

Cards 1, 2 and 3 are for identification of case problem. These are job description or title cards.

Card 4 is to input the span length, SL, in feet and girder spacing, GS, in feet.

SL is the span length, center to center of supports for simply supported girders. Program BRIDGE was designed to handle spans of 70 to 180 ft (2.14 to 54.9 m).

GS is the center to center spacing of girders. Maximum girder spacing is a function of the effective deck span. This is discussed in Step 3. Maximum girder spacing accepted by Program BRIDGE is approximately 11 ft (3.35 m).

Cards 5 and 6 are to input dimensions defining the girder cross section, in inches. These are identified in Figure 31. Card 5 reads horizontal dimensions B1, B2, B3, and B4. Card 6 reads vertical dimensions D1, D2, D3, D4, D5 and D6. For sections with profile as shown in Figure 31.b, dimensions B4 and D4 are equal to zero.

Card 7 reads parameters CTC, CSC and SWW. CTC is the center-to-center spacing of strands in inches at midspan. It is assumed to be the same in both vertical and horizontal directions and depends on the strand size. In Program BRIDGE, size of all strands is assumed to be 1/2 in (12.7 mm). If the minimum clear spacing between strands is three times the diameter of the steel[8], then CTC is equal to 2 in (50.8 mm) This was discussed earlier under Fabrication Details. If strands are bundled, then CTC equals 0.5 in (12.7 mm). Default option for CTC is 2 in (50.8 mm), i.e. if CTC is input as zero, then the program assumes CTC equal to 2 in (50.8 mm).

CSC is the concrete surface to center of strand distance in inches. This dimension reflects the amount of concrete cover



a. I - Section



b. T - Section

Figure 31 Dimensions Defining Girder Cross Section for Computer Input

BEST DOCUMENT AVAILABLE

in the bottom flange at midspan. In most states, this dimension is 2 in (50.8 mm). However, some states use 1.75 in (44.5 mm). The default option for CSC is 2 in (50.8 mm).

SWW is the number of strands in one row, within the web width at midspan. This parameter is needed in Step 6, where number of required strands is determined. If all strands are located within the bottom flange at midspan, SWW is ignored. But if strands are needed in the web, the maximum number of strands within a row depends on the value of CTC and CSC defined above. For example, if web width is 8 in (203 mm), and both concrete cover, CSC, and spacing of strands, CTC, are equal to 2 in (50.8 mm), then it is possible to place three strands within the web width. But common practice in several states is to place only 2 strands, side by side, within the web. Therefore, the default option of SWW = 2 is introduced in the program.

Card 8 provides the value of FCP, FCPI, WC, WCD, WG, and WD. FCP is the girder concrete compressive strength at 28 days in psi units. This value could be as high at 8,000 psi (55.2 MPa). Default option for FCP is 6000 psi (41.4 MPa).

FCPI is the concrete compressive strength at transfer of prestress in psi units. Default option is 4500 psi (31 MPa).

WC and WCD are the unit weights of the girder and deck concretes, respectively, in pcf. Default options set these concrete unit weights at 145 pcf (2,323 kg/m^3).

WG and WD are the unit weights of the girder and deck in pcf units. It accounts for weight of concrete, reinforcing steel, and strands. Default option values are 150 pcf (2,403 kg/m^3).

Card 9 is to input the strand's yield stress, FPY, in psi, the strand's modulus of elasticity, EPS, in psi, and total prestress losses, XLS, in psi. Default options are 23,000 psi (159 MPa), 28,000,000 psi (193,000 MPa), and 45,000 psi (310 MPa), respectively.

Card 10 inputs a stiffness reduction factor, SRF, that is used to compute the girder deflections. It accounts for the concrete creep and prestress losses. The value of SRF = 0.55

suggested in State of Illinois Prestressed Concrete Design Manual[27] is adopted in this computer program as a default option. Further explanation about the stiffness redution factor is discussed below in Step 7.

Card 11 provides the relative unit cost indexes of materials as discussed earlier:

RUCG for girder concrete (Default Option 1 unit/lb)

RUCD for deck concrete (Default Option 1 unit/lb)

RUS for strand (Default Option 8 units/lb)

RUR for deck bottom reinforcing steel (Default Option 9 units/lb)

RUE for deck top epoxy coated reinforcing steel (Default Option 12 units/lb). If top flexural reinforcement of deck is not epoxy coated, RUE should be equal to RUR.

Card 12 is a control card. If a new set of data is to be input, CONTINUE is punched, starting in Column 1. In the last data set, Card 12 reads END starting in Column 1.

In addition to the data input, other data are assigned internally and therefore assumed constant for all case problems.

Concrete compressive strength of deck at 28 days is assumed 4000 psi. Strands are assumed to be Grade 270. Stress-strain characteristics of strand shown in Figure 32 are used to compute the nominal flexural strength of the composite section in Step 6.

Step 2 - Allowable Stresses Allowable concrete stresses at transfer and at service condition are computed according to AASHTO Specifications.[8] Strand effective stress after losses, is computed. A check is made to verify that this value falls within the range specified.[8] If it is outside this range, a message is printed to this effect as discussed below under "Error Messages." In this case all other computations are by-passed, and a new case problem is processed. If the strand effective stress is within the acceptable range, the program proceeds with the next step.

Step 3 - Deck Thickness and Reinforcement Determination of the cast-in-place slab (or deck) thickness and reinforcement have been adopted from design aids prepared by Washington State



Figure 32 Assumed Stress-Strain Characteristics of Strands

BEST DOCUMENT AVAILABLE

Department of Transportation.[28] It is based on the following assumptions:

1. Concrete compressive strength at 28 days is 4000 psi (27.6 MPa).
2. Reinforcing steel is Grade 60 (414 MPa).
3. Interior spans are considered with equal top and bottom flexural reinforcement.
4. Reinforcing steel is perpendicular to traffic direction.

An effective slab span is computed based on center-to-center spacing of girders, width of top flange and deck thickness. The effective slab span is illustrated in Figure 33. Information given in Table 7 was stored in Program BRIDGE. It served as a basis for deck design. If the effective slab span exceeds 10 ft (3.05 m), a message is printed to that effect.

Step 4 - Sectional Properties Properties determined for girder (non-composite) and girder slab (composite) sections are:

1. Location of center of gravity
2. Cross sectional area
3. Modulus of section for top and bottom fibers
4. Moment of inertia

In the composite section, the effective top flange width is the smallest of:

1. Girder span divided by four
2. Girder spacing
3. Twelve times deck thickness plus web width, B3, shown in Figure 31.

In calculations of the composite section properties, a transformed deck-girder section is considered. However, transformed area of strands is neglected.

Step 5 - Design Loads and Moments Dead loads are based on cross sectional area of girder and deck calculated in the previous step and concrete unit weight specified in Step 1. Live load considered in Program BRIDGE is HS 20-44 loading. Impact factor is based on 50/(Span length in feet + 125) , and does not exceed 30 percent.



Figure 33 Effective Slab Span

BEST DOCUMENT AVAILABLE

TABLE 7 - DECK DESIGN[28]

Effective Slab Span (ft)	Slab Thickness (in)	Slab Reinforcement*	
		Bar Size	Spacing (in)
1 to 3 inclusive	7	No. 5	10.0
3 to 4 inclusive	7	No. 5	8.5
4 to 5 inclusive	7	No. 5	7.5
5 to 6 inclusive	7	No. 5	6.5
6 to 7 inclusive	7	No. 6	8.0
7 to 8 inclusive	7-1/2	No. 6	8.0
8 to 9 inclusive	8	No. 6	8.0
9 to 10 inclusive	8-1/2	No. 6	8.0

* Reinforcement shown is for each of top and bottom layers.

1 in = 25.4 mm

BEST DOCUMENT AVAILABLE

Midspan dead and live load moments are computed for simple spans. Live load moments have been adopted from Appendix A of the AASHTO Specifications.[8] They are summarized in Table 8. For intermediate spans, moments are computed through linear interpolation. These moments are per lane width of 10 ft (3.05 m). They are proportioned to determine live load moment per girder spacing. The strength required is based on 1.3 Dead Load + $\frac{5}{3}$ (Live Load + Impact) .

Step 6 - Required Number of Strands Required number of strands is determined through incremental analysis. For each analysis step, the total number of strands is increased by one. Top and bottom concrete stresses are checked at midspan for transfer and service conditions. Flexural strength is also computed. Required number of strands is obtained when concrete stresses and flexural strength conditions[8] are satisfied at midspan.

Location of strands is chosen to achieve maximum prestress eccentricity. These locations are governed by allowable concrete cover and strand spacing. These values are specified in Step 1. They include the concrete surface to center of strand distance CSC, and the center to center spacing of strands CTC.

Strands are placed in rows as shown in Figure 34. The first row is located at a distance CSC from the bottom of the girder. Subsequent rows are spaced CTC apart, Within each row, strands are spaced a distance CTC apart. Side concrete cover is governed by distance CSC.

Strands are positioned in the bottom row first, and by moving to higher rows as required. This is to achieve maximum eccentricity. If the total number of strands required is large, strands may be placed within the web. Common practice is to place two strands side-by-side in each row within the web width. This is discussed under data input for Card 7, in Step 1. If a different number of strands in one row within the web width is desirable, it should be specified in the data input of Card 7.

During the incremental analysis to determine the number of strands, initial and effective prestress levels are computed.

TABLE 8 - HS20-44 MOMENTS[8]

Span (ft)	Bending Moment (ft. kip)
70	985.6
80	1,164.9
90	1,344.4
100	1,524.0
110	1,703.6
120	1,883.3
130	2,063.1
140	2,242.8
150	2,475.1
160	2,768.0
170	3,077.1
180	3,402.1

1 ft = 0.305 m
1 ft.kip = 1.36 kN.m

BEST DOCUMENT AVAILABLE



Figure 34 Strands Locations

BEST DOCUMENT AVAILABLE

For each prestress level, top and bottom concrete stresses are checked against the allowable stresses computed in Step 2. When the required number of strands satisfying allowable concrete stresses is reached, the nominal flexural strength, M_n, is calcu-culated through an iteration process.[29] The required flexural strength, M_u is checked against the nominal flexural strength, M_n, times the strength reduction of 0.9. Minimum steel requirement of Section 1.6.10.B of the AASHTO Specifications[8] is also checked. If these requirements are not satisfied, the number of strands is increased by one strand.

Program BRIDGE contains two criteria governing the number of strands that can be placed in a section:

1. No strands can be placed above the top core or kern[1] of the section.
2. An arbitrary upper limit of 100 strands has been set in the program. This limit exceeds by about 30 percent the maximum number of strands needed in any of the sections analyzed in this report. This criterion may control where strands are bundled. This condition is obtained by specifying a center-to-center spacing of strands, CTC, equal to the strand diameter of 0.5 in (12.7 mm) in Step 1.

If any of the above limits on number of strands is reached without satisfying concrete stress and flexural strength requirements a message is printed to this effect. If the reinforcement index exceeds 0.3[8], a warning message is printed. When stress and strength requirements are satisfied, the program proceeds with the next step.

Step 7 - Midspan Deflections The effect of prestress in a pretensioned member is to produce an upward deflection, or camber. The weight of the girder counteracts this camber. The net effect is usually a camber, but it could be a downward deflection or sag. Due to prestress, the concrete creeps. As a result the camber or sag increases until the girder is transported to the final position and the cast-in-place concrete deck is placed. The net effect of the cast-in-place deck is a downward deflection.

Due to creep, the level of prestress decreases. The net effect of creep and loss of prestress on the girder deflection at erection time is an increase in the camber or sag. A magnification of the elastic deflection by 1.82 is suggested in the State of Illinois, Department of Transportation Design manual.[27] This increase in camber or sag can be accounted for by decreasing the stiffness of the girder. This stiffness reduction factor, SRF, is equal to 1/1.82, i.e. 0.55. This is the default option for data input of SRF.

Camber due to prestress depends on the magnitude and eccentricity of the prestressing force, number and location of draped strands, or number and length of blanketed strands. In Program BRIDGE, camber due to prestress is computed assuming that all strands are straight and bonded over their entire length. The effect of draping or blanketing strands is to decrease the magnitude of the camber.[30]

Step 8 - Cost Index Per Unit Surface Area of Bridge Cost index per unit surface area of bridge computed in Program BRIDGE provides a means of comparing the cost effectiveness of girder cross sections. Total weight of materials is computed for a width of deck equal to the girder spacing. These weights are reduced to weights of materials per unit surface area of bridge. The cost index per unit surface area of bridge is based on the relative unit costs input in Card 11 of Step 1.

Warning Messages

The following is a list of all warning messages and their explanations:

1. EFFECTIVE PRESTRESS IS OUT OF RANGE
   This message appears if the effective prestress after losses is less than 50 percent of the strand strength or greater than 80 percent of the yield strength of the strands.[8]

2. EFFECTIVE DECK SPAN EXCEEDS 10 FT.

   Effective deck slab span computed in Step 3 is limited to 10 ft (3.05 m). Values up to 10 ft (3.05 m) are handled by the program.

3. GIRDER SPAN IS OUT OF RANGE

   The program computes midspan moments due to HS20-44 loading for spans between 70 and 180 ft (21.3 and 54.9 m).

4. CANNOT SATISFY STRESS AND STRENGTH REQUIREMENTS

   Concrete stress and flexural strength requirements are violated at midspan.

5. REINFORCEMENT INDEX EXCEEDS 0.3

   Reinforcement index should not exceed 0.3 to prevent brittle failures.[8]

If any of the above messages is encountered, processing of the problem is terminated, and control is transferred to the subsequent case problem.

User's Input Instructions

This section summarizes data input for each case problem. Detailed explanations of variables and default options are given in the preceding section entitled "Solution Steps." For each case problem, data input consists of 12 punched cards containing the information shown in Table 9. Each variable is described below:

Cards 1,2, and 3

Title to identify case problem

Card 4

SL - Span length, ft

GS - Girder spacing, ft

Card 5

B1, B2, B3, and B4 - Horizontal dimensions, defining girder profile as identified in Figure 31, in

Card 6

D1, D2, D3, D4, D5, D6 - Vertical dimensions defining girder profile as identified in Figure 31, in

Card 7

CTC - center to center spacing of strands, in (D.O.* = 2)

CSC - concrete cover, distance from concrete surface to center of strand, in (D.O. = 2)

SWW - number of strands in a row within web width (D.O. = 2)

Card 8

FCP - Girder concrete compressive strength at 28 days, psi (D.O. = 6000)

FCPI - Girder concrete compressive strength at transfer, psi (D.O. = 4500)

WC - Unit weight of girder concrete, pcf (D.O. = 145)

WCD - Unit weight of deck concrete, pcf (D.O. = 145)

WG - Unit weight of girder, pcf (D.O. = 150)

WD - Unit weight of deck, pcf (D.O. = 150)

*Default option, i.e., if zero value is assigned, the default value is assumed.

TABLE 9 - DATA INPUT

Card Number	Parameters	Format
1, 2, 3	TITLE	20A4
4	SL, GS	2F12.0
5	B1, B2, B3, B4	4F12.0
6	D1, D2, D3, D4, D5, D6	6F12.0
7	CTC, CSC, SWW	3F12.0
8	FCP, FCPI, WC, WCD, WG, WD	6F12.0
9	FPY, EPS, XLS	3F12.0
10	SRF	1F12.0
11	RUCG, RUCD, RUS, RUR, RUE	5F12.0
12	CONTINUE or END (Starting in Column 1)	20A4

BEST DOCUMENT AVAILABLE

Card 9

FPY - Yield stress of strand, psi (D.O. = 230,000)

EPS - Modulus of elasticity of strand, psi (D.O. = 28,000,000)

XLS - Tctal prestress losses, psi (D.O. = 45,000)

Card 10

SRF - Stiffness reduction factor due to creep (D.O. = 0.55)

Card 11

RUCG - Relative unit cost index of girder concrete, unit per lb (D.O. = 1)

RUCD - Relative unit cost index of deck concrete, unit per lb (D.O. = 1)

RUS - Relative unit cost index of strands, unit per lb (D.O. = 8)

RUR - Relative unit cost index of bottom deck reinforcement, unit per lb (D.O. = 9).

RUE - Relative unit cost index of epoxy coated top deck reinforcement, unit per lb (D.O. 12)

Card 12

This is a control card.

CONTINUE is entered starting in column 1 if a new set of data is input.

END is entered starting in column 1 if it is the last set of data.

Source Listing

```
      PROGRAM BRIDGE(INPUT,OUTPUT,TAPE5=INPUT,TAPE6=OUTPUT)
C     ***  STRUCTURAL DESIGN OF PRESTRESSED CONCRETE BRIDGE GIRDERS  ***
C     THIS PROGRAM CALCULATES THE NUMBER OF STRANDS AND THE COST INDEX PER
C     UNIT SURFACE AREA FOR A GIVEN PRESTRESSED CONCRETE BRIDGE GIRDER
C     FHWA CONTRACT NO. DOT-FH-11-9598  / CR4475/4321
C
      DIMENSION TITLE(20),BS(2),ABAR(2),X(3),A(7),Y(7),XJ(7),DM(12),
     1          SLL(12),NR(50)
      DATA ABAR/4HNO.5,4HNO.6/,CONT/4HCONT/
      DATA DM/835.6,1164.9,1344.4,1524.0,1703.6,1883.3,2062.1,2241.8,
     1        2475.1,2766.0,3077.1,3402.1/
      DATA SLL/70.,80.,90.,100.,110.,120.,130.,140.,150.,160.,170.,180./
      IW=3
      IR=8
C*****************************************************************************
C
C **STEP(1) INPUT DATA **
C
C   GEOMETRIC PROPERTIES
C     SL=GIRDER SPAN LENGTH(FT)
C     GS=GIRDER SPACING(FT)
C     B1,B2,B3, AND B4=HORIZONTAL DIMENSIONS OF GIRDER CROSS SECTION(IN)
C     D1,D2,D3,D4,D5,AND D6=VERTICAL DIMENSIONS OF GIRDER (IN)
C    CTC=CENTER TO CENTER DISTANCE OF STRANDS(IN)
C       =2(DEFAULT OPTION)
C    CSC=CONCRETE SURFACE TO CENTER OF STRANDS(IN)
C       =2(DEFAULT OPTION)
C    SWW=MAXIMUM NUMBER OF STRANDS WITHIN WEB WIDTH
C       =2(DEFAULT OPTION)
C   MATERIAL PROPERTIES
C    CONCRETE
C     FCP=SPECIFIED GIRDER CONCRETE STRENGTH(PSI)
C     FCP=6000 (DEFAULT OPTION)
C     FCPI=CONCRETE STRENGTH AT PRESTRESS TRANSFER(PSI)
C         =4500(DEFAULT OPTION)
C     WC=UNIT WEIGHT OF GIRDER CONCRETE(PCF)
C       =145(DEFAULT OPTION)
C     WCD=UNIT WEIGHT OF DECK CONCRETE(PCF)
C       =145 DEFAULT OPTION)
C     WG=UNIT WEIGHT OF GIRDER(PCF)
C       =150(DEFAULT OPTION)
C     WD=UNIT WEIGHT OF DECK(PCF)
C       =150(DEFAULT DOPTION)
C    STRAND
C     FPY=SPECIFIED YIELD STRESS OF STRAND(PSI)
C       =230000(DEFAULT OPTION)
C     EPS=MODULUS OF ELASTICITY OF STRAND(PSI)
C       =29000000(DEFAULT OPTION)
C     XLS=TOTAL PRESTRESS LOSSES(PSI)
C       =45000(DEFAULT OPTION)
C
C     SRF=STIFFNESS REDUCTION FACTOR DUE TO CREEP AND PRESTRESS LOSS
C       =0.95(DEFAULT OPTION)
C
C   RELATIVE UNIT COSTS
C     RUCG=RELATIVE UNIT COST OF GIRDER CONCRETE(UNIT/LB)
C       =1(DEFAULT OPTION)
C     RUCD=RELATIVE UNIT COST OF DECK CONCRETE(UNIT/LB)
C       =1(DEFAULT OPTION)
C     RUS=RELATIVE UNIT COST OF STRAND(UNIT/LB)
C       =8(DEFAULT OPTION)
C     RUR=RELATIVE UNIT COST OF DECK REINFORCEMENT(UNIT/LB)
C       =9(DEFAULT OPTION)
C     RUE=RELATIVE UNIT COST OF EPOXY COATED DECK REINFORCEMENT
C       =12(DEFAULT OPTION)  IF NO EPOXY COATED BAR IS USED, THE VALUE
C                            EQUAL TO RUR IS TO BE GIVEN FOR RUE
C
C  READ EXAMPLE IDENTIFICATION
   10 WRITE(IW,20)
   20 FORMAT(1H1)
      DO 50 I=1,3
      READ(IR,30) (TITLE(J),J=1,20)
   30 FORMAT(20A4)
      WRITE(IW,40) (TITLE(J),J=1,20)
   40 FORMAT(1H ,5X,'** ',20A4,' **')
   50 CONTINUE
```


BEST DOCUMENT AVAILABLE

```
C  READ GEOMETRIC PROPERTIES                                          00770
      READ(IR,60) SL,GS                                              00780
   60 FORMAT(2F12.0)                                                 00790
      READ(IR,70) B1,B2,B3,B4                                        00800
   70 FORMAT(4F12.0)                                                 00810
      READ(IR,80) D1,D2,D3,D4,D5,D6                                  00820
   80 FORMAT(6F12.0)                                                 00830
      READ(IR,90) CTC,CSC,SWW                                        00840
   90 FORMAT(3F12.0)                                                 00850
      IF(CTC.EQ.0.) CTC=2.0                                          00860
      IF(CSC.EQ.0.) CSC=2.0                                          00870
      IF(SWW.EQ.0.) SWW=2.0                                          00880
      WRITE(IW,100)                                                  00890
  100 FORMAT(1H0,4X,'**(1) INPUT DATA **')                           00900
      WRITE(IW,110)                                                  00910
  110 FORMAT(1H0, 5X, GEOMETRIC PROPERTIES')                         00920
      WRITE(IW,120) SL, GS                                           00930
  120 FORMAT(1H0,10X,'GIRDER SPAN LENGTH(FT)    SL=',F10.2,/         00940
     1           11X, GIRDER SPACING(FT)        GS=',F10.2)         00950
      WRITE(IW,130) B1,B2,B3,B4                                      00960
  130 FORMAT(1H0,10X, HORIZONTAL DIMENSIONS OF GIRDER CROSS SECTION ..  00970
     1           12X, B1=',F10.2,2X, B2= ,F10.2,2X, B3= ,F10.2,2X, B4=',  00980
     2                F10.2)                                        00990
      WRITE(IW,140) D1,D2,D3,D4,D5,D6                                01000
  140 FORMAT(1H0,10X, VERTICAL DIMENSIONS OF GIRDER CROSS SECTION ..  01010
     1           12X, D1=',F10.2,2X,'D2= ,F10.2,2X,'D3= ,F10.2,2X, D4= ,  01020
     2                F10.2,2X,'D5= ,F10.2,2X, D6= ,F10.2)          01030
      WRITE(IW,150) CTC,CSC,SWW                                      01040
  150 FORMAT(1H0,10X, CENTER TO CENTER SPACING OF STRANDS(IN)     CTC=',  01050
     1F6.2,/    11X,'CONCRETE SURFACE TO CENTER OF STRANDS(IN)   CSC= ,  01060
     2F6.2,/    11X,'NUMBER OF STRANDS WITHIN WEB WIDTH          SWW=',  01070
     3F6.2)                                                          01080
C                                                                    01090
C  READ MATERIAL PROPERTIES                                          01100
C                                                                    01110
C                                                                    01120
C   CONCRETE                                                         01130
      READ(IR,160) FCP,FCPI,WC,WCD,WG,WD                             01140
  160 FORMAT(6F12.0)                                                 01150
      IF(FCP.EQ.0.) FCP=6000.                                        01160
      IF(FCPI.EQ.0.) FCPI=4500.                                      01170
      IF(WC.EQ.0.) WC=145.                                           01180
      IF(WCD.EQ.0.) WCD=145.                                         01190
      IF(WG.EQ.0.) WG=150.                                           01200
      IF(WD.EQ.0.) WD=150.                                           01210
C     FIXED DATA                                                     01220
C     FCD=SPECIFIED CONCRETE STRENGTH FOR DECK(PSI)                  01230
      FCD=4000.                                                      01240
C                                                                    01250
C    STRAND                                                          01260
      READ(IR,170) FPY,EPS,XLS                                       01270
  170 FORMAT(3F12.0)                                                 01280
      IF(FPY.EQ.0.) FPY=230000.                                      01290
      IF(EPS.EQ.0.) EPS=26000000.                                    01300
      IF(XLS.EQ.0.) XLS=45000.                                       01310
C     FIXED DATA                                                     01320
C     FPU=SPECIFIED ULTIMATE STRENGTH OF STRAND(PSI)                 01330
C     FPM=SPECIFIED STRAND STRESS LEVEL, WHICH IS POSITIONED BETWEEN 01340
C         FPU AND FPY TO FORM TRILINEAR STRESS-STRAIN CURVE(PSI)     01350
C     SY=STRAIN CORRESPONDING TO FPY                                 01360
C     SM=STRAIN CORRESPONDING TO FPM                                 01370
C     SU=STRAIN CORRESPONDING TO FPU                                 01380
C     ASTD=NOMINAL AREA OF STRAND(IN2)                               01390
C     UST=NOMINAL WEIGHT OF STRAND(LBS/FT)                           01400
C                                                                    01410
C    DECK REINFORCEMENT                                              01420
C     UR5=NOMINAL WEIGHT OF NO.5 BAR(LBS/FT)                         01430
C     UR6=NOMINAL WEIGHT OF NO.6 BAR(LBS/FT)                         01440
      FPU=270000.                                                    01450
      FPM=255000.                                                    01460
      SY=FPY/EPS                                                     01470
      SM=0.012                                                       01480
      SU=0.04                                                        01490
      ASTD=0.153                                                     01500
      UST=0.53                                                       01510
      UR5=1.043                                                      01520
      UR6=1.502                                                      01530
      WRITE(IW,180)                                                  01540
  180 FORMAT(1H0,5X,'MATERIAL PROPERTIES',3X,                        01550
     1           '(**INTERNALLY ASSIGNED VALUES)')                   01560
      WRITE(IW,190)
```


BEST DOCUMENT AVAILABLE

```
  190 FORMAT(1H0,7X,'CONCRETE ')
      WRITE(IW,200) FCP,FCPI,FCD
  200 FORMAT(1H0,10X,'SPECIFIED GIRDER CONCRETE STRENGTH(PSI)',      FCP =
     1 ,F7.1,/ 11X,'CONCRETE STRENGTH AT PRESTRESS TRANSFER(PSI)',  FCPI=
     2 ,F7.1,/ 11X,'SPECIFIED DECK CONCRETE STRENGTH(PSI)',         FCD =
     3 ,F7.1,'*')
      WRITE(IW,210) WC,WCD,WG,WD
  210 FORMAT(1H0,10X,'UNIT WEIGHT OF GIRDER CONCRETE(PCF)',          WC =
     1,F6.1,/     11X,'UNIT WEIGHT OF DECK CONCRETE(PCF)',          WCD=
     2,F6.1,/     11X,'UNIT WEIGHT OF GIRDER(PCF)',                 WG =
     3,F6.1,/     11X,'UNIT WEIGHT OF DECK(PCF)',                   WD =
     4,F6.1)
      WRITE(IW,220)
  220 FORMAT(1H0,7X,'STRAND')
      WRITE(IW,230) FPU,SU,FPM,SM,FPY,SY
  230 FORMAT(1H0,10X,'STRESS-STRAIN CURVE OF STRAND ',/ 42X,
     1       'STRESS(PSI)',6X,'STRAIN',/
     2  11X,'SPECIFIED ULTIMATE STRENGTH FPU=',F9.1,' *',2X,'SU=',F7.4,
     3  ' *',/ 11X,'INTERMEDIATE STRESS          FPM=',F9.1,' *',2X,'SM=',
     4 F7.4,' *',/11X,'SPECIFIED YIELD STRESS      FPY=',F9.1,3X,'SY=',
     5 F7.4)
      WRITE(IW,240)EPS,XLS
  240 FORMAT(1H0,10X,'MODULUS OF ELASTICITY OF STRAND(PSI)',   EPS= ,F11.1
     1,      /    11X,'TOTAL PRESTRESS LOSSES (PSI)',          XLS= ,F11.1
C
C  READ STIFNESS REDUCTION FACTOR
      READ(IR,250) SRF
  250 FORMAT(F12.0)
      IF(SRF.EQ.0.) SRF=0.55
      WRITE(IW,260) SRF
  260 FORMAT(1H0,5X,'GIRDER STIFFNESS REDUCTION FACTOR',10X,'SRF= ,F6.3)
C
C  READ RELATIVE UNIT COST INDEX
      READ(IR,270) RUCG,RUCD,RUS,RUR,RUE
  270 FORMAT(5F12.0)
      IF(RUCG.EQ.0.) RUCG=1.
      IF(RUCD.EQ.0.) RUCD=1.
      IF(RUS.EQ.0.) RUS=8.
      IF(RUR.EQ.0.) RUR=9.
      IF(RUE.EQ.0.) RUE=12.
      WRITE(IW,280) RUCG,RUCD,RUS,RUR,RUE
  280 FORMAT(1H0,5X,'RELATIVE COST INDEX(UNIT/LB) ',/
     1           11X,'GIRDER CONCRETE                          RUCG= ,F6.2,/
     2           11X,'DECK CONCRETE                            RUCD= ,F6.2,/
     3           11X,'STRAND                                   RUS = ,F6.2,/
     4           11X,'DECK REINFORCEMENT                       RUR = ,F6.2,/
     5           11X,'EPOXY COATED DECK REINFORCEMENT          RUE = ,F6.2)
C*****************************************************************************
C
C **STEP(2) MATERIAL PROPERTIES **
C  * INPUT *
C      FROM STEP(1)
C        FCP,FCPI,FCD,WC,WCD,WG,WD
C        FPU,FPY,EPS,XLS
C  * OUTPUT *
C   CONCRETE
C     FCCI= ALLOWABLE COMPRESSIVE STRESS OF GIRDER CONCRETE AT PRESTRESS
C          TRANSFER(PSI)
C     FCTI= ALLOWABLE TENSILE STRESS OF GIRDER CONCRETE AT PRESTRESS
C          TRANSFER(PSI)
C     FCC =ALLOWABLE COMPRESSIVE STRESS OF GIRDER CONCRETE AT SERVICE
C          LOAD(PSI)
C     FCT =ALLOWABLE TENSILE STRESS OF GIRDER CONCRETE AT SERVICE LOAD
C          (PSI)
C     FCR =MODULUS OF RUPTURE OF GIRDER CONCRETE(PSI)
C     EC  =MODULUS OF ELASTICITY OF GIRDER CONCRETE(PSI)
C     ECI=MODULUS OF ELASTICITY OF GIRDER CONCRETE AT PRESTRESS TRANSFER
C          (PSI)
C     ECD=MODULUS OF ELASTICITY OF DECK CONCRETE(PSI)
C     XNE=MODULAR RATIO (DECK CONCRETE TO GIRDER CONCRETE)
C   STRAND
C     FPS=ALLOWABLE STRESS OF STRAND AT SERVICE LOAD(PSI)
C     FSE=EFFECTIVE PRESTRESS AT SERVICE LOAD(PSI)
C
C  CALCULATION OF CONCRETE PROPERTIES
       FCCI=0.6*FCPI
       FCTI=0.0
       FCC=0.4*FCP
       FCT=6.0*SQRT(FCP)
       FCR= 7.5*SQRT(FCP)
```


BEST DOCUMENT AVAILABLE

```
      EC=33.0*WC**1.5*SQRT(FCP)                                          02370
      ECI=33.0*WC**1.5*SQRT(FCPI)                                        02380
      ECD=33.0*WCD**1.5*SQRT(FCD)                                        02390
      XNE=ECD/EC                                                         02400
C                                                                        02410
      WRITE(IW,290)                                                      02420
  290 FORMAT(1H0,4X, **(2) CALCULATED MATERIAL PROPERTIES ** )            02430
      WRITE(IW,300)                                                      02440
  300 FORMAT(1H0,5X,'CONCRETE )                                          02450
      WRITE(IW,310)                                                      02460
  310 FORMAT(1H0,7X, ALLOWABLE GIRDER CONCRETE STRESSES(PSI) )           02470
      WRITE(IW,320) FCCI,FCTI,FCC,FCT                                    02480
  320 FORMAT(1H0,9X, AT PRESTRESS TRANSFER ,// 12X,                      02490
     1  COMPRESSIVE STRESS     FCCI=',F7.1 ,/  12X,                     02500
     2  TENSILE STRESS         FCTI= ,F7.1 ,/  10X,                     02510
     3  AT SERVICE LOAD'                   ,/  13X,                     02520
     4  COMPRESSIVE STRESS     FCC = ,F7.1 ,/  13X,                     02530
     5  TENSILE STRESS         FCT =',F7.1)                             02540
      WRITE(IW,330) FCR                                                  02550
  330 FORMAT(1H0,7X,'MODULUS OF RUPTURE OF GIRDER CONCRETE(PSI)  FCR= ,  02560
     1F7.1)                                                              02570
      WRITE(IW,340)                                                      02580
  340 FORMAT(1H0,7X,'MODULUS OF ELASTICITY(PSI)                          02590
      WRITE(IW,350) EC,ECI,ECD                                           02600
  350 FORMAT(1H ,10X,'GIRDER CONCRETE                                EC = ,F10.1  02610
     1, /  11X,      GIRDER CONCRETE AT PRESTRESS TRANSFER  ECI= ,F10.1  02620
     2, /  11X,      'DECK CONCRETE                         ECD= ,F10.1)02630
      WRITE(IW,360) XNE                                                  02640
  360 FORMAT(1H0,7X,'MODULAR RATIO,DECK TO GIRDER    XNE=',F6.2)         02650
C                                                                        02660
C  CALCULATION OF STRAND PROPERTIES                                      02670
      FPS=0.80*FPY                                                       02680
      FSE=0.7*FPU-XLS                                                    02690
C                                                                        02700
      WRITE(IW,370)                                                      02710
  370 FORMAT(1H0,5X,'STRAND')                                            02720
      WRITE(IW,380) FPS,FSE                                              02730
  380 FORMAT(1H ,10X,'ALLOWABLE STRESS AT SERVICE LOAD(PSI)      FPS= ,  02740
     1F9.1,/  11X,  'EFFECTIVE PRESTRESS AT SERVICE LOAD(PSI)  FSE= ,    02750
     2F9.1)                                                              02760
      IF(0.5*FPU).GT.FSE) GO TO 390                                      02770
      IF(FSE.GT.FPS) GO TO 390                                           02780
      GO TO 410                                                          02790
  390 WRITE(IW,400) FSE                                                  02800
  400 FORMAT(1H0,10X, *** WARNING *** ,// 11X                            02810
     1 EFFECTIVE PRESTRESS IS OUT OF RANGE   FSE=',F12.1)                02820
      GO TO 1290                                                         02830
  410 CONTINUE                                                           02840
C**********************************************************************  02850
C                                                                        02860
C **STEP(3) THICKNESS AND REINFORCEMENT OF DECK **                       02870
C  * INPUT *                                                            02880
C       FROM STEP(1)                                                     02890
C         SS,B1                                                          02900
C  * OUTPUT *                                                           02910
C     SE=EFFECTIVE SPAN OF DECK(FT)                                      02920
C     TD=THICKNESS OF DECK(IN)                                           02930
C     BS=BAR SPACING(IN) OF NO.5 BAR OR NO.6 BAR                         02940
C          BS(1)=NO.5 , BS(2)=NO.6                                       02950
C                                                                        02960
C   SELECTION OF THICKNESS AND REINFORCEMENT FROM A LIST                 02970
      SE=SS-B1/12.0+10.0/12.0                                            02980
      BS(1)=0.                                                           02990
      BS(2)=0.                                                           03000
C     IBAR=INDICATOR OF SIZE OF BAR USED IN DECK                         03010
      TD=7.                                                              03020
      IBAR=1                                                             03030
      IF(SE.GT.3.) GO TO 420                                             03040
      BS(1)=10.                                                          03050
  420 IF(SE.GT.4.) GO TO 430                                             03060
      BS(1)=8.5                                                          03070
      GO TO 510                                                          03080
  430 IF(SE.GT.5.) GO TO 440                                             03090
      BS(1)=7.5                                                          03100
      GO TO 510                                                          03110
  440 IF(SE.GT.6.) GO TO 450                                             03120
      BS(1)=6.5                                                          03130
      GO TO 510                                                          03140
  450 BS(2)=8.                                                           03150
      IBAR=2                                                             03160
```


BEST DOCUMENT AVAILABLE

```
      IF(SE.GT.7.) GO TO 460                                                    03170
      GO TO 510                                                                 03180
  460 IF(SE.GT.8.) GO TO 470                                                    03190
      TD=7.5                                                                    03200
      GO TO 510                                                                 03210
  470 IF(SE.GT.9.) GO TO 480                                                    03220
      TD=8.                                                                     03230
      GO TO 510                                                                 03240
  480 IF(SE.GT.10.) GO TO 490                                                   03250
      TD=8.5                                                                    03260
      GO TO 510                                                                 03270
  490 WRITE(IW,500) SE                                                          03280
  500 FORMAT(1HO,10X,' *** WARNING ***',// 11X,                                 03290
     1     'EFFECTIVE DECK SPAN EXCEEDS 10 FT.   SE=',F12.2)                    03300
      GO TO 1290                                                                03310
  510 CONTINUE                                                                  03320
C                                                                               03330
      WRITE(IW,520)                                                             03340
  520 FORMAT(1HO,4X,'**(3) THICKNESS AND REINFORCEMENT OF DECK **')             03350
      WRITE(IW,530) SE,TD                                                       03360
  530 FORMAT(1HO,10X,'EFFECTIVE SPAN OF DECK(FT)     SE= ',F6.2,/,11X,          03370
     1           'THICKNESS OF DECK(IN)          TD= ',F6.2)                    03380
      WRITE(IW,540) ABAR(IBAR),BS(IBAR)                                         03390
  540 FORMAT(1H ,10X,' BAR SPACING(IN) OF  ',A4,'  BAR   BS= ',F6.2)            03400
C**********************************************************************       03410
C                                                                               03420
C **STEP(4) SECTIONAL PROPERTIES OF GIRDER **                                   03430
C  * INPUT *                                                                    03440
C       FROM STEP(1)                                                            03450
C         SL,GS,B1-B4,D1-D6                                                     03460
C       FROM STEP(2)                                                            03470
C         XNE                                                                   03480
C       FROM STEP(3)                                                            03490
C         TD                                                                    03500
C  * OUTPUT *                                                                   03510
C     AG=AREA OF NONCOMPOSITE SECTION(IN2)                                      03520
C     AC=AREA OF COMPOSITE SECTION(IN2)                                         03530
C     BE=EFFECTIVE TOP FLANGE(DECK) WIDTH(IN) -COMPOSITE SECTION-               03540
C     YT=DISTANCE FROM CENTROID TO TOP FIBER(IN) -NONCOMPOSITE SECTION-         03550
C     YB=DISTANCE FROM CENTROID TO BOTTOM FIBER(IN)-NONCOMPOSITE SECTION-       03560
C     YTC=YT FOR COMPOSITE SECTION(IN)                                          03570
C     YBC=YB FOR COMPOSITE SECTION(IN)                                          03580
C     AIG=MOMENT OF INERTIA OF GIRDER SECTION(IN4) -NONCOMPOSITE SECTION-       03590
C     AICC=AIG FOR COMPOSITE SECTION(IN4)                                       03600
C     ST=SECTION MODULUS FOR TOP FIBER(IN3)-NONCOMPOSITE SECTION-               03610
C     SB=SECTION MODULUS FOR BOTTOM FIBER(IN3) -NONCOMPOSITE SECTION-           03620
C     STC=ST FOR COMPOSITE SECTION(IN3)                                         03630
C     SBC=SB FOR COMPOSITE SECTION(IN3)                                         03640
C                                                                               03650
C   EFFECTIVE TOP FLANGE WIDTH                                                  03660
      X(1)=SL*12./4.                                                            03670
      X(2)=GS*12.                                                               03680
      X(3)=TD*12.*2                                                             03690
      BE=10000.                                                                 03700
      DO 550 I=1,3                                                              03710
      IF(BE.GT.X(I)) BE=X(I)                                                    03720
  550 CONTINUE                                                                  03730
C                                                                               03740
C   NONCOMPOSITE SECTION                                                        03750
C     A(7)=AREA OF EACH ELEMENT OF SECTION                                      03760
      A(1)=B1*D2                                                                03770
      A(2)=(2.*B4+B3)*D3                                                        03780
      A(3)=(B1-2.*B4-B2)*D3/2.                                                  03790
      A(4)=2.*B4*D4/2.                                                          03800
      A(5)=B2*(D1-D2-D3-D4)                                                     03810
      A(6)=(B2-B3)*D5/2.                                                        03820
      A(7)=B3*D6                                                                03830
C     Y(7)=DISTANCE FROM BOTTOM FIBER TO CENTROID OF EACH ELEMENT               03840
      Y(1)=D1-D2/2.                                                             03850
      Y(2)=D1-D2-D3/2.                                                          03860
      Y(3)=D1-D2-D3/3.                                                          03870
      Y(4)=D1-D2-D3-D4/3.                                                       03880
      Y(5)=(D1-D2-D3-D4-D5/2.+D6                                                03890
      Y(6)=D6/2.+D6                                                             03900
      Y(7)=D6/2.                                                                03910
C     AJ(7)=MOMENT OF INERTIA OF EACH ELEMENT                                   03920
      AJ(1)=B1*D2**3/12.                                                        03930
      AJ(2)=(2.*B4+B3)*D3**3/12.                                                03940
      AJ(3)=(B1-2.*B4-B2)*D3**3/36.                                             03950
      AJ(4)=2.*B4*D4**3/36.                                                     03960
```


BEST DOCUMENT AVAILABLE

```
      XJ(5)=B3*(D1-D2-D3-D6)**3/12.                                          03970
      XJ(6)=(B2-B3)*D5**3/36.                                                03980
      XJ(7)=B2*D6**3/12.                                                     03990
      AG=0.                                                                  04000
      DO 560 I=1,7                                                           04010
  560 AG=AG+A(I)                                                             04020
      TJ=0.                                                                  04030
      DO 570 I=1,7                                                           04040
  570 TJ=TJ+XJ(I)                                                            04050
      YBB=0.                                                                 04060
      DO 580 I=1,7                                                           04070
  580 YBB=YBB+A(I)*Y(I)                                                      04080
      YB=YBB/AG                                                              04090
      YT=D1-YB                                                               04100
      XIGG=0.                                                                04110
      DO 590 I=1,7                                                           04120
  590 XIGG=XIGG+A(I)*(Y(I)-YB)**2                                            04130
      XIG=TJ+XIGG                                                            04140
      ST=XIG/YT                                                              04150
      SB=XIG/YB                                                              04160
C                                                                            04170
C   COMPOSITE SECTION                                                        04180
      A(1)=XNE*BE*TD                                                         04190
      A(2)=AG                                                                04200
      Y(1)=D1+TD/2.                                                          04210
      Y(2)=YB                                                                04220
      XJ(1)=XNE*BE*TD**3/12.                                                 04230
      XJ(2)=XIG                                                              04240
      AC=A(1)+A(2)                                                           04250
      YBC=(A(1)*Y(1)+A(2)*Y(2))/AC                                           04260
      YTC=D1-YBC                                                             04270
      XIGC=XJ(1)+XJ(2)+A(1)*(Y(1)-YBC)**2+A(2)*(Y(2)-YBC)**2                 04280
      STC=XIGC/YTC                                                           04290
      SBC=XIGC/YBC                                                           04300
C                                                                            04310
      WRITE(IW,600)                                                          04320
  600 FORMAT(1H0,4X,'**(4) SECTIONAL PROPERTIES OF GIRDER **')               04330
      WRITE(IW,610) BE,AG,AC                                                 04340
  610 FORMAT(1H0,10X,'EFFECTIVE TOP FLANGE(DECK) WIDTH(IN)  BE= ',F8.2,//    04350
     1   11X,          'AREA OF NONCOMPOSITE SECTION(IN2)     AG= ',F8.2,/   04360
     2   11X,          'AREA OF COMPOSITE SECTION(IN2)        AC= ',F8.2)    04370
      WRITE(IW,620) YT,YB,YTC,YBC                                            04380
  620 FORMAT(1H0,10X,'DISTANCE FROM CENTROID TO TOP FIBER(IN)      YT= ',     04390
     1F7.2,2X,'-NONCOMPOSITE SECTION-',                                      04400
     2     / 11X,     DISTANCE FROM CENTROID TO BOTTOM FIBER(IN)  YB= ',     04410
     3F7.2,2X, '-NONCOMPOSITE SECTION-',                                     04420
     4     / 11X,    'YT FOR COMPOSITE SECTION(IN)               YTC= ',    04430
     5F7.2,/ 11X,    'YB FOR COMPOSITE SECTION(IN)               YBC= ',    04440
     6F7.2)                                                                  04450
      WRITE(IW,630) XIG,XIGC                                                 04460
  630 FORMAT(1H0,10X,'MOMENT OF INERTIA OF NONCOMPOSITE SECTION(IN4)         04470
     1XIG= ',F12.1,/ 11X, 'MOMENT OF INERTIA OF COMPOSITE SECTION(IN4)       04480
     2   XIGC= ',F12.1)                                                      04490
      WRITE(IW,640) ST,SB,STC,SBC                                            04500
  640 FORMAT(1H0,10X,'SECTION MODULUS FOR TOP FIBER(IN3)      ST= ',F10.1,    04510
     1 2X, '-NONCOMPOSITE SECTION-',/                                        04520
     2           11X,'SECTION MODULUS FOR BOTTOM FIBER(IN3)  SB= ',F10.1,    04530
     3 2X,'-NONCOMPOSITE SECTION-',/                                         04540
     4           11X, 'ST FOR COMPOSITE SECTION(IN3)         STC= ',F10.1,   04550
     5         /,11X,'SB FOR COMPOSITE SECTION(IN3)          SBC= ',F10.1)   04560
C*************************************************************************** 04570
C                                                                            04580
C **STEP(5) DESIGN LOADS AND MOMENTS **                                      04590
C  * INPUT *                                                                 04600
C      FROM STEP(1)                                                          04610
C        SL,OS,WG,WD                                                         04620
C      FROM STEP(3)                                                          04630
C        TD                                                                  04640
C      FROM STEP(4)                                                          04650
C        AG                                                                  04660
C  * OUTPUT *                                                               04670
C     XMD=MOMENT DUE TO DECK PLUS GIRDER WEIGHT(FT-KIP)                      04680
C     XMDG=MOMENT DUE TO GIRDER WEIGHT(FT-KIP)                               04690
C     XML=MOMENT DUE TO LIVE LOAD(FT-KIP)                                    04700
C     XMU=FACTORED MOMENT(FT-KIP)                                            04710
C     XIP=IMPACT LOAD COEFFICIENT                                            04720
C     WUG=UNIFORMLY DISTRIBUTED LOAD DUE TO GIRDER WEIGHT(KIP/FT)            04730
C     WUD=UNIFORMLY DISTRIBUTED LOAD DUE TO DECK WEIGHT(KIP/FT)              04740
C                                                                            04750
C     DM(12)=HS 20-44 MOMENTS FOR 10FT.WIDE LANE (FT-K)                      04760
```


BEST DOCUMENT AVAILABLE

```
C     SLL(12)=SPANS CORRESPONDING TO MS 20-44 MOMENTS (FT)                    04770
C                                                                             04780
C   CALCULATION OF DESIGN LOADS AND MOMENTS                                   04790
      XIP=50./(SL+125.)                                                       04800
      IF(XIP.GT.0.3) XIP=0.3                                                  04810
      WUG=WG*AG/(12.**2)/1000.                                                04820
      WUD=WD*GS*TD/12./1000.                                                  04830
      XMDG=WUG*SL**2/8.                                                       04840
      XMD=XMDG+WUD*SL**2/8.                                                   04850
      IF(SL.GT.SLL(1)) GO TO 650                                              04860
      IF(SL.LT.SLL(1)) GO TO 660                                              04870
      XXM=DM(1)                                                               04880
      GO TO 680                                                               04890
  650 CONTINUE                                                                04900
      DO 660 I=2,12                                                           04910
      IF(SL.GT.SLL(I)) GO TO 660                                              04920
      XXM=(SL-SLL(I-1))/(SLL(I)-SLL(I-1))*(DM(I)-DM(I-1))+DM(I-1)             04930
      GO TO 680                                                               04940
  660 CONTINUE                                                                04950
      WRITE(IW,670) SL                                                        04960
  670 FORMAT(1HO,10X,'*** WARNING ***',// 11X,                                04970
     1   'GIRDER SPAN IS OUT OF RANGE   SL=',F12.2)                           04980
      GO TO 1290                                                              04990
  680 CONTINUE                                                                05000
      XML=GS/10.*XXM                                                          05010
      XMU=1.3*(XMD+1.67*XML*(1.+XIP))                                         05020
C                                                                             05030
      WRITE(IW,690)                                                           05040
  690 FORMAT(1HO,4X,'**(5) DESIGN LOADS AND MOMENTS **')                      05050
      WRITE(IW,700) XIP,WUG,WUD                                               05060
  700 FORMAT(1HO,10X,'IMPACT LOAD FACTOR',30X,'XIP=',F6.3,/ 11X,              05070
     1'UNIFORM LOAD DUE TO GIRDER WEIGHT(KIP/FT)', 7X,'WUG=',F7.3,/,11X,      05080
     2'UNIFORM LOAD DUE TO DECK WEIGHT(KIP/FT)   ', 7X,'WUD=',F7.3)           05090
      WRITE(IW,710) XMDG,XMD,XML,XMU                                          05100
  710 FORMAT(1HO,10X,'MOMENT DUE TO GIRDER WEIGHT(FT-KIP)            XMG      05110
     1G=',F8.2,/ 11X,'MOMENT DUE TO DECK PLUS GIRDER WEIGHT(FT-KIP)   XM     05120
     2D=',F8.2,/ 11X,'MOMENT DUE TO LIVE LOAD(FT-KIP)                 XML    05130
     3L=',F8.2,/ 11X,'FACTORED MOMENT(FT-KIP)                         XM     05140
     4U=',F8.2)                                                               05150
C*****************************************************************************05160
C                                                                             05170
C **STEP(6) REQUIRED NUMBER OF STRANDS **                                     05180
C                                                                             05190
C **SUBSTEP(6-A) ALLOWABLE STRESSES CHECK **                                  05200
C  * INPUT *                                                                  05210
C       FROM STEP(1)                                                          05220
C         FPU,B2,B3,D5,D6,ASTD,CTC,CSC,SHW                                    05230
C       FROM STEP(2)                                                          05240
C         FCCI,FCTI,FCC,FCT,FBE                                               05250
C       FROM STEP(4)                                                          05260
C         AG,ST,SB,STC,SBC,YB                                                 05270
C       FROM STEP(5)                                                          05280
C         XMD,XMDG,XML,XIP                                                    05290
C  * OUTPUT *                                                                05300
C    NS=NO. OF STRANDS REQUIRED                                               05310
C    ET=DISTANCE FROM CENTROID OF STRANDS TO CENTROID OF GIRDER SECTION        05320
C          -NONCOMPOSITE-(IN)                                                 05330
C    AS=TOTAL AREA OF STRANDS REQUIRED(IN2)                                   05340
C    FI=TOTAL INITIAL PRESTRESSING FORCE(KIP)                                 05350
C    FS=TOTAL PRESTRESSING FORCE AT SERVICE LOAD(KIP)                         05360
C    CE=DISTANCE FROM CENTROID OF STRANDS TO BOTTON FIBER(IN)                 05370
C    NR(I) =MAX. NO. OF STRANDS PLACED IN I-TH ROW (MAX.I=50)                 05380
C            THE FIRST ROW IS LOCATED NEXT TO THE BOTTOM SURFACE              05390
C                                                                             05400
C   STRAND ARRANGEMENT                                                        05410
      XA=(SHW-1.)*CTC/2.                                                      05420
      XB=B2/2.-CSC                                                            05430
      DO 720 I=1,50                                                           05440
  720 NR(I)=0                                                                 05450
      A1=-D5/(B2/2.-B3/2.)                                                    05460
      B=-A1/2.*B2**2-D6-CSC*SQRT((B2/2.-B3/2.)**2+D5**2)/(B2/2.-B3/2.)        05470
C     I=NO. OF ROWS                                                           05480
      I=0                                                                     05490
      YBM = SB/AG+YB                                                          05500
  730 I=I+1                                                                   05510
      YI=I                                                                    05520
      Y1=CTC*(YI-1.)+CSC                                                      05530
      IF(Y1.GT.YBM) GO TO 740                                                 05540
      IF(I.GE.50) GO TO 740                                                   05550
C     I=NO. OF COLUMNS                                                        05560
```


BEST DOCUMENT AVAILABLE

```
      J=0                                                                   05570
  740 J=J+1                                                                 05580
      X2=J-1                                                                05590
      X1=CTC*X2/2.                                                          05600
      IF(X1.LE.XA) GO TO 740                                                05610
      IF(Y1.GT.(A1*X1+B)) GO TO 750                                         05620
      IF(X1.GT.XB) GO TO 750                                                05630
      GO TO 740                                                             05640
  750 NR(I)=J-1                                                             05650
      GO TO 720                                                             05660
  760 CONTINUE                                                              05670
C                                                                           05680
      WRITE(IW,770)                                                         05690
  770 FORMAT(1H0, 4X, **(6) REQUIRED AMOUNT OF STRAND ** )                  05700
C                                                                           05710
      NS=0                                                                  05720
C*************************************************************************** 05730
C   ITERATION START (THE NO. OF STRANDS IS INCREASED ONE BY ONE)            05740
  720 CONTINUE                                                              05750
      NS=NS+1                                                               05760
      IF (NS.GT.100) GO TO 810                                              05770
      XNS=NS                                                                05780
      AC=ASTD*XNS                                                           05790
      A2=0.                                                                 05800
      AY=0.                                                                 05810
      I=0                                                                   05820
      NRT=0                                                                 05830
  790 I=I+1                                                                 05840
      IF(NR(I).EQ.0) GO TO 810                                              05850
      XI=I                                                                  05860
      XN=NS-NRT                                                             05870
      NRT=NRT+NR(I)                                                         05880
      IF(NS.GT.NRT) GO TO 800                                               05890
      A2=A2+ASTD*XN                                                         05900
      AY=AY+XN*ASTD*(CSC+CTC*(XI-1.))                                       05910
      CE=AY/A2                                                              05920
      GO TO 840                                                             05930
  800 XNR=NR(I)                                                             05940
      A2=A2+XNR*ASTD                                                        05950
      AY=AY+XNR*ASTD*(CSC+CTC*(XI-1.))                                      05960
      GO TO 790                                                             05970
  810 WRITE(IW,820)                                                         05980
  820 FORMAT(1H0,10X,'*** WARNING *** ,// 11X,                              05990
     1   'CANNOT SATISFY STRESS AND STRENGTH REQUIREMENT')                  06000
      WRITE(IW,830) NS                                                      06010
  830 FORMAT(1H0,10X, NO. OF STRANDS= ,I4)                                  06020
      GO TO 1290                                                            06030
  840 CONTINUE                                                              06040
      ET=YB-CE                                                              06050
      FI=0.7*AS*FPU/1000.                                                   06060
      FS=FSE*AS/1000.                                                       06070
C                                                                           06080
C   CHECK INITIAL STRESSES                                                  06090
C       COMPRESSION=POSITIVE,  TENSION=NEGATIVE                             06100
C    TOP FIBER STRESS                                                       06110
      Z1=-FCTI/1000.                                                        06120
      Z2=FCCI/1000.                                                         06130
      SIT=FI/AC-FI*ET/ST+XMDC*12./ST                                        06140
      IF(Z1.GT.SIT) GO TO 780                                               06150
      IF(Z2.LT.SIT) GO TO 780                                               06160
C    BOTTOM FIBER STRESSES                                                  06170
      SIB=FI/AC+FI*ET/SB-XMDC*12./SB                                        06180
      IF(Z1.GT.SIB) GO TO 780                                               06190
      IF(Z2.LT.SIB) GO TO 780                                               06200
C                                                                           06210
C   CHECK SERVICE LOAD STRESSES                                             06220
C    TOP FIBER STRESSES                                                     06230
      Z1=-FCT/1000.                                                         06240
      Z2=FCC/1000.                                                          06250
      SST=FS/AC-FS*ET/ST+XMD*12./ST+XML*12./STC*(1.+XIF)                    06260
      IF(Z1.GT.SST) GO TO 780                                               06270
      IF(Z2.LT.SST) GO TO 780                                               06280
C    BOTTOM FIBER STRESSES                                                  06290
      SSB=FS/AC+FS*ET/SB-XMD*12./SB-XML*12./SBC*(1.+XIF)                    06300
      IF(Z1.GT.SSB) GO TO 780                                               06310
      IF(Z2.LT.SSB) GO TO 780                                               06320
C*************************************************************************** 06330
C                                                                           06340
C **SUBSTEP(6-B) ULTIMATE POSITIVE MOMENT **                                06350
C  * INPUT *                                                                06360
```


BEST DOCUMENT AVAILABLE

```
C       FROM STEP(1)                                                          06370
C         B1,B2,B3,B4,D1,D2,D3,D4,D5,D6,FPU,FCD,FCP,EPS,EPY,FPH,SY,SM,SU      06380
C       FROM STEP(2)                                                          06390
C         FSE,FCP                                                             06400
C       FROM STEP(3)                                                          06410
C         TD                                                                  06420
C       FROM STEP(4)                                                          06430
C         BE,AC,SB,SBC                                                        06440
C       FROM STEP(5)                                                          06450
C         XMU,XMD                                                             06460
C       FROM SUBSTEP(6-A)                                                     06470
C         AS,CE,FS,ET                                                         06480
C  * OUTPUT *                                                                 06490
C    XMCR=CRACKING MOMENT(FT-KIP)                                             06500
C    XMN=FLEXURAL DESIGN STRENGTH OF COMPOSITE SECTION(FT-KIP)                06510
C    AFSU=AVERAGE STRESS IN STRANDS AT ULTIMATE MOMENT(PSI)                   06520
C    DE=DISTANCE FROM EXTREME COMPRESSION FIBER(COMPOSITE SECTION) TO          06530
C       CENTROID OF THE STRANDS(IN)                                           06540
C    RA=STRAND RATIO                                                          06550
C    EPO=EFFECTIVE STRAIN OF THE STRAND DUE TO PRESTRESS ONLY AT SERVICE      06560
C       LOAD CONDITION                                                        06570
C    EP1=STRAIN OF THE STRANDS AT ULTIMATE MOMENT EXCLUDING EPO               06580
C    EP2=TOTAL STRAIN OF THE STRANDS AT ULTIMATE MOMENT                       06590
C    BE= EQUIVALENT WIDTH OF WEB(IN)                                          06600
C    BET1=RATIO OF THE DEPTH OF COMPRESSION ZONE TO THE DISTANCE FROM         06610
C         EXTREME COMPRESSION FIBER TO NUETRAL AXIS                           06620
C    CD=DISTANCE FROM EXTREME COMPRESSION FIBER TO NEUTRAL AXIS(IN)           06630
C    PIX=REINFORCEMENT INDEX                                                  06640
C    CD1=INCREMENT OF CD(IN)                                                  06650
C    FCE=EQUIVALENT SPECIFIED CONCRETE STRENGTH - WEIGHT AVERAGE OF           06660
C        GIRDER CONCRETE STRENGTH AND DECK CONCRETE STRENGTH(PSI)             06670
C    CBC=DISTANCE FROM EXTREME COMPRESSION FIBER TO THE CENTROID OF            06680
C        COMPRESSION STRESS BLOCK (IN)                                        06690
C    AD=DEPTH OF EQUIVALENT RECTANGULAR COMPRESSION STRESS BLOCK(IN)          06700
C    TF=TENSION FORCE IN STRANDS(LBS)                                         06710
C    CF=COMPRESSION FORCE IN COMPRESSION STRESS BLOCK(LBS)                    06720
C                                                                             06730
C  PRECALCULATED VARIABLES USED IN SUBSTEP(6-B)                               06740
      D1=BE*TD                                                                06750
      D2=TD*D2                                                                06760
      D3=TD*D2*D3                                                             06770
      D4=TD*D2*D3*D4                                                          06780
      D5=B1*D2                                                                06790
      D6=(B1+2.*B4+B3)*D3/2.                                                  06800
      G7=(2.*B3+2.*B4)*D4/2.                                                  06810
      G8=0.85*FCD*TD*BE                                                       06820
      G9=0.85*FCP*D2*B1                                                       06830
      G10=0.85*FCP*(B1+2.*B4+B3)*D3/2.                                        06840
      G11=0.85*FCP*(2.*B3+2.*B4)*D4/2.                                        06850
      G12=TD/2.                                                               06860
      G13=D2/2.+TD                                                            06870
      G14=D3*(B1+4.*B4+2.*B3)/3./(B1+2.*B4+B3)+TD+D2                          06880
      G15=D4*(2.*B4+B3+2.*B3)/3./(2.*B4+B3+B3)+TD+D2+D3                       06890
C                                                                             06900
C  ITERATION PROCESS                                                          06910
      DE=TD+D1-CE                                                             06920
      EPO=FSE/EPS                                                             06930
C   INITIAL VALUES OF CD AND CDI                                              06940
      CD=0.                                                                   06950
      CDI=1.                                                                  06960
C   IPI=POINTER FOR ITERATION NO(=0, THE FIRST ITERATION,=1, THE SECOND)      06970
      IPI=0                                                                   06980
C-------------------------------------------------------------------------    06990
C                                                                             07000
C    START OF LOOP  (ULTIMATE MOMENT)                                         07010
  850 CONTINUE                                                                07020
      CD=CD+CDI                                                               07030
C    CALCULATE AFSU AND TF                                                    07040
      EP1=0.003*(DE-CD)/CD                                                    07050
      EP2=EP1+EPO                                                             07060
      IF(EP2.GT.SY) GO TO 860                                                 07070
      AFSU=FPY*EP2/SY                                                         07080
      GO TO 890                                                               07090
  860 IF(EP2.GT.SM) GO TO 870                                                 07100
      AFSU=FPY+(EP2-SY)/(SM-SY)*(FPH-FPY)                                     07110
      GO TO 890                                                               07120
  870 IF(EP2.GT.SU) GO TO 880                                                 07130
      AFSU=FPH+(EP2-SM)/(SU-SM)*(FPU-FPH)                                     07140
      GO TO 890                                                               07150
  880 AFSU=FPU                                                                07160
```


BEST DOCUMENT AVAILABLE

```
  890 TF=AS*AFSU                                                        07170
C   CALCULATE FCE,BET1 AND AD                                           07180
C     ADT=TENTATIVE VALUE FOR AD(IN)                                    07190
C     ADD=DECK CONCRETE PORTION OF STRESS BLOCK AREA(IN)                07200
C     AGG=GIRDER CONCRETE PORTION OF STRESS BLOCK AREA(IN)              07210
      ADD=G1                                                            07220
      ADT=0.85*CD                                                       07230
      IF(ADT.GT.TD) GO TO 900                                           07240
      AGG=0.                                                            07250
      GO TO 940                                                         07260
  900 IF(ADT.GT.G2) GO TO 910                                           07270
      AGG=(ADT-TD)*B1                                                   07280
      GO TO 940                                                         07290
  910 IF(ADT.GT.G3) GO TO 920                                           07300
      Y1=G3-ADT                                                         07310
      Y3=D3                                                             07320
      X3=(B1-(2.*B4+B3))/2.                                             07330
      X1=X3*Y1/Y3                                                       07340
      Y2=D3-Y1                                                          07350
      AGG=G5+(B1+2.*X1+B3+2.*B4)*Y2/2.                                  07360
      GO TO 940                                                         07370
  920 IF(ADT.GT.G4) GO TO 930                                           07380
      X3=B4                                                             07390
      Y3=D4                                                             07400
      Y1=G4-ADT                                                         07410
      X1=X3*Y1/Y3                                                       07420
      Y2=D4-Y1                                                          07430
      AGG=G5+G6+(2.*B4+B3+2.*X1+B3)*Y2/2.                               07440
      GO TO 940                                                         07450
  930 AGG=G5+G6+G7+B3*(ADT-G4)                                          07460
  940 CONTINUE                                                          07470
      FCE=(ADD*FCD+AGG*FCP)/(ADD+AGG)                                   07480
      BET1=0.85-0.05*(FCE-4000.)/1000.                                  07490
      IF(BET1.LT.0.65) BET1=0.65                                        07500
      AD=BET1*CD                                                        07510
C   CALCULATE CF,CBC AND BF                                             07520
      IF(AD.GT.TD) GO TO 950                                            07530
      CF=0.85*FCD*AD*BE                                                 07540
      CBC=AD/2.                                                         07550
      BF=BE                                                             07560
      GO TO 990                                                         07570
  950 IF(AD.GT.G2) GO TO 960                                            07580
      CF1=G8                                                            07590
      CF2=0.85*FCP*(AD-TD)*B1                                           07600
      CB1=G12                                                           07610
      CB2=(AD-TD)/2.+TD                                                 07620
      CF=CF1+CF2                                                        07630
      CBC=(CF1*CB1+CF2*CB2)/CF                                          07640
      BF=B1                                                             07650
      GO TO 990                                                         07660
  960 IF(AD.GT.G3) GO TO 970                                            07670
      Y3=D3                                                             07680
      Y1=G3-AD                                                          07690
      X3=(B1-(2.*B4+B3))/2.                                             07700
      X1=X3*Y1/Y3                                                       07710
      Y2=D3-Y1                                                          07720
      XX=2.*X1+B3+2.*B4                                                 07730
      CF1=G8                                                            07740
      CF2=G9                                                            07750
      CF3=0.85*FCP*(B1+XX)*Y2/2.                                        07760
      CB1=G12                                                           07770
      CB2=G13                                                           07780
      CB3=Y2*(B1+2.*XX)/3./(B1+XX)+G2                                   07790
      CF=CF1+CF2+CF3                                                    07800
      CBC=(CF1*CB1+CF2*CB2+CF3*CB3)/CF                                  07810
      BF=XX                                                             07820
      GO TO 990                                                         07830
  970 IF(AD.GT.G4) GO TO 980                                            07840
      X3=B4                                                             07850
      Y3=D4                                                             07860
      Y1=G4-AD                                                          07870
      Y2=D4-Y1                                                          07880
      X1=X3*Y2/Y3                                                       07890
      XX=2.*X1+B3                                                       07900
      CF1=G8                                                            07910
      CF2=G9                                                            07920
      CF3=G10                                                           07930
      CF4=0.85*FCP*(2.*B4+B3+2.*X1+B3)*Y2/2.                            07940
      CB1=G12                                                           07950
      CB2=G13                                                           07960
```


BEST DOCUMENT AVAILABLE

```
      CB3=G14                                                           07670
      CB4=V2*(2.*B4-B3+2.*XX)/3./(2.*B4-B3+XX)**3                       07680
      CF=CF1+CF2+CF3+CF4                                                07690
      CBC=(CF1*CB1+CF2*CB2+CF3*CB3+CF4*CB4 )/CF                         08000
      BP=XX                                                             08010
      GO TO 990                                                         08020
  980 CONTINUE                                                          08030
      CF1=G8                                                            08040
      CF2=G9                                                            08050
      CF3=G10                                                           08060
      CF4=G11                                                           08070
      CF5=0.85*FCP*(AD-G4)*B3                                           08080
      CB1=G12                                                           08090
      CB2=G13                                                           08100
      CB3=G14                                                           08110
      CB4=G15                                                           08120
      CB5=(AD-G4)/2.+G4                                                 08130
      CF=CF1+CF2+CF3+CF4+CF5                                            08140
      CBC=(CF1*CB1+CF2*CB2+CF3*CB3+CF4*CB4+CF5*CB5 )/CF                 08150
      BP=B3                                                             08160
  990 CONTINUE                                                          08170
      IF(TF.GT.CF) GO TO 850                                            08180
C   CHECK WHETHER THE FIRST ITERATION OR THE SECOND                     08190
      IF(IPI.EQ.1) GO TO 1000                                           08200
      IPI=1                                                             08210
      CD=CD-CDI                                                         08220
      CDI=0.1                                                           08230
      GO TO 850                                                         08240
C                                                                       08250
C   END OF LOOP (ULTIMATE MOMENT)                                       08260
C                                                                       08270
C-----------------------------------------------------------------------08280
 1000 CONTINUE                                                          08290
C   AFTER THE SECOND ITERATION                                          08300
      XMNS=(CF+TF)*2.*(DE-CBC)/12./1000.                                08310
      XMN = .9*XMNS                                                     08320
      IF(XMN.LT.XMU) GO TO 780                                          08330
C    CALCULATE CRACKING MOMENT                                          08340
      XMCR=SBC/12.*(FS/AG+FS*ET*YB-XMD*12./SB*FCR/1000.)                08350
      IF(XMNS.LT.1.2*XMCR) GO TO 780                                    08360
C                                                                       08370
C   END OF ITERATION (THE NO. OF STRANDS)                               08380
C                                                                       08390
C-----------------------------------------------------------------------08400
C   CHECK MAX. REINFORCEMENT INDEX                                      08410
C    CALCULATE RIX                                                      08420
      IF(AS.GT.TD) GO TO 1010                                           08430
      FCE=FCD                                                           08440
      PA=AS/BP/DE                                                       08450
      GO TO 1020                                                        08460
 1010 CONTINUE                                                          08470
      PA=AD*0.85*FCE/AFSU/DE                                            08480
 1020 RIX=PA*AFSU/FCE                                                   08490
      IF(RIX.LE.0.3) GO TO 1040                                         08500
      WRITE(IW,1030) RIX                                                08510
 1030 FORMAT(1H0,10X, *** WARNING *** ,// 11X,                          08520
     1  REINFORCEMENT INDEX EXCEEDS 0.3   RIX= ,F6.3)                  08530
                                                                        08540
      GO TO 1290                                                        08550
 1040 CONTINUE                                                          08560
C                                                                       08570
      WRITE(IW,1050) NS                                                 08580
 1050 FORMAT(1H0,10X,'NO.OF STRANDS REQUIRED    NS= ,I3)               08590
      WRITE(IW,1060)                                                    08600
 1060 FORMAT(1H0,12X, ROW ,10X, NO.OF STRANDS PER ROW ,/)               08610
      NRR=0                                                             08620
C                                                                       08630
      DO 1100 I=1,50                                                    08640
      NRT=NRR+NR(I)                                                     08650
      IF(NS.GT.NRT) GO TO 1080                                          08660
      NNN=NS-NRR                                                        08670
      WRITE(IW,1070) I,NNN                                              08680
 1070 FORMAT(1H ,12X,I3,17X,I3)                                         08690
      GO TO 1110                                                        08700
 1080 WRITE(IW,1090) I,NR(I)                                            08710
 1090 FORMAT(1H ,12X,I3,17X,I3)                                         08720
      NRR=NRT                                                           08730
 1100 CONTINUE                                                          08740
C                                                                       08750
 1110 CONTINUE                                                          08760
```


BEST DOCUMENT AVAILABLE

```
      WRITE(IW,1120) AS                                                 08770
 1120 FORMAT(1H0,10X,'TOTAL AREA OF STRANDS REQUIRED(IN2)  AS= ',F9.2)  08780
      SIT = SIT*1000.                                                   08790
      SIB = SIB*1000.                                                   08800
      SST = SST*1000.                                                   08810
      SSB = SSB*1000.                                                   08820
      WRITE(IW,1130) FI,SIT,SIB,FS,SST,SSB                              08830
 1130 FORMAT(1H0,10X,' INITIAL PRESTRESSING FORCE(KIP)          FI= ',F8.1 08840
     1 ,/ 12X,'          TOP FIBER STRESS(PSI)      SIT= ',F9.1        08850
     2 ,/ 12X,'          BOTTOM FIBER STRESS(PSI    SIB= ',F9.1        08860
     3 ,/ 11X,'          PRESTRESSING FORCE AT SERVICE LOAD(KIP)  FS= ',F8.1 08870
     4 ,/ 12X,'          TOP FIBER STRESS(PSI)      SST= ',F9.1        08880
     5 ,/ 12X,'          BOTTOM FIBER STRESS(PSI)   SSB= ',F9.1)       08890
      WRITE(IW,1140) EPO,EPS                                            08900
 1140 FORMAT(1H0,10X,' STRAINS AT CENTROID OF STRANDS ,/ 12X,           08910
     1 'STRAIN DUE TO PRESTRESS ONLY AT SERVICE LOAD   EPO= ',F8.5,  12X 08920
     2,'TOTAL STRAIN AT ULTIMATE MOMENT                EPS= ',F8.5)    08930
      WRITE(IW,1150)                                                    08940
 1150 FORMAT(1H0,10X,'GEOMETRIC PARAMETERS OF GIRDER SECTION')          08950
      WRITE(IW,1160) ET,CE                                              08960
 1160 FORMAT(1H0,11X,' DISTANCE FROM CENTROID OF STRANDS TO CENTROID OF C 08970
     1ONCRETE SECTION=NONCOMPOSITE-(IN)   ET= ',F7.2,/ 12X,             08980
     2 DISTANCE FROM CENTROID OF STRANDS TO BOTTOM FIBER(IN) ,31X, CE= ' 08990
     3F7.2)                                                             09000
      WRITE(IW,1170) DE,CD,BET1,AD,CBC,BP                               09010
 1170 FORMAT(1H ,11X,' DISTANCE FROM TOP FIBER(COMPOSITE SECTION) TO CENT 09020
     1ROID OF STRANDS(IN) ,15X,'DE= ',F7.2,/ 12X,                       09030
     2 DISTANCE FROM TOP FIBER(COMPOSITE SECTION) TO NEUTRAL AXIS(IN) ,  09040
     322X, CD= ',F7.2,/ 12X, RATIO OF STRESS BLOCK DEPTH TO CD ,49X,    09050
     4 'BET1= ',F6.3,/ 12X,'COMPRESSION STRESS BLOCK DEPTH(IN) ,50X, AD= 09060
     5,F7.2, / 12X, DISTANCE FROM TOP FIBER(COMPOSITE SECT.)  TO CENTROI 09070
     6D OF STRESS BLOCK(IN) ,10X, CBC= ',F7.2, / 12X, EQUIVALENT WIDTH OF 09080
     7 WEB(COMPOSITE SECTION)(IN) ,38X,'BP=',F7.2)                      09090
      WRITE(IW,1180) AFSU,FCE,PA,RIX                                    09100
 1180 FORMAT(1H0,10X,' AVERAGE STRESS IN STRANDS AT ULTIMATE MOMENT(PSI)  09110
     1  AFSU= ',F9.1,/ 11X,'WEIGHT AVERAGED CONCRETE STRENGTH(PSI) ,15X, 09120
     2 FCE= ',F7.1, / 11X,  STRAND RATIO ,42X, PA= ',F5.3, / 11X, REINFORC 09130
     3EMENT INDEX ,34X, RIX= ',F6.3)                                    09140
      WRITE(IW,1190) TF,CF,XMN,XMCR                                     09150
 1190 FORMAT(1H0,10X, TENSILE FORCE IN STRANDS(LBS)              TF= ',F10.1 09160
     1,/ 11X,          COMPRESSIVE FORCE IN STRESS BLOCK(LBS)   CF= ',F10.1 09170
     2,/ 11X,          FLEXURAL DESIGN STRENGTH OF GIRDER(COMPOSITE SECTIO 09180
     3N,ET=',F5.2,')   XMN= ',F8.1,/ 11X, CRACKING MOMENT OF GIRDER(ET=',F5.2,') 09190
     4,2X, XMCR= ',F8.1)                                                09200
C*********************************************************************** 09210
C                                                                       09220
C **STEP 7) DEFLECTIONS AT MIDSPAN **                                   09230
C   SEE P.3/1.1(1 OF STATE OF ILLINOIS DESIGN MANUAL                    09240
C  * INPUT *                                                           09250
C       FROM STEP(1)                                                    09260
C         SRF,SL                                                        09270
C       FROM STEP(2)                                                    09280
C         EC,ECI                                                        09290
C       FROM STEP(4)                                                    09300
C         XIG                                                           09310
C       FROM STEP(5)                                                    09320
C         WUG,WUD                                                       09330
C       FROM SUBSTEP(6-A)                                               09340
C         FI,ET                                                         09350
C  *OUTPUT *                                                          <--09360
C    DUP=UPWARD DEFLECTION DUE TO PRESTRESSING(STRAIGHT STRANDS) INCH    09370
C    DDG=DOWNWARD DEFLECTION DUE TO GIRDER WEIGHT(IN)                   09380
C    CAMB=RESULTANT CAMBER AT ERECTION(IN)                              09390
C    DDD=DOWNWARD DEFLECTION DUE TO DECK WEIGHT(IN)                     09400
C                                                                       09410
C   CALCULATION OF DEFLECTIONS                                          09420
      DUP=0.125*FI*ET*SL**2*12**2*1000./SRF/ECI/XIG                     09430
      DDG=5.*WUG*SL**4*12**3*1000./SRF/384./ECI/XIG                     09440
      CAMB=DUP-DDG                                                      09450
      DDD=5.*WUD*SL**4*12**3*1000./384./EC/XIG                          09460
C                                                                       09470
      WRITE(IW,1200)                                                    09480
 1200 FORMAT(1HC,4X, **(7) DEFLECTIONS AT MIDSPAN ** )                  09490
      WRITE(IW,1210) DUP,DDG,CAMB,DDD                                   09500
 1210 FORMAT(1HC,10X, UPWARD DEFLECTION DUE TO PRESTRESSING FORCE(STRAIG 09510
     1HT STRANDS)(IN)    DUP= ,F7.2,/11X, DOWNWARD DEFLECTION DUE TO SIE 09520
     2DER WEIGHT(IN) ,25X, DDG= ,F7.3,/11X, RESULTANT CAMBER AT ERECTION 09530
     3(IN) ,30X, CAMB=',F7.3,/11X, DOWNWARD DEFLECTION DUE TO DECK WEIGH 09540
     4T(IN) ,27X, DDD= ,F7.3)                                           09550
C*********************************************************************** 09560
```


BEST DOCUMENT AVAILABLE

```
C                                                                       00070
C  **STEP(5) COST PER UNIT SURFACE AREA OF BRIDGE **                    00080
C   * INPUT *                                                           00090
C       FROM STEP(1)                                                    00100
C         SL,GS,WC,WCD,RUCG,RUCD,RUS,RUR,RUE,UST,UR5,UR6                00110
C       FROM STEP(3)                                                    00120
C         TD,BS                                                         00130
C       FROM STEP(4)                                                    00140
C         AG                                                            00150
C       FROM SUBSTEP(6-A)                                               00160
C         NS                                                            00170
C    *OUTPUT *                                                          00180
C      TWS=TOTAL WEIGHT OF STRANDS PER GIRDER(LBS)                      00190
C      TWR=TOTAL WEIGHT OF DECK REINFORCEMENT PER GIRDER(LBS)           00200
C      TWCG=TOTAL WEIGHT OF GIRDER CONCRETE PER GIRDER(LBS)             00210
C      TWCD=TOTAL WEIGHT OF DECK CONCRETE PER GIRDER(LBS)               00220
C      WUS=STRAND WEIGHT PER UNIT SURFACE AREA(LBS/FT2)                 00230
C      WUR=DECK REINFORCEMENT WEIGHT PER UNIT SURFACE AREA(LBS/FT2)     00240
C      WUCG=GIRDER CONCRETE WEIGHT PER UNIT SURFACE AREA(LBS/FT2)       00250
C      WUCD=DECK CONCRETE WEIGHT PER UNIT SURFACE AREA(LBS/FT2)         00260
C      CUS=COST OF STRAND PER UNIT SURFACE AREA(UNIT/FT2                00270
C      CUR=COST OF DECK REINFORCEMENT PER UNIT SURFACE AREA(UNIT FT2     00280
C      CUCG=COST OF GIRDER CONCRETE PER UNIT SURFACE AREA(UNIT FT2       00290
C      CUCD=COST OF DECK CONCRETE PER UNIT SURFACE AREA(UNIT FT2         00300
C      TUT=TOTAL COST INDEX PER UNIT SURFACE AREA BASED ON RELATIVE      00310
C          UNIT COSTS(UNIT/FT2)                                         00320
C                                                                       00330
C    COST CALCULATION                                                   00340
       XNS=NS                                                           00350
       TWS=XNS*SL*UST                                                   00360
       IF(IBAR.EQ.2) GO TO 1220                                         00370
       TWR=SL*12.*GS*2.*UR5/BS(IBAR)                                    00380
       GO TO 1230                                                       00390
  1220 TWR=SL*12.*GS*2.*UR6/BS(IBAR)                                    00400
  1230 CONTINUE                                                         00410
       TWCG=AG*SL*WC/12.*2                                              00420
       TWCD=TD*GS*SL*WCD/12.                                            00430
       WUS=TWS/SL/GS                                                    00440
       WUR=TWR/SL/GS                                                    00450
       WUCG=TWCG/SL/GS                                                  00460
       WUCD=TWCD/SL/GS                                                  00470
       CUS=RUS*WUS                                                      00480
       CUR=(RUR+RUE)/2.*WUR                                             00490
       CUCG=RUCG*WUCG                                                   00500
       CUCD=RUCD*WUCD                                                   00510
       TUT=CUS+CUR+CUCG+CUCD                                            00520
C                                                                       00530
       WRITE(IW,1240)                                                   00540
  1240 FORMAT(1H0,4X,'**(5) COST INDEX PER UNIT SURFACE AREA OF BRIDGE **  00550
      1 )                                                               00560
       WRITE(IW,1250) TWS,TWR,TWCG,TWCD                                 00570
  1250 FORMAT(1H0,10X,'TOTAL WEIGHT OF EACH MATERIAL PER GIRDER(LBS)  .  00580
      1  // 13X,'STRAND                        TWS= ,F10.1              00590
      2    13X,'DECK REINFORCEMENT           TWR= ,F10.1              00600
      3  / 13X,'GIRDER CONCRETE              TWCG= ,F10.1             00610
      4  / 13X,'DECK CONCRETE                TWCD= ,F10.1)            00620
       WRITE(IW,1260) WUS,WUR,WUCG,WUCD                                 00630
  1260 FORMAT(1H0,10X,'WEIGHT OF EACH MATERIAL PER UNIT SURFACE AREA(LBS'  00640
      1/FT2) .                                                          00650
      2  // 13X,'STRAND                        WUS= ,F10.3,             00660
      3  / 13X,'DECK REINFORCEMENT           WUR= ,F10.3,             00670
      4  / 13X,'GIRDER CONCRETE              WUCG= ,F10.3             00680
      5  / 13X,'DECK CONCRETE                WUCD= ,F10.3)            00690
       WRITE(IW,1270) CUS,CUR,CUCG,CUCD                                 00700
  1270 FORMAT(1H0,10X,'COST INDEX OF EACH MATERIAL PER UNIT SURFACE AREA(  00710
      1UNIT/FT2) .                                                      00720
      2  // 13X,'STRAND                        CUS= ,F10.2,             00730
      3  / 13X,'DECK REINFORCEMENT           CUR= ,F10.2,             00740
      4  / 13X,'GIRDER CONCRETE              CUCG= ,F10.2,            00750
      5  / 13X,'DECK CONCRETE                CUCD= ,F10.2)            00760
       WRITE(IW,1280) TUT                                               00770
  1280 FORMAT(1H0,10X,'TOTAL COST INDEX PER UNIT SURFACE AREA BASED ON RE  00780
      1LATIVE UNIT COSTS(UNIT/FT2) .// 50X,'TUT= ,F10.2)                00790
  1290 READ(IR,30) (TITLE(J),J=1,20)                                    00800
       IF (TITLE(1).EQ.CONT) GO TO 10                                   00810
       STOP                                                             00820
       END                                                              00830
```


BEST DOCUMENT AVAILABLE

Sample Problems

Data input and information output for two sample problems is presented in the following pages. Example 1 is the design of an AASHTO Type VI girder, while Example 2 is for a Washington Series 14 girder. Both examples are for girders with a span of 130 ft (39.6 m) and spacing of 6.0 ft (1.83 m).

Data input on punched cards is reproduced in Table 10. These data were prepared according to "User's Input Instructions" discussed earlier in this appendix, and summarized in Table 9. In Example 1, default options, where available, were selected. For this reason cards 7 through 11 are blank cards. A sample of data output for both examples is given in the next pages. This output is self-explanatory.

TABLE 10 - SAMPLE OF DATA INPUT

Example	Data Punched on Cards						Card No.
1	[illegible]						[illegible]
2	[illegible]						[illegible]

BEST DOCUMENT AVAILABLE

Sample of Data Output for Example 1

```
**EXAMPLE PROBLEM 1                                                    DATE  : **
**AASHTO TYPE VI                                                       DATE  : **
**MARCH 11,1991                                                        DATE  : **

**(1) INPUT DATA **

GEOMETRIC PROPERTIES

     GIRDER SPAN LENGTH(FT)      SL=     130.00
     GIRDER SPACING(FT)          S=        9.00

     HORIZONTAL DIMENSIONS OF GIRDER CROSS SECTION
      B1=      42.00  B2=      28.00  B3=       8.30  B4=       4.30

     VERTICAL DIMENSIONS OF GIRDER CROSS SECTION
      D1=      72.00  D2=       9.00  D3=       1.75  D4=       4.00  D5=      11.13  D6=       8.

     CENTER TO CENTER SPACING OF STRANDS IN          IS=       2.
     CLEAR DISTANCE TO CENTER OF STRAND IN           DS=       2.
     NUMBER OF STRANDS WITHIN WEB WIDTH              NWEB=     4.

MATERIAL PROPERTIES    **INTERNALLY ASSIGNED VALUES

  CONCRETE

     SPECIFIED GIRDER CONCRETE STRENGTH(PSI)         FCB = 6000.0
     CONCRETE STRENGTH AT PRESTRESS TRANSFER(PSI)    FCBI= 4500.0
     SPECIFIED DECK CONCRETE STRENGTH,PSI,           FCD = 4000.0

     UNIT WEIGHT OF GIRDER CONCRETE(PCF)             WC = 145.0
     UNIT WEIGHT OF DECK CONCRETE(PCF)               WCD= 145.0
     UNIT WEIGHT OF GIRDER,PCF)                      WG = 150.0
     UNIT WEIGHT OF DECK,PCF                         WD = 150.0

  STRAND

     STRESS-STRAIN CURVE OF STRAND
                                    STRESS(PSI)          STRAIN
     SPECIFIED ULTIMATE STRENGTH= FS,= 270000.0   E1= 0.040
     INTERMEDIATE STRESS          FS== 202500.0   S== 0.0128
     SPECIFIED YIELD STRESS       FY== 230000.0   E== 0.0082

     MODULUS OF ELASTICITY OF STRAND(PSI)    ES= 28000000.
     TOTAL PRESTRESS LOSSES (PSI)            SLS=    45000.

GIRDER STIFFNESS REDUCTION FACTOR            SRF= 0.950

RELATIVE COST INDEX UNIT/LB)
     GIRDER CONCRETE                  RUCG=  1.00
     DECK CONCRETE                    RUCD=  1.00
     STRAND                           RUS =  8.00
     DECK REINFORCEMENT               RUR =  5.00
     EPOXY COATED DECK REINFORCEMENT  RUE = 12.00

**(2) CALCULATED MATERIAL PROPERTIES **


CONCRETE

  ALLOWABLE GIRDER CONCRETE STRESSES(PSI)

    AT PRESTRESS TRANSFER
       COMPRESSIVE STRESS    FCCI= 2700.0
       TENSILE STRESS        FCTI=    0.0
    AT SERVICE LOAD
       COMPRESSIVE STRESS    FCC = 2400.0
       TENSILE STRESS        FCT = 464.7

  MODULUS OF RUPTURE OF GIRDER CONCRETE PSI)  FCR= 580.7
```


BEST DOCUMENT AVAILABLE

```
   MODULUS OF ELASTICITY(PSI
      GIRDER CONCRETE                          EI = 4.314e+6
      GIRDER CONCRETE AT PRESTRESS TRANSFER    EII= 3.871e+6
      DECK CONCRETE                            EID= 3.441e+6

   MODULAR RATIO(DECK) TO GIRDER     XNE= 0.816

 STRAND
      ALLOWABLE STRESS AT SERVICE LOAD(PSI)      FPE= 154000.0
      EFFECTIVE PRESTRESS AT SERVICE LOAD(PSI)   FSE= 144000.0

**(3) THICKNESS AND REINFORCEMENT OF DECK **

      EFFECTIVE SPAN OF DECK(FT)     SE=  5.33
      THICKNESS OF DECK(IN)          TD=  7.00
      BAR SPACING(IN) OF NO.5 BAR    BS=  8.50

**(4) SECTIONAL PROPERTIES OF GIRDER **

      EFFECTIVE TOP FLANGE(DECK) WIDTH(IN)   BE=   72.00

      AREA OF NONCOMPOSITE SECTION(IN2)      AG= 1085.00
      AREA OF COMPOSITE SECTION(IN2)         AC= 1496.91

      DISTANCE FROM CENTROID TO TOP FIBER(IN)      YT=  29.11  -NONCOMPOSITE SECTION-
      DISTANCE FROM CENTROID TO BOTTOM FIBER (IN)  YB=  21.89  -NONCOMPOSITE SECTION-
      YT FOR COMPOSITE SECTION(IN)                 YTC=  44.96
      YB FOR COMPOSITE SECTION(IN)                 YBC=  47.13

      MOMENT OF INERTIA OF NONCOMPOSITE SECTION(IN4)    AIG=    72210.3
      MOMENT OF INERTIA OF COMPOSITE SECTION(IN4)       AIGC=   119111.1

      SECTION MODULUS FOR TOP FIBER(IN3)     ST=   2480.6  -NONCOMPOSITE SECTION-
      SECTION MODULUS FOR BOTTOM FIBER(IN3)  SB=   3295.8  -NONCOMPOSITE SECTION-
      ST FOR COMPOSITE SECTION(IN3)          STC=  4702.2
      SB FOR COMPOSITE SECTION(IN3)          SBC=  2527.6

**(5) DESIGN LOADS AND MOMENTS **

      IMPACT LOAD FACTOR                                 XIP= 0.196
      UNIFORM LOAD DUE TO GIRDER WEIGHT(KIP/FT)          WUG=  1.130
      UNIFORM LOAD DUE TO DECK WEIGHT(KIP/FT)            WUD=  0.829

      MOMENT DUE TO GIRDER WEIGHT(FT-KIP)            XMDG= 238.50
      MOMENT DUE TO DECK PLUS GIRDER WEIGHT(FT-KIP)  XMD= 349.20
      MOMENT DUE TO LIVE LOAD(FT-KIP)                XML= 123.80
      FACTORED MOMENT(FT-KIP)                        XMU= 772.94

**(6) REQUIRED AMOUNT OF STRAND **


      NO.OF STRANDS REQUIRED    NS= 42

        ROW          NO.OF STRANDS PER ROW

          1                  13
          2                  13
          3                  13
          4                   3

      TOTAL AREA OF STRANDS REQUIRED(IN2)  AS=   6.426

      INITIAL PRESTRESSING FORCE(KIP)          PI=1214.514
       TOP FIBER STRESS(PSI)      SIT=   617.6
       BOTTOM FIBER STRESS(PSI)   SIB=  1631.7
      PRESTRESSING FORCE AT SERVICE LOAD(KIP)  PE= 929.343
       TOP FIBER STRESS(PSI)      SST=  1819.0
       BOTTOM FIBER STRESS(PSI)   SSB=  -458.2

      STRAINS AT CENTROID OF STRANDS

       STRAIN DUE TO PRESTRESS ONLY AT SERVICE LOAD   EPO= 0.00814
       TOTAL STRAIN AT ULTIMATE MOMENT                EPU= 3.02647
```


BEST DOCUMENT AVAILABLE

GEOMETRIC PARAMETERS OF GIRDER SECTION

DISTANCE FROM CENTROID OF STRANDS TO CENTROID OF GIRDER SECTION=NON-COMPOSITE= IN	ET=	[illegible]
DISTANCE FROM CENTROID OF STRANDS TO BOTTOM FIBER IN	EB=	[illegible]
DISTANCE FROM TOP FIBER-COMPOSITE SECTION= TO CENTROID OF STRANDS IN	ES=	[illegible]
DISTANCE FROM TOP FIBER-COMPOSITE SECTION= TO NEUTRAL AXIS IN	..=	[illegible]
RATIO OF STRESS BLOCK DEPTH TO CD	BETA=	[illegible]
COMPRESSION STRESS BLOCK DEPTH=IN=	A=	[illegible]
DISTANCE FROM TOP FIBER-COMPOSITE SECT.= TO CENTROID OF STRESS BLOCK=IN=	YBS=	[illegible]
EQUIVALENT WIDTH OF WEB-COMPOSITE SECTION=IN=	B=	[illegible]

AVERAGE STRESS IN STRANDS AT ULTIMATE MOMENT=PSI= APS= 2.4362.9
WEIGHT AVERAGED CONCRETE STRENGTH=PSI= FCE= 6XXX.X
STRAND RATIO RHO= 0.XXXX%
REINFORCEMENT INDEX OMEGA= X.XX

TENSILE FORCE IN STRANDS=LB= TS= 1.XXX.XXX.
COMPRESSIVE FORCE IN STRESS BLOCK=LBS= CS= 1.XXX.XXX.
FLEXURAL DESIGN STRENGTH OF GIRDER COMPOSITE SECTION PHI*M= PHIMN= X.XX.X
[RAD=IN] MOMENT OF GIRDER PHI*M= PHIMN= X.XX.X

** DEFLECTIONS AT MIDSPAN **

UPWARD DEFLECTION DUE TO PRESTRESSING FORCE=STRAIGHT STRANDS IN [illegible]
DOWNWARD DEFLECTION DUE TO GIRDER WEIGHT IN= [illegible]
RESULTANT CAMBER AT ERECTION=IN= [illegible]
DOWNWARD DEFLECTION DUE TO DECK WEIGHT IN= [illegible]

**(A) COST INDEX PER UNIT SURFACE AREA OF BRIDGE **

TOTAL WEIGHT OF EACH MATERIAL PER GIRDER(LBS)

STRAND	TWS=	2891.5
DECK REINFORCEMENT	TWR=	[illegible]
GIRDER CONCRETE	TWCG=	142050.9
DECK CONCRETE	TWCD=	[illegible]

WEIGHT OF EACH MATERIAL PER UNIT SURFACE AREA (LB/SQ FT)

STRAND	WS=	[illegible]
DECK REINFORCEMENT	WR=	[illegible]
GIRDER CONCRETE	WCG=	102.08
DECK CONCRETE	WCD=	14.99

COST INDEX OF EACH MATERIAL PER UNIT SURFACE AREA (DOLLARS)

STRAND	CWS=	[illegible]
DECK REINFORCEMENT	CWR=	[illegible]
GIRDER CONCRETE	CWCG=	102.04
DECK CONCRETE	CWCD=	14.99

TOTAL COST INDEX PER UNIT SURFACE AREA BASED ON RELATIVE UNIT COSTS (DOLLARS)

	C=	117.0

BEST DOCUMENT AVAILABLE

Sample of Data Output for Example 2

```
**EXAMPLE PROBLEM 2                                                    [UNIT  1 **
**PRESTRESSED BEAMS SERIES 14                                          [UNIT  4 **
**MARCH 11,1981                                                        [UNIT  2 **

**(1) INPUT DATA **

GEOMETRIC PROPERTIES

     GIRDER SPAN LENGTH(FT)          SL=     130.00
     GIRDER SPACING(FT)              GS=       9.00

     HORIZONTAL DIMENSIONS OF GIRDER CROSS SECTION
      B1=      42.00  B2=      24.00  B3=       7.00  B4=       2.50

     VERTICAL DIMENSIONS OF GIRDER CROSS SECTION
      D1=      71.00  D2=       2.67  D3=       2.33  D4=       2.50  D5=       3.67  D6=       4.67

     CENTER TO CENTER SPACING OF STRANDS IN          CTS=      2.33
     DISTANCE BETWEEN CENTER OF STRANDS IN           CTS=      4.67
     NUMBER OF STRANDS WITHIN WEB WIDTH=                       2.00

MATERIAL PROPERTIES    **INTERNALLY ASSIGNED VALUES:

  CONCRETE

     SPECIFIED GIRDER CONCRETE STRENGTH(PSI):          FCG = 6000.0
     CONCRETE STRENGTH AT PRESTRESS TRANSFER(PSI):     FCTI= 4500.0
     SPECIFIED DECK CONCRETE STRENGTH(PSI):            FCD = 4000.00

     UNIT WEIGHT OF GIRDER CONCRETE(PCF)               WC  = 149.2
     UNIT WEIGHT OF DECK CONCRETE(PCF)                 WCD= 149.0
     UNIT WEIGHT OF GIRDER(PCF)                        WI  = 150.1
     UNIT WEIGHT OF DECK(PCF)                          WD  = 150.0

  STRAND

     STRESS-STRAIN CURVE OF STRAND
                                          STRESS(PSI):        STRAIN
     SPECIFIED ULTIMATE STRENGTH FPU= 270000.0   EUP= 0.04000
     INTERMEDIATE STRESS         FPY= 250000.0   EPS= 0.01200
     SPECIFIED YIELD STRESS      FY = 230000.0   EY = 0.00852

     MODULUS OF ELASTICITY OF STRAND(PSI)   EP= 28000000.0
     TOTAL PRESTRESS LOSSES (PSI)           FSE=    45000.0



GIRDER STRENGTH REDUCTION FACTOR              SRF= 0.950

RELATIVE COST INDEX(UNIT/LB):
     GIRDER CONCRETE                    RUCG=  1.00
     DECK CONCRETE                      RUCD=  1.00
     STRAND                             RUS =  9.00
     DECK REINFORCEMENT                 RUR =  5.00
     EPOXY COATED DECK REINFORCEMENT    RUE = 12.00

**(2) CALCULATED MATERIAL PROPERTIES **

CONCRETE

  ALLOWABLE GIRDER CONCRETE STRESSES(PSI):

    AT PRESTRESS TRANSFER
       COMPRESSIVE STRESS     FCTI= 2700.0
       TENSILE STRESS         FCTT=    0.0
    AT SERVICE LOAD
       COMPRESSIVE STRESS     FCC = 2400.0
       TENSILE STRESS         FCT = 464.7

  MODULUS OF RUPTURE OF GIRDER CONCRETE(PSI   FCR= 600.0
```


BEST DOCUMENT AVAILABLE

```
MODULUS OF ELASTICITY OF
   GIRDER CONCRETE                          EC = ***.0(***)
   ASSUMED CONCRETE AT PRESTRESS TRANSFER   EC1= 3.4(10)3.(
   DECK CONCRETE                            EC2= 3644(3.9

 MODULAR RATIO(DECK TO GIRDER     AN= 0.816

STRAND
   ALLOWABLE STRESS AT SERVICE LOAD(PSI)      FS= 184(00.(
   EFFECTIVE PRESTRESS AT SERVICE LOAD PSI)   FSE= 144(00.(

** 1  THICKNESS AND REINFORCEMENT OF DECK **

   EFFECTIVE SPAN OF DECK(FT)     SE=  3.33
   THICKNESS OF DECK(IN)          TD=  7.00
   BAR SPACING(IN  OF NO.5 BAR    BS=  6.00

** 2  SECTIONAL PROPERTIES OF GIRDER **

   EFFECTIVE TOP FLANGE(DECK) WIDTH IN    BE=   72.(

   AREA OF NONCOMPOSITE SECTION(IN2)      AC=  574.13
   AREA OF COMPOSITE SECTION(IN2)         AC= 1(84.7

   DISTANCE FROM CENTROID TO TOP FIBER IN      YT=  19.13  =NONCOMPOSITE SECTIO=
   DISTANCE FROM CENTROID TO BOTTOM FIBER I    YB=  35.1(  =NONCOMPOSITE SECTIO=
    FOR COMPOSITE SECTION(IN)                  YTC=  20.61
   FOR COMPOSITE SECTION(IN)                   YBC=  52.33

   MOMENT OF INERTIA OF NONCOMPOSITE SECTION(IN4)    XIC=    57(311.6
   MOMENT OF INERTIA OF COMPOSITE SECTION(IN4        XICC=   9(1(6.2

   SECTION MODULUS FOR TOP FIBER(IN3      ST=   14555.6  =NONCOMPOSITE SECTIO=
   SECTION MODULUS FOR BOTTOM FIBER(IN3)  SB=   134(5.7  =NONCOMPOSITE SECTIO=
   ST FOR COMPOSITE SECTION(IN3)          STC=  41724.2
   SB FOR COMPOSITE SECTION(IN3)          SBC=  17043.9

** 3  DESIGN LOADS AND MOMENTS **

   IMPACT LOAD FACTOR                                  XIF= 0.1(0
   UNIFORM LOAD DUE TO GIRDER WEIGHT(LB/FT             WDC=  (.71(
   UNIFORM LOAD DUE TO DECK WEIGHT(LB/FT               WDC=  (.(00

   MOMENT DUE TO GIRDER WEIGHT FT-LB                  XMDG= 1401.5(
   MOMENT DUE TO DECK PLUS GIRDER WEIGHT(FT-LB)       XMD=  2(01.(2
   MOMENT DUE TO LIVE LOAD(FT-LB)                     XML=  1(27.6(
   FACTORED MOMENT(FT-LB)                             XMU=  (884.74

** 4  REQUIRED AMOUNT OF STRAND **

   NO.OF STRANDS REQUIRED    NS= 33

     ROW          NO.OF STRANDS PER ROW

      1                  11
      2                  11
      3                   6
      4                   3
      5                   2
      6                   1

   TOTAL AREA OF STRANDS REQUIRED(IN2)  AS=   (.04(

   INITIAL PRESTRESSING FORCE(LB)              PI= ((4.2(0
    TOP FIBER STRESS(PSI)        SIT=    414.3
    BOTTOM FIBER STRESS(PSI)     SIB=   24(2.(
   PRESTRESSING FORCE AT SERVICE LOAD(LB)      PS= 7(7.(((
    TOP FIBER STRESS(PSI)        SIT=   1(42.8
    BOTTOM FIBER STRESS(PSI)     SIB=   -4(8.7

   STRAINS AT CENTROID OF STRANDS

    STRAIN DUE TO PRESTRESS ONLY AT SERVICE LOAD   EPS= (.00814
    TOTAL STRAIN AT ULTIMATE MOMENT                EPS= (.(1(1(
```


BEST DOCUMENT AVAILABLE

GEOMETRIC PARAMETERS OF GIRDER SECTION

DISTANCE FROM CENTROID OF STRAND; TO CENTROID OF GIRDER SECTION(+)/COMPOSITE= IN= [illegible]
DISTANCE FROM CENTROID OF STRANDS TO BOTTOM FIBER(IN)= [illegible]
DISTANCE FROM TOP FIBER(COMPOSITE SECTION) TO CENTROID OF STRAND(S) IN= [illegible]
DISTANCE FROM TOP FIBER (COMPOSITE SECTION) TO NEUTRAL AXIS(IN= [illegible]
RATIO OF STRESS BLOCK DEPTH TO CC= [illegible]
COMPRESSIVE STRESS BLOCK DEPTH(IN)= [illegible]
DISTANCE FROM TOP FIBER(COMPOSITE SECT.) TO CENTROID OF STRESS BLOCK IN= [illegible]
EQUIVALENT WIDTH OF WEB(COMPOSITE SECTION)(IN)= [illegible]

AVERAGE STRESS IN STRANDS AT ULTIMATE MOMENT(PSI) AFSU= 228214.3
WEIGHT AVERAGED CONCRETE STRENGTH PSI. FIC= 4000.
STRAND RATIO RSR= [illegible]
REINFORCEMENT INDEX RIX= [illegible]

TENSILE FORCE IN STRANDS(LBS) TF= 1184[illegible].7
COMPRESSIVE FORCE IN STRESS BLOCK(LBS) CF= 1[illegible].0
FLEXURAL CRACKING STRENGTH OF GIRDER COMPOSITE SECTION(FT-LB) CMCR= [illegible]
CRACKING MOMENT OF GIRDER(FT-LB) CMCR= [illegible]

** 7 DEFLECTIONS AT MIDSPAN **

UPWARD DEFLECTION DUE TO PRESTRESSING FORCE(STRAIGHT STRANDS) IN= [illegible]
DOWNWARD DEFLECTION DUE TO GIRDER WEIGHT IN= [illegible]
RESULTANT CAMBER AT ERECTION(IN)= [illegible]

DOWNWARD DEFLECTION DUE TO DECK WEIGHT(IN)= [illegible]

**.8 COST INDEX PER UNIT SURFACE AREA OF BRIDGE **

TOTAL WEIGHT OF EACH MATERIAL PER GIRDER(LBS)

STRAND	TWS=	2270.7
DECK REINFORCEMENT	TWR=	[illegible]
GIRDER CONCRETE	TWCG=	98283.0
DECK CONCRETE	TWCD=	65975.0

WEIGHT OF EACH MATERIAL PER UNIT SURFACE AREA(LBS/FT2)

STRAND	WUS=	2.914
DECK REINFORCEMENT	WUR=	2.944
GIRDER CONCRETE	WUCG=	113.144
DECK CONCRETE	WUCD=	84.733

COST INDEX OF EACH MATERIAL PER UNIT SURFACE AREA(UNIT/FT2)

STRAND	CUS=	20.31
DECK REINFORCEMENT	CUR=	30.72
GIRDER CONCRETE	CUCG=	113.14
DECK CONCRETE	CUCD=	84.38

TOTAL COST INDEX PER UNIT SURFACE AREA BASED ON RELATIVE UNIT COST=(UNIT/FT2

TUT= [illegible]

BEST DOCUMENT AVAILABLE

APPENDIX F - COST CHARTS

This appendix contains cost charts for the following girders:

1. AASHTO Type IV
2. AASHTO Type V
3. AASHTO Type VI
4. Modified AASHTO Type IV
5. Modified AASHTO Type V
6. Modified AASHTO Type VI
7. Colorado G54
8. Colorado G68
9. Modified Colorado G68/6
10. Washington Series 80
11. Washington Series 100
12. Washington Series 120
13. Washington Series 14
14. Modified Washington 80/6
15. Modified Washington 100/6
16. Modified Washington 120/6
17. Modified Washington 14/6
18. Bulb-T BT48
19. Bulb-T BT60
20. Bulb-T BT72
21. Modified BT48/6
22. Modified BT60/6
23. Modified BT72/6

BEST DOCUMENT AVAILABLE



Figure 35 Cost Chart for AASHTO Type IV Girder

BEST DOCUMENT AVAILABLE



Figure 36 Cost Chart for AASHTO Type V Girder

BEST DOCUMENT AVAILABLE



Figure 37 Cost Chart for AASHTO Type VI Girder

BEST DOCUMENT AVAILABLE



Figure 38 Cost Chart for Modified Type IV Girder

BEST DOCUMENT AVAILABLE



Figure 39 Cost Chart for Modified Type V Girder

BEST DOCUMENT AVAILABLE



Figure 40 Cost Chart for Modified Type VI Girder

BEST DOCUMENT AVAILABLE



Figure 41 Cost Chart for Colorado G54 Girder

BEST DOCUMENT AVAILABLE



Figure 42 Cost Chart for Colorado G68 Girder

BEST DOCUMENT AVAILABLE



Figure 43 Cost Chart for Modified G68/6 Girder

BEST DOCUMENT AVAILABLE



Figure 44 Cost Chart for Washington Series 80

BEST DOCUMENT AVAILABLE



Figure 45 Cost Chart for Washington Series 100

BEST DOCUMENT AVAILABLE



Figure 46 Cost Chart for Washington Series 120

BEST DOCUMENT AVAILABLE



Figure 47 Cost Chart for Washington Series 14

BEST DOCUMENT AVAILABLE



Figure 48 Cost Chart for Modified Series 80/6

BEST DOCUMENT AVAILABLE



Figure 49 Cost Chart for Modified Series 100/6

BEST DOCUMENT AVAILABLE



Figure 50 Cost Chart for Modified Series 120/6

BEST DOCUMENT AVAILABLE



Figure 51 Cost Chart for Modified Series 14/6

BEST DOCUMENT AVAILABLE



Figure 52 Cost Chart for BT48

BEST DOCUMENT AVAILABLE



Figure 53 Cost Chart for BT60

BEST DOCUMENT AVAILABLE



Figure 54 Cost Chart for BT72

BEST DOCUMENT AVAILABLE



Figure 55 Cost Chart for Modified BT48/6

BEST DOCUMENT AVAILABLE



Figure 56 Cost Chart for Modified BT60/6

BEST DOCUMENT AVAILABLE



Figure 57 Cost Chart for Modified BT72/6

* U.S. GOVERNMENT PRINTING OFFICE: 1982 381-439/0022

BEST DOCUMENT AVAILABLE

FEDERALLY COORDINATED PROGRAM (FCP) OF HIGHWAY RESEARCH AND DEVELOPMENT

The Offices of Research and Development (R&D) of the Federal Highway Administration (FHWA) are responsible for a broad program of staff and contract research and development and a Federal-aid program, conducted by or through the State highway transportation agencies, that includes the Highway Planning and Research (HP&R) program and the National Cooperative Highway Research Program (NCHRP) managed by the Transportation Research Board. The FCP is a carefully selected group of projects that uses research and development resources to obtain timely solutions to urgent national highway engineering problems.*

The diagonal double stripe on the cover of this report represents a highway and is color-coded to identify the FCP category that the report falls under. A red stripe is used for category 1, dark blue for category 2, light blue for category 3, brown for category 4, gray for category 5, green for categories 6 and 7, and an orange stripe identifies category 0.

FCP Category Descriptions

1. Improved Highway Design and Operation for Safety

Safety R&D addresses problems associated with the responsibilities of the FHWA under the Highway Safety Act and includes investigation of appropriate design standards, roadside hardware, signing, and physical and scientific data for the formulation of improved safety regulations.

2. Reduction of Traffic Congestion, and Improved Operational Efficiency

Traffic R&D is concerned with increasing the operational efficiency of existing highways by advancing technology, by improving designs for existing as well as new facilities, and by balancing the demand-capacity relationship through traffic management techniques such as bus and carpool preferential treatment, motorist information, and rerouting of traffic.

3. Environmental Considerations in Highway Design, Location, Construction, and Operation

Environmental R&D is directed toward identifying and evaluating highway elements that affect the quality of the human environment. The goals are reduction of adverse highway and traffic impacts, and protection and enhancement of the environment.

4. Improved Materials Utilization and Durability

Materials R&D is concerned with expanding the knowledge and technology of materials properties, using available natural materials, improving structural foundation materials, recycling highway materials, converting industrial wastes into useful highway products, developing extender or substitute materials for those in short supply, and developing more rapid and reliable testing procedures. The goals are lower highway construction costs and extended maintenance-free operation.

5. Improved Design to Reduce Costs, Extend Life Expectancy, and Insure Structural Safety

Structural R&D is concerned with furthering the latest technological advances in structural and hydraulic designs, fabrication processes, and construction techniques to provide safe, efficient highways at reasonable costs.

6. Improved Technology for Highway Construction

This category is concerned with the research, development, and implementation of highway construction technology to increase productivity, reduce energy consumption, conserve dwindling resources, and reduce costs while improving the quality and methods of construction.

7. Improved Technology for Highway Maintenance

This category addresses problems in preserving the Nation's highways and includes activities in physical maintenance, traffic services, management, and equipment. The goal is to maximize operational efficiency and safety to the traveling public while conserving resources.

0. Other New Studies

This category, not included in the seven-volume official statement of the FCP, is concerned with HP&R and NCHRP studies not specifically related to FCP projects. These studies involve R&D support of other FHWA program office research.

* The complete seven-volume official statement of the FCP is available from the National Technical Information Service, Springfield, Va. 22161. Single copies of the introductory volume are available without charge from Program Analysis (HRD-2), Offices of Research and Development, Federal Highway Administration, Washington, D.C. 20590.

BEST DOCUMENT AVAILABLE